

TOWN OF MARATHON

# NEW PUBLIC WORKS FACILITY

2 PENN LAKE ROAD, MARATHON, ONTARIO

## DRAWING INDEX

CIVIL		STRUCTURAL		ELECTRICAL	
C1	SITE GRADING AND DRAINAGE PLAN	S-1	GENERAL NOTES	E001	ELECTRICAL LEGEND, DEMAND LOAD, SHORT CIRCUIT CALCULATION
C2	REMOVALS	S-2	FOUNDATION PLAN	E002	DEMOLITION AND RENOVATION SITE PLANS, ELECTRICAL SITE SERVICES, ELECTRICAL DETAILS
C3	SITE GRADING AND DRAINAGE PLAN	S-3	FOUNDATION SECTIONS & DETAILS	E003	ELECTRICAL SITE SERVICES, ELECTRICAL DETAILS, TRENCH DETAILS, POWER AND COMMUNICATIONS
C4	SITE GRADING AND DRAINAGE PLAN	S-4	LOWER ROOF FRAMING PLAN AND DETAILS	E004	SINGLE LINE DIAGRAM
C5	GENERAL NOTES	S-5	UPPER ROOF FRAMING PLAN AND DETAILS	E005	PARTIAL MAIN FLOOR PLAN, ENLARGED ELECTRICAL ROOM AND BOILER ROOM PLANS, ELECTRICAL REQUIREMENTS
		S-6	MEZZANINE FLOOR PLAN	E006	PANEL SCHEDULES
		S-7	SALT STORAGE SHELTER FOUNDATIONS, FUEL OIL TANK FOUNDATION	E100	MAIN FLOOR PLAN, MEZZANINE PLAN, LIGHTING REQUIREMENTS
				E200	MAIN FLOOR PLAN, MEZZANINE PLAN, POWER REQUIREMENTS
				E201	ROOF PLAN, ELECTRICAL REQUIREMENTS
				E300	MAIN FLOOR PLAN, MEZZANINE PLAN, LIFE SAFETY REQUIREMENTS, FIRE ALARM ZONING
				E301	MAIN FLOOR PLAN, MEZZANINE PLAN, FIRE ALARM ZONING, FIRE ALARM RISER DIAGRAM
				E400	ELECTRICAL SPECIFICATIONS
				E401	ELECTRICAL SPECIFICATIONS
				E402	ELECTRICAL SPECIFICATIONS
ARCHITECTURAL		MECHANICAL			
A0.01	GENERAL NOTES, INTERIOR FURRING SCHEDULE, INTERIOR PARTITION SCHEDULE, SYMBOLS, OBC DATA MATRIX	M100	MAIN FLOOR AND MEZZANINE SANITARY PLANS, AND GENERAL PLUMBING NOTES		
A0.02	FIRE SEPARATION PLAN	M101	DWV PIPING ISOMETRIC		
A0.03	FIRE RATED PARTITION DETAILS	M102	DWV PIPING ISOMETRIC AND DETAILS		
A1.01	SITE PLAN, SITE PLAN DETAILS	M103	MAIN FLOOR, MEZZANINE AND ROOF STORM DRAINAGE PLANS, LP GAS SERVICE SITE PLAN AND DETAILS		
A1.02	SITE PLAN - REMOVALS, SITE PLAN DETAILS	M200	MAIN FLOOR AND MEZZANINE DOMESTIC WATER PLANS		
A1.03	SITE PLAN ADDITIONAL PRICES	M300	MAIN FLOOR AND MEZZANINE HYDRONIC PLANS AND GENERAL HYDRONIC NOTES		
A2.01	MAIN PLAN	M301	MAIN FLOOR IN-SLAB RADIANT HEATING PLAN, IN-SLAB HEATING MANIFOLD LOOP SCHEDULE AND DETAILS		
A2.02	MEZZANINE PLAN	M302	BOILER ROOM PLANS AND SECTIONS		
A2.03	PLAN DETAILS	M303	BOILER PIPING AND DOMESTIC HOT WATER HEATING AND PIPING ISOMETRICS		
A2.04	ROOF PLAN, ROOF PLAN DETAILS	M400	MAIN FLOOR AND MEZZANINE HVAC PLANS AND GENERAL HVAC NOTES		
A3.01	MAIN FLOOR REFLECTED CEILING PLAN	M401	ROOF HVAC PLAN AND SECTION		
A3.02	MEZZANINE REFLECTED CEILING PLAN	M402	HVAC SECTIONS		
A4.01	BUILDING ELEVATIONS	M403	HVAC SECTIONS AND DETAILS		
A5.01	BUILDING SECTIONS	M500	MAIN FLOOR AND MEZZANINE COMPRESSED AIR PLANS		
A5.02	BUILDING SECTION, WALL SECTIONS	M501	COMPRESSED AIR SYSTEM DETAILS		
A5.03	WALL SECTIONS	M600	DETAILS		
A5.04	WALL SECTIONS	M701	EQUIPMENT LIST		
A5.05	WALL SECTION, SECTION DETAILS	M702	EQUIPMENT LIST, COMMISSIONING, BUILDING CONTROLS AND SEQUENCES OF OPERATION		
A5.06	STAIR DETAILS	M703	SCHEDULES		
A7.01	INTERIOR ELEVATIONS	M800	FUEL STORAGE DEMOLITION PLAN AND SCOPE OF WORK		
A7.02	CASEWORK DETAILS				

## CONSULTANTS:

CIVIL: TBT ENGINEERING LTD.  
1918 YONGE STREET  
Thunder Bay, Ontario, P7E 6T9  
T 807 624 5160 . F 807 624 5161

MECHANICAL: TBT ENGINEERING LTD.  
1918 YONGE STREET  
Thunder Bay, Ontario, P7E 6T9  
T 807 624 5160 . F 807 624 5161


ELECTRICAL: TBT ENGINEERING LTD.  
1918 YONGE STREET  
Thunder Bay, Ontario, P7E 6T9  
T 807 624 5160 . F 807 624 5161

STRUCTURAL: TBT ENGINEERING LTD.  
1918 YONGE STREET  
Thunder Bay, Ontario, P7E 6T9  
T 807 624 5160 . F 807 624 5161

CRITCHLEY HILL  
ARCHITECTURE


CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL.CA

2208  
NEW PUBLIC WORKS FACILITY  
ISSUED FOR PERMIT AND TENDER - JULY 28, 2022



SCALE: 1:300


	FINISHED GRADE ELEVATION
	EXISTING ELEVATION
	SLOPE DIRECTION
	REMOVAL
	NEW ASPHALT (DETAIL 'A')
	NEW ASPHALT (DETAIL 'B')
	NEW CONCRETE
	REINSTATE ASPHALT (DETAIL 'F')
	NEW GRAVEL SURFACE
	TOP OF CUT
	DITCH WITH FLOW DIRECTION
	CHAINLINK FENCE
	FIRE HYDRANT
	CATCH BASIN
	MANHOLE
	WATER VALVE
	0.2m CONTOUR (DESIGN)
	EXISTING STORM SEWER
	NEW STORM SEWER
	NEW CATCH BASIN
	NEW MANHOLE
	NEW FIRE HYDRANT
	WATER MAIN
	SANITARY SEWER
	NEW WATER VALVE AND BOX
	PROPERTY LINE
	ROOF DRAINS

[illegible]

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE



Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
MARATHON, ON


Drawing Title:  
SITE GRADING AND DRAINAGE PLAN

Drawn By: BS	Checked By: MP
Scale: AS NOTED	Project No: 22-098
Date Plotted:	
Date Revised: JULY 28, 2022	
Drawing No:	

Drawing No:


**C1**

NOT FOR CONSTRUCTION



## PLAN REMOVALS

LEGEND	
	FINISHED GRADE ELEVATION
	EXISTING ELEVATION
	SLOPE DIRECTION
	REMOVAL
	NEW ASPHALT (DETAIL 'A')
	NEW ASPHALT (DETAIL 'B')
	NEW CONCRETE
	REINSTATE ASPHALT (DETAIL 'F')
	NEW GRAVEL SURFACE
	TOP OF CUT
	DITCH WITH FLOW DIRECTION
	CHAINLINK FENCE
	FIRE HYDRANT
	CATCH BASIN
	MANHOLE
	WATER VALVE
	0.2m CONTOUR (DESIGN)
	EXISTING STORM SEWER
	NEW STORM SEWER
	NEW CATCH BASIN
	NEW MANHOLE
	NEW FIRE HYDRANT
	WATER MAIN
	SANITARY SEWER
	NEW WATER VALVE AND BOX
	PROPERTY LINE
	ROOF DRAINS




07/28/2022	ISSUED FOR TENDER & PERMIT	A

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE



Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**

Drawing Title:  
REMOVALS

Drawn By:  
BS

Checked By:  
MP

Scale:  
AS NOTED

Project No:  
22-098

Date Plotted:

---


Date Revised:  
JULY 28, 20

---


Drawing No:

## C2


NOT FOR CONSTRUCTION




SANITARY, STORM AND WATERMAIN TRENCH REINSTATEMENT  
N.T.S.




TYPICAL - FILL GREATER THAN 300mm  
N.T.S.




TYPICAL - FILL DEPTH LESS THAN 300mm  
N.T.S.




TYPICAL - CUT AREA  
N.T.S.



DETAIL 'A' - PAVEMENT STRUCTURE  
N.T.S.




DETAIL 'B' - SERVICE INSULATION  
N.T.S.



- NOTES:
1. REFER TO DRAWINGS FOR JOINT LAYOUT.
  2. SAWCUT WITHIN 48 HOURS OF POUR.
  3. NO TOOLED EDGES


DETAIL 'D' - TYPICAL CONCRETE SIDEWALK  
N.T.S.

- NOTES:
1. REFER TO DRAWINGS FOR JOINT LAYOUT.
  2. SAWCUT WITHIN 48 HOURS OF POUR.
  3. NO TOOLED EDGES




- NOTES:
- A. SLOPE OF RAMP SHALL NOT EXCEED 8%.
  - B. CROSS SLOPE OF RAMP SHALL NOT EXCEED 2% IN EITHER DIRECTION.
  - C. CROSS SLOPE OF FLARED SIDE OF RAMP SHALL NOT EXCEED 8%.
  - D. ENSURE FLUSH TRANSITION FROM ASPHALT TO RAMP.


DETAIL 'E' - RAMP  
N.T.S.



DETAIL 'C' SUBDRAIN  
N.T.S.




DETAIL 'F' - STORM PIPE EROSION PROTECTION  
N.T.S.



SECTION 1

NOT FOR CONSTRUCTION




Revision	Date	Issued For Tender & Permit
1	07/28/2022	ISSUED FOR TENDER & PERMIT

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE














Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
MARATHON, ON

Drawing Title:  
SITE GRADING AND DRAINAGE PLAN

Drawn By: BS	Checked By: MP
Scale: AS NOTED	Project No: 22-098
Date Plotted:	
Date Revised: JULY 28, 2022	
Drawing No:	

C3



NORTH

Project	Drawing Title	Scale	Date Plotted	Date Revised	Drawing No.
TOWN OF MARATHON NEW PUBLIC WORKS FACILITY MARATHON, ON	SITE GRADING AND DRAINAGE PLAN	AS NOTED			
Drawn By: BS	Checked By: MP	Project No: 22-098			
Date Revised: JULY 28, 2022					
Drawing No.: <b>C4</b>					

CRITCHLEY HILL ARCHITECTURE

TBT ENGINEERING CONSULTING GROUP

NOT FOR CONSTRUCTION

1. ALL DRAWING DIMENSIONS AND ELEVATIONS ARE METRES OR MILLIMETRES UNLESS OTHERWISE INDICATED
2. ALL CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE WITH THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATION FOR CONSTRUCTION PROJECTS AND THE LATEST EDITION OF THE ONTARIO BUILDING CODE. ALL OPSS AND OPSS REFERENCES ARE MUNICIPAL, AND LATEST VERSION CURRENT AT THE TIME OF THE TENDER DRAUGHTING.
3. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS, INVERTS AND ELEVATIONS ON GRADE PRIOR TO CONSTRUCTION, REPORT ANY DISCREPANCIES TO THE CONSULTANT.
4. CONTRACTOR TO OBTAIN AND PAY FOR ALL REQUIRED PERMITS.
5. THE CONTRACTOR SHALL PROVIDE QUALIFIED PERSONNEL TO LAYOUT AND ESTABLISH ALL GRADES AND GRADES NECESSARY FOR CONSTRUCTION. HORIZONTAL AND VERTICAL CONTROL SHALL BE ESTABLISHED USING THE INDICATED CONTROL POINTS.
6. PRIOR TO COMMENCING ANY EXCAVATION, THE EXCAVATOR MUST OBTAIN UTILITY LOCATES FOR THE ENTIRE WORK AREA.
7. CONTRACTOR TO MAINTAIN CLEAN WORK AREA AND PREVENT MATERIAL AND DEBRIS FROM BEING TRACKED ONTO ROADS.
8. CONTRACTOR TO MAKE GOOD ANY DAMAGE TO EXISTING FEATURES.
9. TRAFFIC RESTRICTIONS REQUIRED FOR PUBLIC THROUGHPATHS SHALL BE APPROVED BY THE ROAD AUTHORITY, PROVIDE AT LEAST SEVEN DAYS NOTICE PRIOR TO ANY TRAFFIC RESTRICTIONS. ALL TRAFFIC CONTROL IN ACCORDANCE TO ONTARIO TRAFFIC MANUAL BOOK 7.
10. DISPOSE AND MANAGE SURPLUS MATERIALS IN ACCORDANCE WITH OPSS 180 AND O. REG 406/19: ON-SITE AND EXCESS SOIL MANAGEMENT.

1. WHEN PUBLIC THOROUGHFARES ARE TO BE CLOSED, OR TRAFFIC RESTRICTED, NOTIFY THE ROAD AUTHORITY, THE FIRE DEPARTMENT, THE POLICE DEPARTMENT, THE TRANSIT AUTHORITY AND AMBULANCE SERVICE, GIVING AT LEAST SEVEN DAYS NOTICE OF THE CLOSING OR RESTRICTION.
2. CLOSE THOROUGHFARES OR RESTRICT NORMAL TRAFFIC FLOW ONLY WITH THE CONSENT OF THE AUTHORITIES HAVING JURISDICTION, AND IN ACCORDANCE WITH THEIR REQUIREMENTS.

1. PROVIDE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT SOIL EROSION AND DISCHARGE OF SOIL-BEARING WATER RUNOFF OR AIRBORNE DUST TO ADJACENT PROPERTIES AND WALKWAYS.
2. IMPLEMENTATION, INSPECTION, MAINTENANCE AND REMOVAL OF EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH DPS § 805. ALTERNATIVE MATERIALS OR METHODS ARE ACCEPTABLE PROVIDED THEY MEET INDUSTRY STANDARDS AND PROTECT THE ENVIRONMENT FROM THE IMPACTS OF EROSION AND SEDIMENTATION.
3. REPAIR, REPAIR, REPAIR, MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION UNTIL PERMANENT VEGETATION HAS BEEN ESTABLISHED.
4. REMOVE EROSION AND SEDIMENTATION CONTROLS AND RESTORE AND STABILIZE AREAS DISTURBED DURING REMOVAL.

1. INFRASTRUCTURE DESIGNATED FOR REMOVALS SUCH AS UNDERGROUND PIPES/UTILITIES, BUILDINGS, AND STORM INFRASTRUCTURE SHALL BE BACKFILLED WITH GRANULAR B TYPE I AND CAPPED WITH 150mm OF GRANULAR 'A'.
2. GRANULARS SHALL BE IN ACCORDANCE WITH OPSS 1010.
3. COMPACT EACH LAYER FULL WIDTH IN ACCORDANCE WITH OPSS 501. COMPACT GRANULAR MATERIAL TO 98% SPMD. GRANULAR MATERIAL SHALL BE PLACED IN MAXIMUM COMPACTED LIFT THICKNESS OF 300 MM.

1. SUPPLY AND INSTALL STORM SEWER PIPE AS SPECIFIED. ALL WORK MUST BE SUPERVISED BY A LICENSED PLUMBER.
2. ALL STORM SEWER MATERIAL AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE ONTARIO BUILDING CODE TYPE PSM POLY VINYL CHLORIDE (PVC) TO CSA-B182.2.
  1. STANDARD DIMENSIONAL RATIO (SDR): 35.
  2. LOCKED-IN GASKET AND INTEGRAL BELT SYSTEM.
  3. NOMINAL LENGTHS: 4 – 6 M.
3. CONTRACTOR TO SUBMIT SHOP DRAWINGS TO THE CONSULTANT FOR REVIEW.
4. GRANULAR MATERIALS SUPPLIED IN ACCORDANCE WITH OPSS 1010 TABLE 2. GRANULAR MATERIAL SHALL BE KEPT FREE FROM CLAY AND OTHER TYPES OF DELETERIOUS MATERIAL.
  1. EXCAVATE TO PROVIDE INVERT ELEVATIONS SHOWN.
5. BEDDING AND PIPE SURROUND MATERIAL SHALL BE GRANULAR B TYPE III WITH A MAXIMUM PARTICLE SIZE OF 26.5MM
6. MAXIMUM DRY DENSITY (MOD) SHALL BE DETERMINED USING LS-706 OR ASTM D698. GRANULAR MATERIALS SHALL BE COMPACTED TO A DENSITY OF 98% OF THE MOD.
8. CONTRACTOR SHALL SUPPLY AND CONSTRUCT MAINTENANCE HOLES AND CATCH BASINS WITH HEIGHTS THAT ACHIEVE FINISHED GRATES SPECIFIED. CATCH BASINS REQUIRING ADDITIONAL RISER SECTIONS SHALL BE DESIGNED WITH FROST STRAPS OR BE SUPPLIED AS SINGLE PRECAST UNITS. LOCATION AND ANGLE OF INLET AND OUTLET HOLE TO SUIT NOTED INVERTS. NEW CATCH BASINS TO BE INSTALLED WITH GRATES AS PER OPSD 403.010. EXISTING CATCH BASINS TO BE INSTALLED WITH GRATES AS PER OPSD 403.010.
9. ENSURE ALL CONNECTIONS TO CATCH BASINS ARE WATERTIGHT AND AS PER OPSS 407.
10. CONTRACTOR SHALL REMOVE AND REINSTATE FENCE ALONG PENN LAKE ROAD TO FACILITATE STORM SEWER INSTALLATION.
11. CONTRACTOR SHALL PAY FOR AND OBTAIN PLUMBING PERMITS FROM THE TOWN OF MARATHON BUILDING SERVICES DIVISION FOR INSTALLATION OF ON-SITE CATCH BASINS AND STORM SEWER WORKS.
12. CONTRACTOR SHALL CONTACT THE TOWN OF MARATHON FOR CONSULTATION AND SCHEDULE INSPECTIONS PRIOR TO BACKFILL OF STORM SEWER.

1. CORRUGATED STEEL PIPE (CSP) PRODUCTS SHALL BE ACCORDING TO CSA G401. COATING SHALL BE GALVANIZED. MINIMUM WALL THICKNESS 2.0 mm. CERTIFIED CORRUGATED STEEL PIPE SHALL BE MARKED ACCORDING TO CSA G401, ALONG WITH THE LOGO OF THE CERTIFICATION BODY AND NAME OF THE PIPE MANUFACTURER.
2. MANUFACTURER'S RECOMMENDATIONS FOR TRANSPORTING, UNLOADING, STORING, AND HANDLING OF PIPE, SHALL BE FOLLOWED.
3. GRANULAR BEDDING, EMBEDMENT SHALL BE GRANULAR A OR GRANULAR B WITH 100% PASSING THE 26.5MM SIEVE ACCORDING TO OPSS 1010. GRANULAR TO BE PLACED IN UNFROZEN CONDITION.
4. THE CONTRACTOR SHALL FIELD FIT CULVERT INVERTS TO REFLECT ON SITE CONDITIONS. THE CONTRACT ADMINISTRATOR SHALL APPROVE THE INSTALLATION PRIOR TO BACKFILLING.
5. DEWATER THE EXCAVATION, AS NECESSARY, TO ALLOW PLACEMENT OF CULVERT BEDDING IN DRY CONDITION. PLACE MINIMUM THICKNESS OF 150 mm OF GRANULAR A MATERIAL ON BOTTOM OF EXCAVATION AND COMPACT. SHAPE BEDDING TO FIT LOWER SEGMENT OF PIPE EXTERIOR SO THAT WIDTH OF AT LEAST 50% OF PIPE DIAMETER IS IN CLOSE CONTACT WITH BEDDING.
6. BEGIN PIPE PLACING AT DOWNSTREAM END. ENSURE BOTTOM OF PIPE IS IN CONTACT WITH SHARED BED. CONTINUE PLACING PIPE THROUGHOUT ITS LENGTH. LAY PIPE WITH OUTSIDE CIRCUMFERENTIAL LAPS FACING UPSTREAM AND LONGITUDINAL LAPS OR SEAMS AT SIDE OR QUARTER POINTS. DO NOT ALLOW WATER TO FLOW THROUGH PIPS DURING CONSTRUCTION EXCEPT AS PERMITTED BY CONTRACT ADMINISTRATOR.
7. CORRUGATED STEEL PIPE SECTIONS SHALL BE JOINED BY MEANS OF STEEL COUPLERS. THE COUPLERS SHALL BE INSTALLED TO LAP APPROXIMATELY EQUAL LENGTHS OF THE PIPE BEING CONNECTED SO THAT THE CORRUPTIONS OR PROJECTIONS OF THE COUPLER PROPERLY ENGAGE THE PIPE CORRUGATIONS, AS THE COUPLER IS BEING TIGHTENED, IT SHALL BE TAPPED WITH A MALLET TO TAKE UP THE SLACK. REPAIR SPOTS WHERE DAMAGE HAS OCCURRED TO GALVANIZED COATING BY APPLYING TWO COATS OF ZINC RICH PAINT.
8. PLACE AND COMPACT GRANULAR A EMBEDMENT AND COVER IN 150 mm LAYERS TO FULL WIDTH, ALTERNATE ON EACH SIDE OF CULVERT, SO AS NOT TO DISPLACE IT INTERNALLY OR VERTICALLY.
9. GRANULAR BACKFILL SHALL BE PLACED AND COMPACTED IN UNIFORM LAYERS NOT EXCEEDING 300 mm IN THICKNESS, LOOSE MEASUREMENT, FOR THE FULL WIDTH OF THE TRENCH
10. PROTECT INSTALLED CULVERT WITH MINIMUM 300 mm COVER OF COMPACTED FILL. BEFORE HEAVY EQUIPMENT IS PERMITTED TO CROSS.

1. SUPPLY AND INSTALL 150MM DIAMETER PVC SANITARY SEWER SERVICE TO EXTENTS SHOWN.
2. INVERT OF EXISTING SANITARY MAINTENANCE HOLE AT CONNECTION POINT IS APPROXIMATE.
3. CONFIRM INVERT AT EXISTING SANITARY MAINTENANCE HOLE PRIOR TO CONSTRUCTION.
4. CONTRACTOR SHALL SURVEY AND CONSTRUCT MAINTENANCE HOLES WITH HEIGHTS TO ACTIVE FINISH GRADES SPECIFIED. LOCATION AND ANGLE OF INLET AND OUTLET HOLE TO SUIT NOTED INVERTS.
5. CONNECTION TO EXISTING SANITARY SANITARY MAINTENANCE HOLE TO BE WATERTIGHT AND AS PER OPSS 407.
10. THE MINIMUM DEPTH OF COVER IS 2.5M. WHERE THIS DEPTH IS NOT ACHIEVED THE SANITARY SHALL BE INSULATED AS PER DETAIL 'B'.
1. TYPE PSM POLYVINYL CHLORIDE (PVC); TO CSA-B182.2.
  - STANDARD DIRECTIONAL RATIO (SDR): 28.
  - LOCKED-IN GASKET AND INTEGRAL BELL SYSTEM.
  - NOMINAL LENGTHS: 4 = 6 M.
12. PIPE BEDDING AND SURROUND GRANULAR B TO OPSS 1010 WITH MAXIMUM PARTICLE SIZE OF 26.5MM.
13. COMPACT EACH LAYER FULL WIDTH OF BED IN ACCORDANCE WITH OPSS 501. COMPACT GRANULAR MATERIAL TO 98% SDP.
14. TIE INS TO EXISTING SANITARY MAINTENANCE HOLE WILL BE COMPLETED BY THE CONTRACTOR AND SHALL BE COORDINATED WITH THE TOWN OF MARATHON.
15. CONTRACTOR SHALL REINSTATE ROADWAY GRANULAR, FENCE AND ASPHALT TO COMPLETE TIE IN WORK.

1. PIPE SHALL BE INSTALLED AS PER OPSS 441.
2. INSTALL THRUST BLOCKS NECESSARY IN ACCORDANCE WITH OPSS 441.
3. CONTRACTOR TO PERFORM CHLORINATION, PRESSURE TEST AND FLUSH NEW PIPING AS PER REQUIREMENTS OF OPSS 441.
4. CONNECTION TO EXISTING WATERMAIN TO BE APPROVED SADDLE OR TEE.
5. PIPE BEDDING AND SURROUND GRANULAR B TO OPSS 1010 WITH MAXIMUM PARTICLE SIZE OF 26.5MM.
6. COMPACT EACH LAYER FULL WIDTH OF BED IN ACCORDANCE WITH OPSS 501. COMPACT GRANULAR MATERIAL TO 98% SPMD.
7. TIE INS TO EXISTING WATERMAIN WILL BE COMPLETED BY THE CONTRACTOR AND SHALL BE COORDINATED WITH THE TOWN OF MARATHON.
8. MUELLER VALVE AND VALVE BOX APPROVED BY THE TOWN OF MARATHON AND CONSULTANT.
9. FIRE HYDRANT SHALL BE AS IN ACCORDANCE WITH AWWA C502 AND BE APPROVED BY THE TOWN OF MARATHON AND CONSULTANT.
10. THE MINIMUM DEPTH OF COVER IS 2.15M. WHERE THIS DEPTH IS NOT ACHIEVED THE WATER SERVICE SHALL BE INSTALLED AS PER DETAIL 'B'.
11. PVC PIPE: ANSI/AWWA C900 D18.8. FLEXIBLE ELASTOMERIC SEALS FOR BELL AND SPIGOT JOINTS SHALL BE ACCORDING TO ASTM D3139.
12. POLYVINYL CHLORIDE PRESSURE PIPE FITTINGS: INJECTION MOLDED POLYVINYL CHLORIDE, BLUE IN COLOUR AND ACCORDING TO AWWA C907 AND CSA B137.2
13. THAW/TRACER WIRE SHALL BE FOURTEEN (14) GAUGE TW SO COPPER LIGHT COATED PLASTIC COATED.
14. INSTALL THAW / TRACER WIRE ALONG ALL NON-METALLIC WATER DISTRIBUTION PIPING. SECURE WIRE TO PIPELINE WITH ELECTRICAL TAPE AT 3 METRE INTERVALS. CABLED WIRE TO HYDRANT BOOTS. TEST CONDUCTIVITY FOLLOWING BACKFILL OF TRENCHES.
15. ANCHORAGE AND THRUST BLOCKS: CONTRACTOR TO SUPPLY AND INSTALL CONCRETE THRUST BLOCKS AND M20 STAINLESS STEEL CLAMP, TIE RODS AND BOLTS OR APPROVED EQUIAL.

1. THE WORK SHALL INCLUDE EXCAVATING, HAULING, HANDLING, SHAPING, COMPACTING, STRIPPING AND TRIMMING OF EARTH MATERIAL AND THE MANAGEMENT OF EXCAVATED MATERIAL FOR NEW CONSTRUCTION AREAS.
2. 150mm STRIPPING DEPTH IN AREAS WHERE VEGETATION IS PRESENT.
3. CONTRACTOR SHALL MANAGE EXCESS MATERIAL IN ACCORDANCE WITH O. REG. 406/19: ON-SITE AND EXCESS SOIL MANAGEMENT
4. CONTRACTOR TO CO-ORDINATE WITH THE UTILITY AUTHORITIES HAVING JURISDICTION PRIOR TO EXCAVATION OPERATIONS WITHIN CLOSE PROXIMITY OF ANY UTILITY INFRASTRUCTURE & POLES
5. SAW CUT VERTICAL AT LATERAL REMOVAL LIMITS TO PRODUCE STRAIGHT CLEAN VERTICAL FACE.
6. STRIP TOPSOIL OVER AREAS TO BE COVERED BY GRANULAR BASE, OVER AREAS WHERE GRADE CHANGES ARE REQUIRED, AND SO THAT EXCAVATED MATERIAL MAY BE STOCKPILED WITHOUT COVERING TOPSOIL.
7. EXCAVATE TO LINES, GRADES, ELEVATIONS AND DIMENSIONS AS INDICATED FOR DITCHING AND SUBGRADE FOR ASPHALT PAVING AND GRANULAR BASE.
8. PROOF-ROLL SUBGRADE WITH FULLY LOADED TANDEM AXLE TRUCK TO DETECT SOFT AREAS. SOFT AREAS OR SILT SHALL BE REPAIRED AS DIRECTED BY THE CONSULTANT.
9. EXCAVATION SHALL BE COMPLETED USING AN EXCAVATOR WITH A SMOOTH BLADED BUCKET AND OPERATING FROM THE EDGE OF THE EXCAVATION TO MINIMIZE DISTURBANCE TO THE EXPOSED SUBGRADE.
10. GRADE SO THAT WATER WILL DRAIN AWAY FROM BUILDINGS, WALLS AND PAVED AREAS. TO DISPOSE OF EXCESS MATERIAL, DITCHING SHALL BE COMPLETED IN ADVANCE OF CONSTRUCTION OF GRANULAR BASE.

ENCOUNTERED IN THE EXCAVATED SLOPES, BACKFILLING SHALL NOT BE PERMITTED TO REDUCE SLOPES TO EXISTING SLOPES. WHEN BOLDERS ARE ENCOUNTERED IN THE EXCAVATED SLOPES, THE BOLDERS SHALL BE REMOVED WHEN DIRECTED BY THE CONTRACT ADMINISTRATOR AND THE CAVITY BACKFILLED WITH APPROVED MATERIAL AND COMPACTED.

12. NOTIFY CONSULTANT WHEN EXCAVATIONS ARE COMPLETE AND DO NOT COMMENCE BACKFILLING UNTIL FILL MATERIAL AND SUBGRADE HAS BEEN INSPECTED AND APPROVED BY THE CONTRACT ADMINISTRATOR.

13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CARRYING OUT ALL QUALITY CONTROL GRADE CHECKS TO ENSURE HORIZONTAL AND VERTICAL GRADING TOLERANCES ARE MET.

- a. VERTICAL GRADING TOLERANCE FOR TOP OF EARTH SUBGRADE:  $\pm 0$  - 30 MM
- b. HORIZONTAL GRADING TOLERANCE FOR VERTICAL FACES OF EXCAVATIONS TO BE BACKFILLED:  $+ 100$  MM,  $- 0$  MM
- c. VERTICAL GRADING TOLERANCE FOR DITCHING:  $\pm 0$  - 30 MM
- d. HORIZONTAL GRADING TOLERANCE FOR DITCH INVERTS AND BACK SLOPES:  $\pm 0$  - 300 MM

1. HDPE PERFORATED SUBDRAIN AND PIPE FITTINGS TO OPSS 1840.
2. NON-WOVEN GEOTEXTILE TO OPSS 1860, CLASS II, FOS 75-150 MICRONS.
3. PLACE HDPE PERFORATED SUBDRAINS AS SPECIFIED AND PER OPSS 405.
4. PLACE CLASS II NON-WOVEN GEOTEXTILE AS SPECIFIED.
5. 19MM TYPE II CLEAR STONE MATERIAL AS PER OPSS 1004.

GRANULAR BASE

1. THE WORK SHALL INCLUDE THE SUPPLY, TRANSPORTATION, HAULING, PLACING, GRADING AND COMPACTION OF GRANULAR SUB-BASE AND GRANULAR BASE.
2. GRANULAR A AND GRANULAR B TYPE I ACCORDING TO OPSS 1010. MATERIAL SHALL BE KEPT FREE FROM CLAY AND OTHER TYPES OF DELETERIOUS MATERIAL. THE CONTRACTOR'S OPERATIONS SHALL NOT DISTURB UNDERLYING WORK.
3. STOCKPILE MATERIAL IN AREAS APPROVED BY THE CONSULTANT.

4. BACKFILLING AND CONSTRUCTION OF GRANULAR SUB-BASE AND BASE SHALL NOT COMMENCE UNTIL GRANULAR MATERIAL HAS BEEN APPROVED BY THE CONTRACT ADMINISTRATOR.
5. BACKFILLING AND CONSTRUCTION OF GRANULAR BASE SHALL NOT COMMENCE UNTIL SUBGRADE IS CONSTRUCTED, INSPECTED AND APPROVED BY CONSULTANT.
6. CONSTRUCT GRANULAR BASE TO DEPTH AND GRADE IN AREAS IDENTIFIED. ENSURE NO FROZEN MATERIAL IS PLACED. PLACE MATERIAL ONLY ON CLEAN UNFROZEN SURFACE, FREE FROM SNOW AND ICE. PLACE MATERIAL USING METHODS WHICH DO NOT LEAD TO SEGREGATION OR DEGRADATION OF AGGREGATE.
7. SHAPE EACH LAYER TO SMOOTH CONTOUR AND COMPACT TO SPECIFIED DENSITY BEFORE THE FOLLOWING LAYER IS PLACED. GRANULAR MATERIAL PLACED IN MAXIMUM LIFT THICKNESS OF 300 MM.
8. REMOVE AND REPLACE THAT PORTION OF LAYER IN WHICH MATERIAL BECOMES SEGREGATED DURING SPREADING.
9. FINISHED BASE SURFACE TO BE WITHIN PLUS OR MINUS 25 MM OF ESTABLISHED GRADE AND CROSS SECTION BUT NOT UNFORMILY HIGH OR LOW. HORIZONTAL GRADING TOLERANCE FOR EXTENTS OF GRANULAR BASE: + 100 MM, - 0 MM.
10. NOTIFY CONSULTANT WHEN CONSTRUCTION OF GRANULAR BASE IS COMPLETE AND DO NOT COMMENCE PAVING UNTIL GRADES & LIMITS HAVE BEEN INSPECTED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
11. SEE QUALITY CONTROL SECTION FOR TESTING REQUIREMENTS.

1. THE MATERIALS USED IN THE PRODUCTION OF THE HMA SHALL BE ACCORDING TO OPSS 1150.
2. ASPHALT PAVING SHALL CONSIST HLA COURSES AS SPECIFIED. ASPHALT CEMENT SHALL BE PGAC 52-34.
3. CONTRACTOR TO SUBMIT MIX DESIGN MINIMUM 7 DAYS PRIOR TO PAVING.
4. EQUIPMENT IN ACCORDANCE TO OPSS 310.06.
5. PRIOR TO PLACING ANY COURSE OF HMA ON A GRANULAR GRADE, A CLASS S ROLLER OF A MINIMUM OF 7 TONNES OR AN EQUIVALENT CLASS V ROLLER WITH A DRUM WIDTH OF AT LEAST 1.2 METRES SHALL BE USED TO FINISH ROLL THE GRANULAR GRADE OF THE PAVEMENT TO ENSURE A COMPACTED, SMOOTH, AND FLOAT-FREE SURFACE. ANY DISTORTION THAT WILL IMPACT THE SPECIFIED THICKNESS OF THE PAVEMENT TO BE PLACED SHALL BE REPAIRED.
6. THE TEMPERATURE OF THE HMA PRIOR TO PLACEMENT SHALL BE WITHIN THE TEMPERATURE RANGE THAT CORRESPONDS TO THE PGAC MANUFACTURER'S RECOMMENDED MIX TEMPERATURE. THE TEMPERATURE OF THE HMA IMMEDIATELY AFTER SPREADING AND PRIOR TO INITIAL ROLLING SHALL NOT BE LESS THAN 120 °C.
7. PAVING SHALL NOT BE CARRIED OUT IF THE GRANULAR BASE IS FROZEN, THE GRANULAR GRADE SHALL BE FREE OF STANDING WATER AT THE TIME OF HMA PLACEMENT.
8. PLACING OF HOT MIX ASPHALT IN ACCORDANCE TO OPSS 310.07.06.02.
9. USE OF PAVING EQUIPMENT IN ACCORDANCE TO OPSS 310.07.07.
10. LONGITUDINAL AND TRAVERSE JOINTS IN ACCORDANCE TO OPSS 310.07.11.
11. COMPACTION IN ACCORDANCE TO OPSS 310.07.12
12. EACH COURSE AFTER FINAL COMPACTION SHALL BE OF UNIFORM TEXTURE AND SHALL BE FREE OF DEFECTS SUCH AS SEGREGATION, FAT SPOTS, OIL SPILLS, AND ROLL MARKS. DEFECTIVE AREAS SHALL BE REMOVED AND REPLACED WITH ASPHALT OF THE SAME TYPE AND COMPACTED TO NO COST TO THE OWNER AND TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR.
13. FINISHED GRADES SHALL BE WITHIN 25 MM OF SPECIFIED GRADES BUT NOT UNIFORMLY HIGH OR LOW.
14. SEE QUALITY CONTROL SECTION FOR TESTING REQUIREMENTS.

1. THE TYPE OF COMPACTION EQUIPMENT USED SHALL BE SUITED TO THE MATERIAL TO BE COMPACTED, DEGREE OF COMPACTION REQUIRED, AND SPACE AVAILABLE.
2. GRANULAR SUBBASE MATERIAL SHALL BE COMPACTED TO A MINIMUM OF 98% STANDARD PROCTOR MAXIMUM DRY DENSITY (SPMDD). GRANULAR BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM OF 98% SPMDD. THE SPMDD SHALL BE DETERMINED USING LS-706 OR ASTM D 698.
4. WATER SHALL BE APPLIED, AS NECESSARY, TO ACHIEVE THE DEGREE OF COMPACTION REQUIRED.
5. HOT MIX ASPHALT SHALL BE COMPACTED TO A MINIMUM DENSITY OF 92% BASED ON THE MAXIMUM RELATIVE DENSITY.

1. NEW SIDEWALKS AND CURB TO BE CONSTRUCTED TO ELEVATIONS INDICATED.
2. PROVIDE MINIMUM 300mm COMPACTED GRANULAR B TYPE I BENEATH CONCRETE CURBS AND SIDEWALK
3. MINIMUM 28-DAY COMPRESSIVE STRENGTH: 32 MPA
4. CONCRETE MIXES AND MATERIALS IN ACCORDANCE WITH OPSS 1350. SUBMIT PERFORMANCE BASED CONCRETE MIX DATA.
5. JOINT FILLER MATERIAL SHALL BE ASPHALT IMPREGNATED FIBREBOARD HAVING A MINIMUM OF 12 MM THICKNESS AND SHALL BE ACCORDING TO OPSS 1308, TYPE A.
6. HOT RUBBERIZED ASPHALT JOINT SEALING COMPOUND IN ACCORDANCE TO OPSS 1212.
7. CURING COMPOUND IN ACCORDANCE TO OPSS 1315.
8. CONCRETE PLACEMENT, JOINTS, FINISHING AND CURING FOR CONCRETE SIDEWALKS IN ACCORDANCE TO OPSS 351.
9. CONCRETE PLACEMENT, JOINTS, FINISHING AND CURING FOR CONCRETE CURB, GUTTERS AND SPILLWAYS AND GUTTER OUTLETS IN ACCORDANCE TO OPSS 353.
10. ALLOW CONCRETE TO CURE FOR 7 DAYS PRIOR TO BACKFILLING.
11. SEE QUALITY CONTROL FOR TESTING REQUIREMENTS.

1. EXCAVATED AND DISTURBED GRASS AREAS SHALL BE REPLACED WITH 75mm TOPSOIL AND SOD. TOPSOIL AND SOD TO BE PLACED IN ACCORDANCE WITH OPSS 802 AND OPSS 803. MAKE GOOD ALL SOFT LANDSCAPING OUTSIDE EXTENT OF CONTRACT AS REQUIRED DUE TO NEW WORK WITH NEW 75mm TOPSOIL AND SOD. REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL TOPSOIL AND SOD LIMITS, NOTES AND DETAILS.

1. THE SCOPE OF WORK INCLUDES THE APPLICATION OF PAVEMENT MARKINGS ONTO BITUMINOUS PAVEMENT.
2. PAINT IN ACCORDANCE TO CSGS 1-PG-71, ORGANIC SOLVENT BASE TRAFFIC PAINT SHALL BE HOMOGENEOUS, AND SHALL BE WELL GROUND TO A UNIFORM SMOOTH CONSISTENCY. IT SHALL BE FREE FROM SKIN, DIRT AND OTHER FOREIGN PARTICLES, AND SHALL BE CAPABLE OF BEING SPRAYED AT THE TEMPERATURE INTENDED FOR APPLICATION. THE ORGANIC SOLVENT BASED TRAFFIC PAINT SHALL FLOW EVENLY AND SMOOTHLY AND COVER SOLIDLY WHEN APPLIED TO PAVEMENTS.
3. PAINT COLOUR: CSGS 1-PG-12C YELLOW 505-308, CSG 1-PG-12C WHITE 513 - 301, BLUE.
4. THE EQUIPMENT TO BE USED FOR APPLICATION OR INSTALLATION OF PAVEMENT MARKINGS SHALL AS RECOMMENDED BY THE MANUFACTURER OF THE RESPECTIVE PAVEMENT MARKING MATERIAL.
5. THE PAVEMENT SURFACE MUST BE CLEAN AND DRY. CONTAMINANTS SUCH AS DIRT, LOOSE ASPHALT PARTICLES AND OILY RESIDUE SHALL BE REMOVED PRIOR TO APPLICATION OF PAVEMENT MARKING.
6. UNLESS OTHERWISE APPROVED BY CONSULTANT, APPLY PAINT ONLY WHEN AIR TEMPERATURE IS ABOVE 5°C, WIND SPEED IS LESS THAN 40 KM/H AND NO RAIN IS FORECAST WITHIN NEXT 4 HOURS.
7. PAINT LINES TO BE OF UNIFORM COLOUR AND DENSITY WITH SHARP EDGES.
8. DO NOT THIN PAINT UNLESS APPROVED BY CONSULTANT.

1. ALL MATERIALS AND WORKMANSHIP SUBJECT TO THE INSPECTION AND APPROVAL OF THE CONSULTANT.
2. CONTRACTOR TO RETAIN A CCIL CERTIFIED LAB FOR QUALITY CONTROL TESTING (QC) . QC MATERIAL TESTS SHALL BE USED FOR THE PURPOSE OF ACCEPTANCE.
3. CONTRACTOR IS RESPONSIBLE FOR COSTS ASSOCIATED WITH ADDITIONAL TESTING DUE TO FAILED RESULTS. MATERIAL REPRESENTED BY FAILED TESTS MAY BE REJECTED AND REMOVED FROM SITE AT NO COST TO THE OWNER.
4. CONTRACTOR TO OBTAIN SAMPLES AND PROVIDE CLEAN SAMPLE BAGS. ALL SAMPLING SHALL BE WITNESSED BY THE CONSULTANT.
5. QUALITY CONTROL (QC) DENSITY TESTING TO ENSURE GRANULAR MATERIALS ARE COMPACTED ACCORDING TO THE REQUIREMENTS. COMPACTION TESTING SHALL BE DONE FOR EACH LIFT OF GRANULAR A & GRANULAR B. MINIMUM OF FOUR LOTS PER LIFT OF MATERIAL. MINIMUM FOUR TESTS PER LOT.
6. A MINIMUM OF FOUR SAMPLES OF GRANULAR A AND TWO OF GRANULAR A TO BE TAKEN AT RANDOM FOR TESTING GRADATION REQUIREMENTS IN ACCORDANCE WITH OPSS 1010. SAMPLE SIZES AS PER OPSS 1010.
7. ONE LOOSE MIX ASPHALT SAMPLE (QC & REF) TO BE TAKEN FOR EACH DAY OF PAVING FOR TESTING ASPHALT CEMENT CONTENT AND GRADATION. SAMPLING AS PER OPSS 310.
8. ONE 7 DAY CYLINDER, TWO 28 DAY CYLINDERS AND A HOLD TO BE TAKEN PER DAY OF CONCRETE POURING FOR TESTING COMPRESSIVE STRENGTH. ADDITIONAL SET TO BE TAKEN IF DAILY POURED QUANTITY EXCEEDS 1000 M<sup>3</sup>. COMPRESSIVE FIELD TESTING AND FREQUENCY TO BE DONE IN ACCORDANCE TO OPSS 1350.
9. ALL TEST RESULTS SHALL BE PROVIDED TO THE CONSULTANT WITHIN 24 HOURS.

OPSS	180	GENERAL SPECIFICATION FOR THE MANAGEMENT OF EXCESS MATERIALS	NOVEMBER 2016
OPSS	310	CONSTRUCTION SPECIFICATION FOR HOT MIX ASPHALT	NOVEMBER 2017
OPSS	441	CONSTRUCTION SPECIFICATION FOR WATERMAIN INSTALLATION IN OPEN CUT	NOVEMBER 2021
OPSS	501	CONSTRUCTION SPECIFICATION FOR COMPACTING	NOVEMBER 2017
OPSS	802	CONSTRUCTION SPECIFICATION FOR TOPSOIL	NOVEMBER 2019
OPSS	803	CONSTRUCTION SPECIFICATION FOR SODDING	APRIL 2018
OPSS	805	CONSTRUCTION SPECIFICATION FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	NOVEMBER 2021
OPSS	1010	MATERIAL SPECIFICATION FOR AGGREGATES—BASE, SUBBASE, SELECT SUBGRADE AND BACKFILL	MATERIAL NOVEMBER 2013


		07/28/2022	ISSUED FOR TENDER & PERMIT	A
			Revision	
			Date	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

---

 **TBT ENGINEERING**  
CONSULTING GROUP

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY

MARATHON, ON

Drawing Title:  
SITE GRADING AND DRAINAGE PLAN

Drawn By: BS	Checked By: MP
-----------------	-------------------

Scale: AS NOTED	Project No: 22-098
--------------------	-----------------------

Date Plotted:

Date Revised:  
JULY 28, 2022

Drawing No:

NOT FOR CONSTRUCTION

1. ALL NON-LOADBEARING CONCRETE MASONRY UNITS (CMU) ON THIS PROJECT WILL BE CONCRETE TYPE "LIGHT-WEIGHT" (2-20S) IN ORDER TO ACHIEVE THE REQUIRED FIRE RESISTANCE RATINGS. REFER TO STRUCTURAL DRAWINGS FOR SPECIFICATIONS OF ALL LOADBEARING MASONRY.
2. FOR LOCATION AND EXTENT OF ALL INTERIOR PARTITIONS AND FURRING REQUIRED FOR FLOOR PLANS, A2 SERIES OF DRAWINGS.
3. ALL CONCRETE UNIT MASONRY PARTITIONS NOT TAGGED ON FLOOR PLANS SHALL BE ASSUMED TO BE PARTITION TYPE 'P1'.
4. COORDINATE ALL REQUIRED CONCRETE UNIT MASONRY BETWEEN ARCHITECTURAL AND STRUCTURAL ENGINEERING DRAWINGS. ANY DISCREPANCIES BETWEEN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS REGARDING THE SIZES OF THE STRUCTURAL DRAWINGS SHALL GOVERN.
5. THIS SCHEDULE IS TO BE READ IN CONJUNCTION WITH THE FIRE SEPARATION DRAWINGS. ALL PARTITIONS THAT CONSTITUTE FIRE SEPARATION SHALL BE CONSTRUCTED AND SEALED IN ACCORDANCE TO DETAILS IN LIST OF DETAILS THIS SCHEDULE. COMPLETE ASSEMBLY OF ALL PARTITIONS FORMING PART OF A FIRE SEPARATION SHALL EXTEND TO THE UNDERSIDE OF THE STRUCTURAL DECK ABOVE.
6. CALK ALL JOINTS BETWEEN FINISHED MASONRY AND GYPSUM FINISHES.
7. WHERE STRUCTURE INTERFERES WITH STUD PARTITIONS AND NON STRUCTURAL MASONRY, PREVENTING IT FROM RUNNING TO UNDERSIDE OF FLOOR/ROOF DECK, REMOVE PARTITION AS DETAILED ON THIS DRAWING SHEET.
8. GYPSUM BOARD AS NOTED ON THE INTERIOR PARTITION AND FURRING SCHEDULE SHALL ASSUME TO BE 16MM TYPE 'X'. REFER TO THE INTERIOR ELEVATIONS SERIES AG AND THE ROOM FINISH SCHEDULE FOR LOCATION OF ABOVE RESISTANT GYPSUM (ABG), GLAS TACK GYPSUM (MG) AND TILE BACKER BOARD (TBB) TO BE INSTALLED IN JUEI TYPE 'X'.
9. AT ALL PARTITIONS FORMING PART OF A FIRE SEPARATION ABOVE RESISTANT GYPSUM BOARD, JOINT MAT GYPSUM AND THE BACKER BOARD SHALL BE SUBSTITUTED FOR ULC FIRE RATED OF SAME TYPE IN LIEU OF SPECIFIED. COORDINATE WITH FIRE SEPARATION DRAWINGS.
10. ALL SOUND ATTENUATION PARTITIONS, INSTALL ACOUSTICAL SEALANT BETWEEN TOP AND BOTTOM OF PARTITIONS AND DECORATE EACH SIDE OF WALL AT JUNCTION OF FLOOR SLAB OR STRUCTURE ABOVE. INSTALL ACOUSTICAL SEALANT AROUND ALL WALL PENETRATIONS INCLUDING BUT NOT LIMITED TO CUT-OUTS FOR ELECTRICAL BOXES, DUCTS, AND MISC. STRUCTURE.
11. ALL EXPOSED CONCRETE UNIT MASONRY TO COME WITH BULLNOSE ON OUTSIDE CORNERS INCLUDING AT WALL OPENINGS.
12. REFER TO SPECIFICATION SECTIONS 09110 AND 09250 FOR ALL OTHER NOTES REGARDING CAST STEEL STUD AND GYPSUM PARTITIONS.
13. ENSURE MINIMUM OF 100MM CONCRETE UNIT MASONRY CLEAR BEHIND ALL MECHANICAL AND ELECTRICAL EQUIPMENT RECESSED INTO MASONRY WALLS REQUIRING A RATED FIRE SEPARATION TO MAINTAIN CONTINUITY OF FIRE SEPARATION.
14. ALL MECHANICAL AND ELECTRICAL DEVICES REQUIRED IN MASONRY WALL 190MM OR WIDER TO BE INSTALLED SO HEAD OF DEVICE IS SET TO FULL BLOCK COURSING. COORDINATE WORK WITH MECHANICAL AND ELECTRICAL SUBTRADES.
15. ALL HOLLOW METAL FRAMES TO BE INSTALLED IN ACOUSTICALLY RATED PARTITIONS SHALL BE FILLED WITH ACOUSTIC BATT INSULATION AS SPECIFIED.

TYPE	DETAIL	CONSTRUCTION	NOTES
P1	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<p>CONCRETE MASONRY UNIT PARTITION</p> <ul style="list-style-type: none"> <li>– WALL FINISH</li> <li>– 140 CONCRETE MASONRY UNITS</li> <li>– WALL FINISH</li> </ul> <p>NOTE: SEE PLAN DETAIL ON DRAWING A2.03 FOR "P1" TYPE WHERE T/O WALL TERMINATES AT 2800.</p>	<ol style="list-style-type: none"> <li>1. REFER TO STRUCTURAL ENGINEERING DRAWINGS FOR ALL GROUTING AND REINFORCING AS REQUIRED.</li> <li>2. TOP OF WALL TO BE KNOTCHED TO ACCOMMODATE INSTALL OF DUCTWORK.</li> </ol>
P1a	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<p>CONCRETE MASONRY UNIT PARTITION</p> <ul style="list-style-type: none"> <li>– WALL FINISH</li> <li>– 140 CONCRETE MASONRY UNITS</li> <li>– WALL FINISH</li> </ul>	<ol style="list-style-type: none"> <li>1. DEFLECTION GAP AND LATERAL SUPPORT AS PER STRUCTURAL ENGINEERING DEFLECTION GAP TO BE MINIMUM 25MM OR AS PER STRUCTURAL REQUIREMENTS</li> <li>2. REFER TO STRUCTURAL ENGINEERING DRAWINGS FOR ALL GROUTING AND REINFORCING AS REQUIRED</li> <li>3. CONTINUOUS COMPRESSIBLE MINERAL WOOL BATT INSULATION FILLER BETWEEN STRUCTURE AND TOP OF BLOCK. REFER ALSO TO FIRE SEPARATION DIAGRAM AND DETAILS.</li> </ol>
P2	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<p>CONCRETE MASONRY UNIT PARTITION</p> <ul style="list-style-type: none"> <li>– WALL FINISH</li> <li>– 190 CONCRETE MASONRY UNITS</li> <li>– WALL FINISH</li> </ul>	<ol style="list-style-type: none"> <li>1. REFER TO STRUCTURAL ENGINEERING DRAWINGS FOR ALL GROUTING AND REINFORCING AS REQUIRED.</li> <li>2. TOP OF WALL TO BE KNOTCHED TO ACCOMMODATE INSTALL OF DUCTWORK, WHERE REQUIRED.</li> </ol>

TYPE	DETAIL	CONSTRUCTION	NOTES
P2a	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<p>CONCRETE MASONRY UNIT PARTITION</p> <ul style="list-style-type: none"> <li>— WALL FINISH</li> <li>— 190 CONCRETE MASONRY UNITS</li> <li>— WALL FINISH</li> </ul>	<ol style="list-style-type: none"> <li>1. DEFLECTION GAP AND LATERAL SUPPORT AS PER STRUCTURAL ENGINEERING DEFLECTION GAP TO BE MINIMUM 25MM OR AS PER STRUCTURAL REQUIREMENTS</li> <li>2. REFER TO STRUCTURAL ENGINEERING DRAWINGS FOR ALL GROUTING AND REINFORCING AS REQUIRED</li> <li>3. CONTINUOUS COMPRESSIBLE MINERAL WOOL BATT INSULATION FILLER BETWEEN STRUCTURE AND TOP OF BLOCK. REFER ALSO TO FIRE SEPARATION DIAGRAM AND DETAILS.</li> </ol>
P3	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<p>CONCRETE MASONRY UNIT PARTITION</p> <ul style="list-style-type: none"> <li>— WALL FINISH</li> <li>— 240 CONCRETE MASONRY UNITS</li> <li>— WALL FINISH</li> </ul>	<ol style="list-style-type: none"> <li>1. REFER TO STRUCTURE FOR BEARING.</li> <li>2. REFER TO STRUCTURAL ENGINEERING DRAWINGS FOR ALL GROUTING AND REINFORCING AS REQUIRED</li> </ol>
F1	<p><b>STRUCTURE</b></p> <p>FINISHED CEILING</p> <p>FLOOR SLAB</p>	<ul style="list-style-type: none"> <li>— WALL FINISH</li> <li>— 16 GYPSUM BOARD TO 100MM ABOVE FINISHED CEILING</li> <li>— 92 STEEL STUDS @ 405 OC</li> </ul>	<ol style="list-style-type: none"> <li>1. TERMINATE GYPSUM BOARD / FURR-OUT ABOVE FINISHED CEILING, AS INDICATED.</li> <li>2. KEEP BOTTOM EDGE OF GYPSUM BOARD 13MM ABOVE THE SLAB.</li> <li>3. PROVIDE CONTINUOUS SILL GASKET UNDER BOTTOM TRACK.</li> </ol>

ALL WORK SHALL BE CONSTRUCTED IN ACCORDANCE TO THE LATEST ADDITION OF THE ONTARIO BUILDING CODE AND ALL LOCAL MUNICIPAL BY-LAWS HAVING JURISDICTION.

DO NOT SCALE ANY DRAWING. ALL NOTES AND DIMENSIONS TAKE PRECEDENCE OVER ANY SCALE. ALL DIMENSIONS SHALL BE CHECKED AND VERIFIED ON SITE. REPORT ALL DISCREPANCIES TO THE CONSULTANT PRIOR TO PROCEEDING WITH WORK.

THE GENERAL CONTRACTOR IS RESPONSIBLE FOR REVIEWING ALL DRAWINGS AND SPECIFICATIONS AND NOTIFYING THE CONSULTANT OF ANY DISCREPANCIES TO THE CONSULTANT PRIOR TO PROCEEDING WITH THE WORK. ARCHITECTURAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL CIVIL, STRUCTURAL, MECHANICAL, ELECTRICAL AND PLUMBING AS A COMPLETE PACKAGE. UNLESS OTHERWISE SPECIFICALLY NOTED WITHIN THE DRAWINGS, IN THE EVENT OF ANY DISCREPANCIES BETWEEN DRAWINGS THE ARCHITECTURAL DRAWINGS SHALL GOVERN.

THE GENERAL CONTRACTOR SHALL REVIEW ALL DRAWINGS AND SPECIFICATIONS AND NOTIFY THE CONSULTANT BEFORE REQUIRED TO INSTALL MECHANICAL AND ELECTRICAL SERVICES AND REPORT DISCREPANCIES AS FAR AHEAD AS POSSIBLE.

ALL MECHANICAL, ELECTRICAL, STRUCTURAL AND CIVIL ENGINEERING WORK INDICATED ON THE ARCHITECTURAL DRAWINGS ARE STRICTLY FOR THE GENERAL CONSTRUCTION OF THE BUILDING. THEY DO NOT INCLUDE ALL WORK OR DEVICES / FIXTURES / EQUIPMENT OF ENGINEERING DRAWINGS ARE INDICATED ON THE ARCHITECTURAL. REFER TO THE ENGINEERING DRAWINGS FOR FULL EXTENT AND LOCATIONS OF ALL WORK IN CONJUNCTION WITH NOTE NO. 3 ABOVE.

ALL ITEMS NOTED AS "X" SHALL BE OWNER SUPPLIED ITEM, EQUIPMENT OR FIXTURE. SUPPLY AND INSTALLATION SHALL NOT BE INCLUDED IN THE SCOPE OF WORK BUT ALL RELATED WORK SHALL BE FULLY COORDINATED WITH THE CONSULTANT PRIOR TO FABRICATION OR INSTALLATION TO ENSURE PROPER FIT.

07/26/2022	Issued For Permit and Tender	0
	Date	Revision

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



 INTERIOR PARTITION, SEE INTERIOR PARTITION SCHEDULE

 WALL FURRING, SEE INTERIOR FURRING SCHEDULE

 INTERIOR CONCRETE UNIT MASONRY PARTITION, SEE PARTITION SCHEDULE

 NEW DOOR

 DOOR NUMBER, SEE DOOR AND FRAME SCHEDULE

 BARRIER FREE TURNING RADIUS

 DRAWING #  
DRAWING TITLE  
DRAWING SCALE

 SHEET #  
DRAWING #  
SHEET #

 ELEVATION DRAWING #  
DRAWING AND SHEET #

 SECTION DRAWING #  
SHEET #

 WHITEBOARD

 ELECTRICAL PANEL (SEE ELECTRICAL DRAWINGS)

 FIRE EXTINGUISHER CABINET (SEE MECHANICAL DRAWINGS)

 POWER DOOR OPERATOR PUSH BUTTON

 RADIANT IN SLAB MANIFOLD CABINET (SEE MECHANICAL DRAWINGS)

 RAINWATER LEADER AND DOWN SP  
NOZEL OUTLET (SEE MECHANICAL DRAWINGS)



 HOSE BIBB (SEE MECHANICAL)

	<p>W2</p> <ul style="list-style-type: none"> <li>-PREFINISHED INSULATED METAL PANEL' (IMP) BY METL-SPAN OR APPROVED EQUAL -SEE ELEVATIONS</li> <li>-150 WINDBEARING GALVANIZED STEEL STUDS @ 405 OC</li> <li>-1/2 GYPSUM BOARD</li> <li>-INTERIOR FINISH</li> </ul>
	<p>W4</p> <ul style="list-style-type: none"> <li>-PREFINISHED INSULATED METAL PANEL' (IMP) BY METL-SPAN OR APPROVED EQUAL -SEE ELEVATIONS</li> <li>-STEEL GIRTS &amp; SAG RODS (SEE STRUCTURAL)</li> <li>-PREFINISHED METAL LINER PANEL (CL 508, BY VIC WEST, OR APPROVED EQUAL), SEAL ALL GAPS, JOINTS, TRANSITIONS AND PENETRATIONS</li> </ul>

	<p>— FLOOR FINISH          — CONCRETE SLAB ON GRADE (THICKNESS VARIES), WITH IN SLAB HEAT          — 10MIL POLY VAPOUR BARRIER, LAP AND SEAL ALL JOINTS, TRANSITIONS AND PENETRATIONS          — 40 RIGID XPS INSULATION (SHIPPAPPED), PROVIDE LAYER VERTICAL AT FOUNDATION PERIMETER (UNDERSIDE OF SLAB TO TOP OF FOOTING).          — COMPACTED SUBSLAB GRANULAR FILL MATERIAL</p> <p>SEE ALTERNATE PRICES IN SUPPLEMENTARY TENDER FOR USE OF SPRAY FOAM INSULATION IN LEU OF XPS AND VAPOUR BARRIER.</p>
--	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

<p><b>R1</b></p> 	<p>-FULLY ADHERED EPDM ROOF MEMBRANE          -2 LAYERS RIGID POLYISO INSULATION, 100MM ON 100MM          RIGID POLYISO INSULATION, BOTTOM LAYER MECHANICAL          FASTENED, TOP LAYER FULLY ADHERED, STAGGER ALL          JOINTS (PROVIDE RIGID SLOPED INSULATION WHERE          INDICATED)          -FULLY ADHERED VAPOUR BARRIER, SEAL ALL JOINTS,          TRANSITIONS AND PENETRATIONS          -STRUCTURAL STEEL DECK AND STEEL STRUCTURE PER          STRUCTURAL DRAWINGS</p>
--------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Four technical drawings of window types are shown, each with dimensions and labels:

- W1 (FIXED STRIP WINDOW):** Dimensions are 4267 (width) and 1372 (height). The window is divided into three vertical sections, each labeled 'T'.
- W2 (FIXED STRIP WINDOW):** Dimensions are 2440 (width) and 1220 (height). The window is divided into three vertical sections, each labeled 'T'.
- W3 (FIXED STRIP WINDOW):** Dimensions are 2823 (width) and 1830 (height). The window is divided into three vertical sections, each labeled 'T'. A label 'INSULATED 90 DEGREE COUPLER BY WINDOW SUPPLIER' points to the top edge of the middle section.
- W4 (FIXED PUNCHED WINDOW):** Dimensions are 1269 (width) and 1220 (height). The window is a single square section labeled 'T'.

T

TEMPERED GLAZING

OPAQUE FILM

<p> <b>Form Name:</b> Critchley Hill Architecture Inc.  <b>Certificate of Practice Number:</b> 5887  <b>Ian Critchley Hill</b>  <b>123 McIntyre Street West</b>  <b>North Bay, On</b>  <b>P1B 2Y5</b>  <b>Name of Project:</b>  <b>Town of Marathon -New Public Works Facility</b>  <b>Location:</b>  <b>2 Penn Lake Road</b>  <b>Marathon, Ontario</b> </p>						<p>                     The architect noted above has exercised responsible control with respect to design activities. The architect's seal number is the architect's BC2DN                 </p>	
Item	Ontario Building Code Data Matrix Parts 3 & 9				OBC Reference		
1	Project Description: <input checked="" type="checkbox"/> New <input type="checkbox"/> Part 11 <input checked="" type="checkbox"/> Part 3 <input type="checkbox"/> Part 9		11.1 to 11.4		2.1.1	2.1.1	
	<input type="checkbox"/> Change of Use <input type="checkbox"/> Addition <input type="checkbox"/> Alteration				9.10.2	9.10.1,3	
2	Major Occupancy(s) Group F, Division 2, Industrial Occupancy				3.1.2.1.(1)	9.10.2	
3	Building Area(m <sup>2</sup> ) Existing <b>N/A</b> New <b>1396</b> Total <b>1396</b>				1.1.3.2	1.1.3.2	
4	Gross Area(m <sup>2</sup> ) Existing <b>N/A</b> New <b>1652</b> Total <b>1652</b>				1.1.3.2	1.1.3.2	
5	Number of Storeys Above Grade <b>2</b> Below Grade <b>0</b>				3.2.1.1 & 1.1.3.2	2.1.1.3	
6	Number of Streets/Access Routes <b>2</b>				3.2.2.10 & 3.2.5.5	9.10.19	
7	Building Classification <b>OBC 3.2.2.70</b>				3.2.2.20-83	9.10.4	
8	Sprinkler System Proposed <input type="checkbox"/> entire building <input type="checkbox"/> basement only <input type="checkbox"/> in lieu of roof rating <input checked="" type="checkbox"/> not required				3.2.2.20-83 3.2.1.5 3.2.2.17	9.10.8	
9	Standpipe required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				3.2.9	N/A	
10	Fire Alarm required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				3.2.4	9.10.7.2	
11	Water Service/Supply is Adequate <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				3.2.5.7	N/A	
12	High Building <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				3.2.6	N/A	
13	Permitted Construction <input type="checkbox"/> Combustible <input checked="" type="checkbox"/> Non-combustible <input type="checkbox"/> Both				3.2.2.20-83	9.10.6	
14	Actual Construction <input type="checkbox"/> Combustible <input checked="" type="checkbox"/> Non-combustible <input type="checkbox"/> Both						
14	Mezzanine(s) Area m <sup>2</sup> <b>128 (Open Mezzanine)</b>				3.2.1.1.(3)-(8)	9.10.4.1	
15	Occupant load based on <input type="checkbox"/> m <sup>2</sup> /person <input checked="" type="checkbox"/> design of building				3.1.16	9.9.1.3	
	Basement:	Occupancy <b>N/A</b> Load <b>N/A</b> persons					
	1st Floor	Occupancy <b>N/A</b> Load <b>20</b> persons					
	2nd Floor	Occupancy <b>N/A</b> Load <b>0</b> persons					
	3rd Floor	Occupancy <b>N/A</b> Load <b>N/A</b> persons					
16	Barrier-free <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No                     (Explain) .				3.8	9.5.2	
17	Hazardous Substances <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				3.3.1.2 & 3.3.1.19	9.10.13(4)	
17	Required Fire Resistance Rating (FRR)	Horizontal Assemblies FRR (Hours)		Listed Design No. or Description (SG-2)		3.2.2.20-83 & 3.2.1.4	
Floors		3/4	Hour (Note 1)	200 Precast Concrete Slabs		9.10.9	
Roof		N/A	Hours	N/A			
Mezzanine		N/A	Hour	Non-Combustible			
FRR of Supporting Members		Listed Design No. or Description (SG-2)					
Floors		3/4	Hour (Note 1)	240 CMU			
	Roof	N/A	Hours	N/A			
	Mezzanine	N/A	Hour	Non-Combustible			
19	Spatial Separation - Construction of Exterior Walls				3.2.3	9.10.14	
Limiting distance of all exposed building faces to property lines are set back adequately to allow for 100% unprotected openings as per OBC 3.2.3. There is no fire resistance rating required for any exposed building face.							

Note 1: Floor for Trades Shop Mezzanine will require a 2 hour fire separation, as it separates the Repair Garage portion of the building from the remainder of the building.

CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY

Drawing Title:  
OBC MATRIX  
GENERAL NOTES  
INTERIOR PARTITION SCHEDULE  
INTERIOR FLIPPING SCHEDULE

Drawn By:	Checked By:
-----------	-------------

Scale: N/A	Project No: 2208
---------------	---------------------

Date Plotted:

Date Revised:

Drawing No:


# A0.01




CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL.CA

[illegible]


Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.




8 TYPICAL COLUMN DETAIL  
A0.04 SCALE 1:10



5 TYPICAL DETAIL - PLAN DETAILS  
A0.04 SCALE 1:10



4 TYPICAL DETAIL - PLAN DETAIL  
A0.04 SCALE 1:10



2 TYPICAL DETAILS - RATED PARTITION PENETRATIONS  
A0.04 SCALE 1:10

1. DETAILS DRAWN ON THIS SHEET ARE FOR ALL TYPICAL CONDITIONS THROUGHOUT THE WORK. NOT ALL CONDITIONS ARE DRAWN. REVIEW FULL SET OF DRAWINGS AND SPECIFICATIONS FOR ALL OTHER DETAILS AND NOTES INFLUENCING INTERIOR PARTITION WORK.
2. THESE DETAILS SHALL BE READ IN CONJUNCTION WITH THE FLOOR PLANS, INTERIOR PARTITION AND FURRING SCHEDULES ALONG WITH THE FIRE SEPARATION PLANS.
3. ALL ACoustICAL CAULKING INDICATED ON THESE DETAILS SHALL BE SUBSTITUTED FOR ULC RATED FIRE SEALANT ALL PARTITIONS FORMING PART OF A FIRE SEPARATION.
4. ALL INSULATION AS NOTED IN THESE DRAWINGS SHALL BE MINERAL WOOL WHEN PARTITION FORMS PART OF A FIRE SEPARATION.
5. ALL FIRE RATED DETAILS THIS SHEET ARE BASED ON A 2" MINIMUM ANNULAR SPACE AROUND WALL PENETRATION. SHOULD ACTUAL ON SITE CONDITIONS GENERATE A LARGER ANNULAR SPACE THAN GENERAL CONTRACTOR SHALL PROVIDE CONSULTANT WITH INFORMATION INCLUDING ULC PROVEN METHODS TO PROVIDE PROPER SEAL.

[illegible]

Do not scale from this drawing. The Constructor shall verify all actual on-site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO T0S 0S5 2301 CRITCHLEYHILL CA

Subject: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road

**Drawing Title:**  
**TYPICAL DETAILS FOR**  
**FIRE RATED PARTITIONS**

Drawn By:

Checked By:	
-------------	--

Scale:

Project No:

Date Plotted



---


Date Revise

---


Drawing No:

## A0.03







4 SIDEWALK INSULATION  
A1.02 SCALE 1:20



3 BOLLARDS AT O/H DOOR APRONS  
A1.02 SCALE 1:20



2 BOLLARDS AT FUEL TANKS  
A1.02 SCALE 1:20



1 OVERALL SITE PLAN -REMOVALS  
A1.02 SCALE 1:400



Revision	Date
0	
1	07/28/2022
2	
3	
4	
5	
6	
7	
8	
9	
10	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL.CA

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON

Drawn By:






Scale:

Date Plotted:

Date Revised:

Drawing No:

A1.02



PROJECT NORTH

Revision	Date	Issued For Permit and Tender
0		
1	07.28.2022	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.

ONTARIO ASSOCIATION OF ARCHITECTS  
IAN HILL  
LICENCE 5282

**CRITCHLEY HILL ARCHITECTURE**  
CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.992.2391 CRITCHLEYHILL.CA

Project: **TOWN OF MARATHON NEW PUBLIC WORKS FACILITY**  
2022-2023  
Marathon, ON

Drawing Title: **SITE PLAN**  
ADDITIONAL PRICES


Drawn By: KSH  
Checked By: ICH

Scale: As Noted  
Project No: 2208

Date Plotted: August 12, 2022  
Date Revised:

Drawing No: **A1.03**

FIRE SEPARATION LEGEND:  
----- 1 HOUR FIRE SEPARATION.  
- - - - - 1.5 HOUR FIRE SEPARATION.  
===== 2 HOUR FIRE SEPARATION.  
2 HOUR HORIZONTAL FIRE SEPARATION (TRADES MEZZANINE FLOOR).  
1 HOUR HORIZONTAL FIRE SEPARATION



0	Revision
07.28.2022	Issued For Permit and Tender
	Date

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY, ONTARIO 705.995.2391 CRITCHLEYHILL.CA

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON

Drawn By:  
KSH

Scale:  
1:100


Date Plotted:  
August 12, 2022



Date Revised:

Drawing No:

**A2.01**

1 MAIN FLOOR PLAN  
A2.01 SCALE 1:100



[illegible]

Do not scale from this drawing. The Constructor shall verify all actual site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.

Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
2 Penn Lake Road  
Marathon, ON


Drawing Title:

Date Revised:


Drawing No:

## A2.02

LEGENDS:



CERAMIC TILE FLOORING



Date	Revision
07/28/2022	Issued For Permit and Tender

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.239-1 CRITCHLEYHILL.CA

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Fern Lake Road  
Marathon, ON

Drawing Title:  
PLAN DETAILS

Drawn By:  
KSH

Checked By:  
ICH

Scale:  
1:50


Project No:  
2208

Date Plotted:  
August 12, 2022

Date Revised:

Drawing No:



**A2.03**





3 GENERAL NOTES  
A2.04 SCALE 1:200



[illegible]

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL.CA



**NOTES:**

1. MECHANICAL AND ELECTRICAL FIXTURES ARE SHOWN ON THESE DRAWINGS FOR THE PURPOSE OF COORDINATION BETWEEN TRADES ONLY. ANY DISCREPANCIES WITH MECHANICAL / ELECTRICAL FIXTURES BETWEEN THE ARCHITECTURAL AND MECHANICAL / ELECTRICAL DRAWINGS THE MECHANICAL AND ELECTRICAL DRAWINGS SHALL GOVERN. THE GENERAL CONTRACTOR SHALL REPORT ALL DISCREPANCIES BETWEEN THE REFLECTED CLING PLAN AND MECHANICAL / ELECTRICAL DRAWINGS TO THE CONSULTANT AND RECEIVE A RESPONSE BEFORE PROCEEDING WITH THE WORK.
2. ALL STRUCTURE INDICATED ON THESE DRAWINGS ARE FOR COORDINATION PURPOSES ONLY. REFER TO STRUCTURAL DRAWINGS FOR ALL STRUCTURAL WORK.
3. UNLESS OTHERWISE NOTED, WHERE EXPOSED STRUCTURE PAINTED IS INDICATED, ASSUME ALL STRUCTURAL DECK, JOISTS, BEAMS, ALL OTHER MISC. STRUCTURE TO BE PAINTED ALONG WITH ALL ELECTRICAL ITEMS SHALL BE PAINTED THE SAME COLOUR. DO NOT PAINT DUCTWORK.
4. REFER TO ROOM FINISH SCHEDULE FOR ALL OTHER NOTES.

1 MAIN FLOOR REFLECTED CEILING PLAN  
A3.01 SCALE 1:100

Drawing No:

### A3.01

[illegible]

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2391 CRITCHLEYHILL.

project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON

Drawing Title:  
MEZZANINE REFLECTED CEILING PLAN

Drawn By:	Checked By:
-----------	-------------

Scale: 1:100	Project No: 2208
-----------------	---------------------




Date Plotted:  
August 12, 2022





Date Revised:

Drawing No:

## A3.02

1 MEZZANINE REFLECTED CEILING PLAN  
A3.02 SCALE 1:100





Revision	Date	Issued For	Firm and Tender
0			
1	07.28.2022		

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY, ONTARIO 705.995.2391 CRITCHLEYHILL.CA

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON

Drawing Title:  
BUILDING SECTIONS

Drawn By:  
KSH

Checked By:  
ICH

Scale:  
1:100


Project No:  
2208

Date Plotted:  
August 12, 2022




Date Revised:

Drawing No:

**A5.01**



Drawn By: KSH	Checked By: ICH
Scale: AS NOTED	Project No: 2208
Date Plotted: August 12, 2022	
Date Revised:	
Drawing No: <b>A5.02</b>	



Revision	Date
0	07/28/2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE  
CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2381 CRITCHLEYHILL.CA

Project:  
**TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
2 Penn Lake Road  
Marathon, ON

Drawn By:  
KSH

Checked By:  
ICH




Scale:  
1:20

Project No:  
2208

Date Plotted:  
August 12, 2022

Date Revised:

Drawing No:  
**A5.03**










Revision	Date	Issued For Permit and Tender
0	07/28/2022	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE  
CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY, ONTARIO 705.995.2391 CRITCHLEYHILL.CA

Project: <b>TOWN OF MARATHON NEW PUBLIC WORKS FACILITY</b> 2 Penn Lake Road Marathon, ON	
Drawn By: KSH	Checked By: ICH
Scale: 1:20	Project No: 2208
Date Plotted: August 12, 2022	
Date Revised:	
Drawing No: <b>A5.04</b>	



Revision	
Date	Issued For Permit and Tender
07/28/2022	0

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.

ONTARIO ASSOCIATION OF ARCHITECTS  
IAN HILL  
LICENCE 6989

CRITCHLEY HILL ARCHITECTURE  
CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY, ONTARIO 705.995.2381 CRITCHLEYHILL.CA

Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON

Drawing Title: WALL SECTION SECTION DETAILS

Drawn By: KSH  
Scale: AS NOTED  
Date Plotted: August 12, 2022  
Date Revised:

Checked By: ICH  
Project No: 2208


Drawing No: A5.05





CASEWORK NOTES:


1. CAULK AND SEAL ALL BACKSPLASHES. CAULK PERIMETER OF ALL CABINETS AGAINST WALLS.
2. PROVIDE +/- 25MM OR AS NOTED FILLER STRIP TO MATCH ADJACENT CASEWORK AT ALL SIDEWALLS. PROVIDE FILLER AT INSIDE CORNERS TO ALLOW FOR DOORS TO FULLY SWING OPEN. FILLERS AT INSIDE CORNERS TO BE CO-PLANAR WITH DOORS. WRAP ALL FILLERS ON UNDERSIDE OF UPPER CASEWORK BACK TO WALL.
3. UNLESS OTHERWISE NOTED ALL ENDS OF COUNTERS, CABINETS, GABLES, BACKSPLASHES, KICKPLATES, DOORS AND FILLER PANELS TO BE FINISHED TO MATCH ADJACENT CASEWORK.
4. PROVIDE ALL CUTOUTS FOR MISCELLANEOUS OPENINGS AS REQUIRED BY ALL TRADES. COORDINATE LOCATION AND SIZES FOR CUTOUTS WITH ALL TRADES BEFORE CUTTING OPENINGS. FINISH EXPOSED EDGES TO MATCH ADJACENT CASEWORK. COORDINATE WITH OTHER TRADES ALL REQUIRED ROUGH OPENINGS FOR FIXTURES BY OTHERS TO BE MOUNTED WITHIN CASEWORK.
5. ENSURE CABINETS ARE COORDINATED TO RECEIVE ALL EQUIPMENT AS PER EQUIPMENT LIST AND REQUIREMENTS. COORDINATE AS REQUIRED WITH OWNER ALL OWNER SUPPLIED EQUIPMENT TO ENSURE PROPER CLEARANCES PRIOR TO FABRICATION.
6. UNLESS OTHERWISE NOTED ON DRAWINGS ALL CASEWORK BODY MATERIALS ARE ASSUMED TO BE MELAMINE ON PARTICLE CORE BOARD (MCP). SEE SPECIFICATIONS.
7. SEE CASEWORK DETAILS FOR CONSTRUCTION OF ALL COUNTER TOPS. IF NOT NOTED ASSUME ALL COUNTERTOPS AND DESKTOPS TO BE POST FORMED PLASTIC LAMINATE WITH 180° WRAP NOSING.
8. UNLESS OTHERWISE NOTED, CABINET BASES TO BE FINISHED WITH WALL BASE BY DIVISION 09 00 00 AS PER ROOM FINISH SCHEDULE.
9. SITE MEASURE ALL DIMENSIONS PRIOR TO FABRICATION AND REPORT ANY INCONSISTENCIES TO THE ARCHITECT.
10. ALL FASTENERS TO BE CONCEALED. IF FASTENINGS MUST OCCUR IN AN EXPOSED CONDITION COUNTERSINK FASTENER AND PLUG WITH COLOUR MATCH FASTENER PLUG SUITABLE FOR THE APPLICATION.
11. ANY DISCREPANCIES BETWEEN THESE NOTES AND THE SPECIFICATIONS, THE SPECIFICATIONS SHALL GOVERN.



SECTION  
-SOLID DOORS  
-ADJUSTABLE SHELVES

UC1


-SOLID DOORS  
-ADJUSTABLE SHELVES (1)  
-ABOVE SINK



SECTION  
-SOLID DOORS  
-ADJUSTABLE SHELF  
-ABOVE FRIDGE


UC2

UC3




SECTION  
-SOLID DOORS  
-MICROWAVE SHELF

UC4




SECTION  
-P.LAM. SUPPORT BRACKET

SB1




SECTION  
-LOCKER BASE

LB1




MB1




SECTION  
-SOLID DOORS  
-ADJUSTABLE SHELVES

LC1




SECTION  
-SOLID DOORS  
-ADJUSTABLE SHELVES

LC2




SECTION  
-SOLID PANEL  
-SOLID DOORS

LC3




SECTION  
-FOUR (4) DRAWERS  
-HEAVY DUTY DRAWER SLIDES

LC4



SECTION  
-OPEN SPACE LOWER CABINET  
-DISHWASHER (N.I.C.)

LC5



Revision	Date	Issued For Tender & Permit
0	08.12.2022	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE  
CRITCHLEY HILL ARCHITECTURE INC.  
NORTH BAY ONTARIO 705.995.2381 CRITCHLEYHILL.CA

Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
2 Peim Lake Road  
Marathon, ON  
Drawing Title: **CASEWORK DETAILS**

Drawn By: **KSH**  
Checked By: **ICH**

Scale: **1:50**  
Project No: **2208**

Date Plotted: **August 10, 2022**  
Date Revised: **AUGUST 12, 2022**

Drawing No: **A7.02**

GENERAL

- ## STRUCTURAL STEEL

- STEEL DECK

- MASONRY

- ## EXCAVATION

- ## FOUNDATIONS

- CONCRETE

- ### CONCRETE PROPERTIES













CRANE

BASE PLATE SCHEDULE:



- Drawing name: Y:\Projects\2022\22-098 CHAI, Marathon Public Works Building\Drawings\20-000-65 Structural\CAD\Current\22-098 Marathon Public Works.dwg







Revision	Date
ISSUED FOR TENDER & PERMIT	AUG. 12, 2022
ISSUED FOR FINAL REVIEW	JUL. 27, 2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY 2 Fern Lake Road Marathon, ON	Drawing Title: Foundation Sections & Details
Drawn By: MS	Checked By:
Scale: AS SHOWN	Project No: 22-098
Date Plotted: Aug 11, 2022	Date Revised: Aug. 12, 2022
Drawing No: <b>S-3</b>	




Revision	Date
ISSUED FOR TENDER & PERMIT	AUG. 12, 2022
ISSUED FOR FINAL REVIEW	JUL. 27, 2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY 2 Fern Lake Road Marathon, ON	
Drawn By: MS	Checked By:
Scale: AS SHOWN	Project No: 22-098
Date Plotted: Aug 11, 2022	
Date Revised: Aug. 12, 2022	
Drawing No: <b>S-4</b>	




**A**  
UPPER ROOF FRAMING PLAN  
1:100

+L - + L102x102x6 TRIMMER L U/N  
MC - MOMENT CONNECTION  
CANT. - CANTILEVER BEAM / O.W.S.J.  
CONT. - CONTINUOUS  
- do - DITTO  
KB - KNEE BRACE  
T.J. - TIE JOIST


DESIGN LOADS (kPa)  
DEAD LOAD = 1.5  
SNOW LOAD = 3.3

C-1  
H53203x203x9.5 COL.  
C-2  
H53152x152x9.5 COL.  
CAP ALL COLUMNS w  
6mm PLATE


-SLOPE FOR ROOF  
-100 DROP JOIST SHOE




**1**  
SECTION  
1:16




**2**  
SECTION  
1:16




**3**  
SECTION  
1:16



**4**  
SECTION  
1:16



**5**  
SECTION  
1:16



Revision	Date
ISSUED FOR TENDER & PERMIT	AUG. 12, 2022
ISSUED FOR FINAL REVIEW	JUL. 27, 2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE

TBT ENGINEERING  
CONSULTING GROUP

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Fern Lake Road  
Marathon, ON


Drawing Title:  
Upper Roof Framing Plan and Details

Drawn By: MS  
Scale: AS SHOWN  
Checked By:  
Project No: 22-098

Date Plotted:  
Aug 11, 2022

Date Revised:  
Aug. 12, 2022

Drawing No:  
**S-5**




A MEZZANINE FRAMING PLAN  
S-6 1:100


+L - + L4x4x1/4" TRIMMER L U/N  
M.C. - MOMENT CONNECTION  
CANT. - CANTILEVER BEAM / O.W.S.J.  
CONT. - CONTINUOUS  
- do - DITTO  
KB - KNEE BRACE

DESIGN LOADS (kPa)  
DEAD LOAD = 1.5 kPa  
LIVE LOAD = 7.2 kPa


C-1 H55 203x203x9.5 COL.  
C-2 H55 152x152x9.5 COL.  
C-3 W 200 x 59 COL.  
CAP ALL H55 COLUMNS  
w 6mm PLATE




B LINTEL DETAIL 'L1'  
S-6 1:20




C LINTEL DETAIL 'L2'  
S-6 1:20



2 WALL SECTION  
S-6 1:16



1 WALL SECTION  
S-6 1:16




Revision	Date	Issued For Tender & Permit	Issued For Final Review
		Aug. 12, 2022	JUL. 27, 2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE




Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Fern Lake Road  
Marathon, ON

Drawing Title:  
Mezzanine Floor Plan


Drawn By: MS	Checked By:
Scale: AS SHOWN	Project No: 22-098
Date Plotted: Aug 11, 2022	Date Revised: Aug. 12, 2022

Drawing No:


S-6




A SALT STORAGE FOUNDATION PLAN  
S-7 1:50



B FUEL OIL STORAGE SECTION  
S-7 N.T.S.



I SECTION  
S-7 1:16



II SECTION  
S-7 1:16

GENERAL:


- DO NOT SCALE DRAWINGS.
- DESIGN, CONSTRUCTION, MATERIALS AND WORKMANSHIP OF THIS PROJECT SHALL COMPLY WITH THE ONTARIO BUILDING CODE, (ONTARIO REGULATION 413/12).
- CONTRACTOR SHALL VISIT SITE TO BECOME FAMILIAR WITH THE FULL SCOPE OF WORK PRIOR TO SUBMITTING BID.
- CONSTRUCTION METHODS, EQUIPMENT, AND ALL OPERATIONS SHALL CONFORM WITH ALL APPLICABLE REGULATIONS, ACTS AND BY-LAWS IN FORCE TO ENSURE THE SAFETY OF THE WORK AND THE CONTRACTOR'S PERSONNEL AND OTHERS AT ALL TIMES.
- PROVIDE AND TAKE RESPONSIBILITY FOR ALL TEMPORARY BRACING AND SHORING.
- WORK NOT INDICATED ON A PART OF THE DRAWINGS BUT REASONABLY IMPLIED TO BE SIMILAR TO THAT SHOWN AT CORRESPONDING PLACES SHALL BE PROVIDED.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND REPORT ANY DISCREPANCY BEFORE PROCEEDING WITH THE WORK.
- SUBMIT SHOP DRAWINGS STAMPED BY A PROFESSIONAL ENGINEER LICENSED IN THE PROVINCE OF ONTARIO ACCEPTING RESPONSIBILITY FOR THE DESIGN.

CONCRETE:

- ALL CONCRETE MATERIALS AND METHODS OF CONSTRUCTION SHALL COMPLY WITH CAN/CSA-A23.1-09 (R2014) AND CSA-A23.2-09(R2014).
- REINFORCEMENT SHALL BE DEFORMED BILLETS STEEL BARS AND CONFORM TO CAN/CSA G30.18-09, GRADE 400 MPA. WIRE MESH SHALL CONFORM TO CSA G30.5 YIELD POINT 385MPA.
- FRESHLY PLACED CONCRETE TO BE CURED AND PROTECTED TO CONFORM TO CLAUSE 21 OF CSA/CAN3-A23.1-09(R2014).
- REINFORCING STEEL SHOP DRAWINGS TO BE SUBMITTED FOR ENGINEER'S APPROVAL.
- DURING COLD WEATHER CONSTRUCTION ALL FOUNDATIONS SHALL BE PROTECTED BY 1200MM OF EARTH OR MATERIALS WITH AN EQUIVALENT INSULATING VALUE.
- CONCRETE THAT HAS BEEN ON THE READY MIX TRUCK LONGER THAN 1.5 HOURS SHALL NOT BE USED.
- CONTRACTOR NOT TO INSTALL EQUIPMENT OR BUILDING ON THE SLAB OR FOUNDATIONS UNTIL CONCRETE HAS ACHIEVED SUFFICIENT STRENGTH TO WITHSTAND THE LOADS APPLIED.
- CONCRETE EXPOSED TO WEATHER OR TO DEICER SALTS SHALL HAVE 5 TO 8% AIR ENTRAINMENT.
- CONCRETE TESTING TO CSA STANDARD A23.1 FOR ALL CONCRETE WORK AS DIRECTED BY CONSULTANT.
- NO SLEEVES, PIPES, HOLES OR NOTCHES SHALL BE PLACED THROUGH WALLS, PIERS OR SLABS EXCEPT AS SHOWN ON THE STRUCTURAL DRAWINGS APPROVED BY THE ENGINEER.
- ALL LAP SPICES TO BE CLASS B TENSION SPICES, PROVIDE 1200MM LAP SPICES FOR ALL WALL STRIP FOOTING BARS PROVIDE 300MM LAP SPICES FOR FOUNDATION WALL TOP BARS AND 600MM LAP SPICES FOR FOUNDATION WALL BOTTOM BARS.
- WHEREVER OPENINGS INTERRUPTING ONE OR MORE REINFORCING BARS OCCUR IN SLABS OR WALLS, PROVIDE ADDITIONAL REINFORCING STEEL EQUAL TO THE REINFORCING STEEL DISPLACED BY THE OPENING UNLESS OTHERWISE SHOWN. DISTRIBUTE REINFORCING EQUALLY ON EITHER SIDE OF THE OPENING AND EXTENDING THE FULL SPAN LENGTH.
- SEAL CONCRETE W/ TWO COATS CONCRETE SEALER IN ACCORDANCE W/ MANUFACTURER'S INSTRUCTIONS.

CONCRETE PROPERTIES

COMPONENT	28 DAY STRENGTH	CEMENT TYPE	AGGREGATE SIZE	EXPOSURE CLASS	AIR CONTENT	SLUMP +/- 10mm	W/C RATIO	COVER TO REINF.
FOUNDATION / SLAB	35 MPa	10	20mm	C-1	5-8%	80mm	.40	60mm



Revision	Date	Issued For Tender & Permit	Issued For Final Review
		Aug. 12, 2022	JUL. 27, 2022

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
2 Penn Lake Road  
Marathon, ON  
Drawing Title:  
Salt Storage Shelter Foundations  
Fuel Oil Tank Foundation


Drawn By:  
MS

Scale:  
AS SHOWN

Date Plotted:  
Aug 11, 2022

Date Revised:  
Aug. 12, 2022


Drawing No:  
S-7




MAIN FLOOR PLAN -SANITARY LAYOUT  
SCALE: 1:100

MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

- GENERAL PLUMBING NOTES:**
1. PRIOR TO COMMENCING WORK, CONTRACTOR TO COORDINATE WITH SITE PLAN FOR LOCATION OF PLUMBING CONNECTIONS TO BUILDING.
  2. CO-ORDINATE SANITARY, DOMESTIC WATER, STORM DRAINAGE AND GAS PIPING WITH DISTRIBUTION DUCTWORK, EQUIPMENT, HYDRONIC PIPING, LIGHTING LAYOUT, COMPRESSED AIR, REFRIGERANT PIPING, CONDENSATE PIPING, BUILDING STRUCTURE, FOUNDATION AND REQUIRED CEILING HEIGHTS.
  3. FOR DOMESTIC HOT AND COLD WATER CONNECTION SIZES TO FIXTURES REFER TO CHART ON DRAWING M200. PROVIDE REDUCERS WHERE REQUIRED TO SUIT FIXTURE CONNECTIONS SIZES. PROVIDE STAINLESS STEEL BRAIDED FLEX HOSE FOR ALL FIXTURE CONNECTIONS WHERE APPLICABLE.
  4. WHERE CEILING IS TO BE USED AS RA PLENUM, ALL MATERIALS USED IN CEILING SPACE TO MEET (OR EXCEED) MINIMUM SMOKE AND FLAME SPREAD RATINGS AS DEFINED IN O.B.C.
  5. THERMOSTATIC MIXING VALVES (TMV-X) TO BE INSTALLED WITHIN MILLWORK UNLESS NOTED OTHERWISE. FIELD ADJUST ALL THERMOSTATIC MIXING VALVES TO 43.3°C
  6. FOR MECHANICAL SPECIFICATIONS, EQUIPMENT LIST AND SEQUENCE OF OPERATIONS REFER TO M700 SERIES DRAWINGS.
  7. INSULATE ALL PIPING AS PER MECHANICAL SPECIFICATIONS ON DRAWING M700.
  8. REFER TO ARCHITECTURAL PLANS FOR FIRE SEPARATIONS. ALL PENETRATIONS TO BE SEALED TO MAINTAIN INTEGRITY OF FIRE RATING. PROVIDE FIRE DAMPER OR ULC LISTED INTUMESCENT FIRESTOP ASSEMBLY FOR PIPING PENETRATING REQUIRED SEPARATIONS.
  9. COORDINATE SANITARY PIPING AND DOMESTIC WATER PIPING WITH EQUIPMENT, DISTRIBUTION DUCTWORK, HYDRONIC LAYOUTS, REFRIGERANT LINES AND BUILDING STRUCTURE.
  10. PROVIDE ADEQUATE SUPPORT FOR ALL EQUIPMENT AND PIPING. PROVIDE SERVICE CLEARANCE FOR ALL EQUIPMENT AS PER MANUFACTURERS RECOMMENDATIONS.
  11. CORE ALL OPENINGS IN NEW BUILDING CONSTRUCTION AS REQUIRED FOR ROUTING OF NEW PIPING.
  12. MOUNT RECESSED TRAP SEAL PRIMER MANIFOLDS AT 305mm AFF.
  13. PROVIDE ONE PIECE ESCUTCHEONS FOR ALL SANITARY AND WATER PIPING WALL AND FINISHED FLOOR AND CABINET PENETRATIONS.
  14. PROVIDE NON-RATED OR FIRE RATED ACCESS DOORS TO MAINTAIN ACCESS TO MECHANICAL EQUIPMENT AND PIPING WHERE REQUIRED.




MEZZANINE PLAN -SANITARY LAYOUT  
SCALE: 1:100



PROJECT NORTH

Revision	Date
0	JULY 28/22

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



D. W. SHALLEY  
JULY 28/22  
PROVINCE OF ONTARIO

CRITCHLEY HILL  
ARCHITECTURE


TBT ENGINEERING  
CONSULTING GROUP

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario

Drawing Title: MAIN FLOOR AND MEZZANINE SANITARY PLANS  
AND GENERAL PLUMBING NOTES

Drawn By: ER	Checked By: DS
Scale: AS NOTED	Project No: 22-098
Date Plotted:	
Date Revised: JULY 2022	
Drawing No: <b>M100</b>	





**21**  
**M102** DETAIL -TRENCH AN PIT WATER RECYCLE SYSTEM  
SCALE = N.T.S.

**24**  
**M102** DETAIL -OIL / SEDIMENT INTERCEPTOR 'OS1'  
SCALE = N.T.S.

**DWV PIPING ISOMETRIC 'B'**  
SCALE: N.T.S.

**NOTE:**  
FOR GENERAL PLUMBING NOTES, REFER TO DRAWING M100

MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

Revision	Date	Issued For Permit and Tender
0	JULY 28/22	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE  
**TBT ENGINEERING**  
CONSULTING GROUP

Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario  
Drawing Title: **DWV PIPING ISOMETRIC AND DETAILS**


Drawn By: **ER**  
Checked By: **DS**  
Scale: **AS NOTED**  
Project No: **22-098**

Date Plotted:

Date Revised:  
JULY 2022


Drawing No:

**M102**




LP GAS SERVICE -SITE PLAN

SCALE: 1:750



20 DETAIL -TYPICAL I.P. GAS PIPE BEDDING DETAIL

SCALE: N.T.S.




24 DETAIL PWL DOWNSPOUT

Σ1	DETAIL
M400	CONF: NTC

**NOTE:**  
FOR GENERAL PLUMBING NOTES, REFER TO DRAWING M100

MECHANICAL DRAWINGS SHALL BE READ IN  
CONJUNCTION WITH ALL DESIGN DRAWINGS.



	JULY 28 / 22	ISSUED FOR PERMIT AND TENDER	0
		Date	Revision

do not scale from this drawing. The constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE



**TBT ENGINEERING  
CONSULTING GROUP**

**TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

LP GAS SERVICE SITE PLAN AND DETAILS


Drawn By: ER	Checked By: DS
Scale: AS NOTED	Project No: 22-098
Date Plotted:	

ate Revised:  
JULY 2022

Drawing No:

M103






**MAIN FLOOR PLAN -HYDRONIC LAYOUT**  
SCALE: 1:100


MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

**GENERAL HYDRONIC NOTES:**

- FOR MECHANICAL SPECIFICATIONS, EQUIPMENT LIST AND SEQUENCE OF OPERATIONS REFER TO DRAWING M700 SERIES DRAWINGS.
- INSULATE HYDRONIC PIPING AS PER MECHANICAL SPECIFICATIONS ON DRAWING M700.
- FOR CIRCUIT BALANCING VALVE (ABV-X) AND CONTROL/BALANCING VALVES (CBV-X) SIZES AND FLOWS, REFER TO SCHEDULES ON DRAWING M704. PROVIDE REDUCERS TO SUIT VALVE SIZES AS REQUIRED.
- CO-ORDINATE MANIFOLDS, HYDRONIC AND GAS PIPING WITH SANITARY, DOMESTIC WATER, STORM DRAINAGE, GAS PIPING, DISTRIBUTION DUCTWORK, EQUIPMENT, LIGHTING LAYOUT, COMPRESSED AIR, REFRIGERANT, CONDENSATE PIPING, BUILDING STRUCTURE AND REQUIRED CEILING HEIGHTS.
- PROVIDE NON-RATED OR FIRE RATED ACCESS DOORS TO MAINTAIN ACCESS TO MECHANICAL EQUIPMENT AND PIPING WHERE REQUIRED.
- IN-SLAB HYDRONIC HEATING SUB-TRADE MUST CO-ORDINATE WITH CONCRETE/SLAB, MASONRY AND WALL TRADES FOR MANIFOLDS AND IN-SLAB PIPING INSTALLATIONS.
- ALL GHS/GHR PIPING TAKE-OFFS TO MANIFOLDS ARE 19# UNLESS NOTED OTHERWISE. PROVIDE DIELECTRIC UNIONS AT CONNECTIONS OF DISSIMILAR METALS.
- ALL MANIFOLDS ARE RECESSED. MANIFOLDS TO BE EASILY ACCESSIBLE THROUGH ACCESS DOORS ON SIDE NOTED BY SYMBOL. ACCESS DOORS TO HAVE ARCHITECTURAL FINISH TO SUIT WALL IN WHICH THEY ARE MOUNTED.
- IN-SLAB HEATING MANIFOLD CABINETS SHALL BE PROVIDED WITH TAMPERPROOF FASTENERS. PROVIDE CONTROL VALVE OR THERMAL ACTIVATED TELESTATS FOR EACH MANIFOLD OR MANIFOLD CIRCUIT AS REQUIRED. CONNECT TO DDC SYSTEM. FOR MANIFOLD REQUIREMENTS REFER TO DETAIL '1/M301'.
- PROVIDE MANUAL HIGH POINT AIR VENTS WHERE REQUIRED.
- USE FTS PLENUM RATED CABLING WHERE INSTALLED IN PLENUM SPACES. WIRING IN ACCESSIBLE CEILING SPACE TO BE SUPPORTED BY TRAY OR P-CLIPS. CABLES TO BE STRAPPED USING VELCRO, TIE STRAPS ARE NOT ACCEPTABLE. INSTALL WIRING PARALLEL TO BUILDING LINES. LABEL WIRING AT EACH END AND EQUIPMENT TO CONFORM WITH INDUSTRY STANDARDS.
- PROVIDE ADEQUATE SUPPORT FOR ALL EQUIPMENT AND PIPING. PROVIDE SERVICE CLEARANCE FOR ALL EQUIPMENT AS PER MANUFACTURERS RECOMMENDATIONS.
- ALL PENETRATIONS TO BE SEALED TO MAINTAIN INTEGRITY OF FIRE RATING. PROVIDE ULC LISTED INTUMESCENT FIRESTOP ASSEMBLY FOR PIPING AND DUCTWORK PENETRATING REQUIRED SEPARATIONS.
- PROVIDE NON-RATED OR FIRE RATED ACCESS DOORS TO MAINTAIN ACCESS TO MECHANICAL EQUIPMENT AND PIPING WHERE REQUIRED.
- REFER TO ARCHITECTURAL PLANS FOR FIRE SEPARATIONS. ALL PENETRATIONS TO BE SEALED TO MAINTAIN INTEGRITY OF FIRE RATING. PROVIDE FIRE DAMPER OR ULC LISTED INTUMESCENT FIRESTOP ASSEMBLY FOR DUCTWORK AND PIPING PENETRATING REQUIRED SEPARATIONS.



**MEZZANINE PLAN -HYDRONIC LAYOUT**  
SCALE: 1:100



PROJECT NORTH

Revision	Date	Issued For Permit and Tender
0	JULY 28/22	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE

**TBT ENGINEERING**  
CONSULTING GROUP

Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

Drawing Title: **MAIN FLOOR AND MEZZANINE HYDRONIC PLANS  
AND GENERAL HYDRONIC NOTES**

Drawn By: ER  
Checked By: DS

Scale: AS NOTED  
Project No: 22-098

Date Plotted:


Date Revised:  
JULY 2022

Drawing No:

**M300**







	JULY 28 / 22	ISSUED FOR PERMIT AND TENDER	0
	Date	Revision	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE

**TBT ENGINEERING**  
CONSULTING GROUP

Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

---


Drawing Title: **BOILER PIPING AND DOMESTIC HOT WATER  
PIPING ISOMETRICS**

Drawn By: ER	Checked By: DS
Scale: AS NOTED	Project No: 22-098


Data Reviewed:

Drawing No:  
**M303**





ROOF PLAN -HVAC LAYOUT  
SCALE: 1:100



SECTION -HVAC  
SCALE: 1:50

NOTE:  
FOR GENERAL HVAC NOTES, REFER TO DRAWING M400

MECHANICAL DRAWINGS SHALL BE READ IN  
CONJUNCTION WITH ALL DESIGN DRAWINGS.

PROJECT NORTH

0

ISSUED FOR PERMIT AND TENDER

DATE

Revision

DATE

Do not scale from this drawing. The Contractor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.

D. W. SHALLEY

PROFESSIONAL ENGINEER

PROVINCE OF ONTARIO

July 28/22

CRITCHLEY HILL  
ARCHITECTURE

TBT ENGINEERING  
CONSULTING GROUP

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario

Drawing Title: ROOF HVAC PLAN AND SECTION

Drawn By: ER  
Scale: AS NOTED  
Date Plotted:

Checked By: DS  
Project No: 22-098

Date Revised: JULY 2022


Drawing No: M401



**NOTE:**  
FOR GENERAL HVAC NOTES, REFER TO DRAWING M100


## M402






**MAIN FLOOR PLAN -COMPRESSED AIR LAYOUT**  
SCALE: 1:100

- NOTES:**
1. SLOPE COMPRESSED AIR PIPING HEADERS TOWARDS DRIP LEGS
  2. NEW COMPRESSED AIR PIPING TO BE PNEUMATICALLY TESTED AT 210 PSIG AS PER PARA. 13.5.1 TO 137.5.5 OF ASME B31.1 - LATEST EDITION.
  3. NEW COMPRESSED AIR PIPING SYSTEM SHALL BE INSPECTED BY THE TSSA INSPECTOR. CONTRACTOR TO CARRY THE COSTS OF ALL REQUIRED INSPECTIONS BY THE TSSA.




**PARTIAL MECH. SHOP MEZZ. 202 PLAN -COMPRESSED AIR LAYOUT**  
SCALE: 1:50

MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.



**MEZZANINE PLAN -COMPRESSED AIR LAYOUT**  
SCALE: 1:100



PROJECT NORTH

Revision	Date	Issued For Permit and Tender
0	JULY 28/22	

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



**CRITCHLEY HILL**  
ARCHITECTURE

**TBT ENGINEERING**  
CONSULTING GROUP

Project: **TOWN OF MARATHON NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

Drawing Title: **MAIN FLOOR AND MEZZANINE COMPRESSED AIR PLANS**


Drawn By: **ER** Checked By: **DS**

Scale: **AS NOTED** Project No: **22-098**


Date Plotted:

Date Revised: **JULY 2022**


Drawing No: **M500**




**5** DETAIL -TYPICAL AIR DROP  
M501 SCALE = N.T.S.




**6** DETAIL -TYPICAL DRIP LEG  
M501 SCALE = N.T.S.




**7** DETAIL -DRIP LEG IN Rm. 110  
M501 SCALE = N.T.S.




**8** DETAIL -TYPICAL HOSE REEL AIR DROP  
M501 SCALE = N.T.S.



**22** DETAIL -VEHICLE LIFT AIR DROP  
M501 SCALE = N.T.S.



**23** DETAIL -WASHBAY EQUIPMENT OZONE GENERATOR AIR DROP  
M501 SCALE = N.T.S.



**J** SECTION  
M501 SCALE: NTS

Revision	Date
0	JULY 28/22

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario


Drawing Title:  
COMPRESSED AIR SYSTEM DETAILS

Date Plotted:


Date Revised:  
JULY 2022

Drawing No:


**M501**




9 DETAIL -DOMESTIC WATER METER DETAIL  
M600 SCALE = N.T.S.




10 DETAIL -EYEWASH THERMOSTATIC MIXING VALVE  
M600 SCALE = N.T.S.




11 DETAIL -CONDENSATE DRAIN TRAP  
M600 SCALE = N.T.S.




12 DETAIL -TYPICAL CABINET UNIT HEATER PIPING  
M600 SCALE = N.T.S.




13 DETAIL -TYPICAL HEATING COIL PIPING  
M600 SCALE = N.T.S.




14 DETAIL -TYPICAL UNIT HEATER PIPING  
M600 SCALE = N.T.S.




15 DETAIL -VAV TERMINAL UNIT TYPICAL INSTALLATION  
M600 SCALE = N.T.S.



17 DETAIL -AIR CONTROL VALVE TYPICAL INSTALLATION  
M600 SCALE = N.T.S.



18 DETAIL -HRU-X HYDRONIC HEATING COIL PIPING VESTIBULE  
M600 SCALE = N.T.S.




19 DETAIL -FIRE DAMPER INSTALLATION  
M600 SCALE = N.T.S.

MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

Revision	Date
0	JULY 28/22

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario  
Drawing Title:  
DETAILS

Drawn By:  
ER  
Scale:  
AS NOTED  
Date Plotted:

Checked By:  
DS  
Project No:  
22-098

Date Revised:  
JULY 2022

Drawing No:

M600

## M700



EQUIPMENT LIST -CONTINUED

HR-1 HOSE REEL (4 REQ'D)	REELCRAFT MODEL 7850 OLP PREMIUM DUTY SPRING RETRACTABLE HOSE REEL SUPPLIED COMPLETE WITH FORMED HOSE, GRADE 300L REEL, GRADE 300L REEL, GRADE 300L FINISH, FULL FLOW STRESS FREE SWIVEL DESIGN, ADJUSTABLE GUIDE ARM, SWIVEL ASSEMBLY, WALL MOUNTED UNIVERSAL SWING BRACKET, 13mm NPT(F) REEL OUTLET, 13mmø I.D. x 15.24 METER LONG HOSE WITH 13mmø NPT(F) INLET AND 9.5mmø NPT(M) OUTLET, 65.5°C HOSE TEMPERATURE RATING, ADJUSTABLE BUMPER STOP, 340° PIVOT BASE, 13mmø x 610mm LONG INLET HOSE AND M.A.W.P.: 2070 kPa (300 PSI).
AD-1 ACCESS DOOR	ACUDOR MODEL UP-5000 UNIVERSAL FLUSH MOUNT ACCESS DOOR SUPPLIED COMPLETE WITH FLUSH TO FRAME STEEL DOOR WITH ROUNDED SAFETY CORNERS, STEEL ONE PIECE TRIM FLANGE, CONTINUOUS CONCEALED HINGE, STAINLESS STEEL SLOTTED SCREWDRIVER CAM LATCH, WHITE ALKYO BAKED ENAMEL PRIME COAT, SIZE 405mm X 405 mm AND UNDER -16 GAUGE DOOR, 18 GAUGE MOUNTING FRAME, ABOVE 405mm X 405mm -14 GAUGE DOOR, 16 GAUGE MOUNTING FRAME, PRIME AND PAINT TO MATCH NEW GYPSUM BOARD CEILING.

COMMISSIONING

1. COMMISSION SYSTEM OPERATION TO ENSURE THE PROPER OPERATION OF ALL COMPONENTS. BALANCE AIR FLOWS TO THE QUANTITIES SHOWN ON DRAWINGS. BALANCING CONTRACTOR SHALL ASSIST THE CONTROLS CONTRACTOR IN THE SETUP AND CALIBRATION OF THE AIR TERMINAL UNITS AND AIR CONTROL VALVES.
2. COMMISSION SYSTEM OPERATION TO VERIFY THE PROPER OPERATION OF ALL NEW EQUIPMENT. COMMISSIONING WORK TO BE PERFORMED IN CONJUNCTION WITH THE DESIGN CONSULTANT TO VERIFY THE PROPER FUNCTIONING OF THE MECHANICAL SYSTEMS IN ACCORDANCE WITH THE SEQUENCE OF OPERATIONS.
3. PROVIDE END USER TRAINING SESSION INCLUDING SYSTEM DEMONSTRATION, MAINTENANCE REQUIREMENTS AND CONTROL SYSTEM REVIEW.
4. DURING CONSTRUCTION KEEP AN ACCURATE RECORD OF ALL DEVIATIONS BETWEEN THE WORK SHOWN ON THE DESIGN DRAWINGS AND THAT WHICH IS INSTALLED. PROVIDE AS-BUILT DRAWINGS TO REFLECT THE ACTUAL INSTALLED CONFIGURATION AND SUBMIT TO THE DESIGN ENGINEER.
5. PROVIDE OPERATION AND MAINTENANCE MANUALS FOR ALL EQUIPMENT. O&M MANUALS SHALL BE SUBMITTED IN TWO FORMATS; ONE (1) BOUND HARD COPY AND ONE (1) ELECTRONIC FORMAT ON CD. ELECTRONIC FORMAT SHALL BE COLLATED COMPLETE WITH INDEX AND SECTION DIVIDERS IN THE SAME MANNER AS BOUND HARD COPY. SUBMIT O&M MANUALS TO THE DESIGN ENGINEER.

BUILDING CONTROLS

PROVIDE NEW WEB ENABLED DDC SYSTEM COMPLETE WITH SUPERVISORY CONTROLLER, SUB CONTROLLERS, FIELD DEVICES, COLOUR GRAPHICAL OPERATING SOFTWARE AND UPS. PROVIDE INTEGRAL DISPLAY WITH PUSHBUTTON INTERFACE FOR ALL DDC FIELD CONTROLLERS TO AID WITH TROUBLE SHOOTING OF EQUIPMENT. PROGRAM THE DDC SYSTEM GRAPHICAL OPERATING SOFTWARE TO INCORPORATE ALL HVAC AND BUILDING SYSTEMS EQUIPMENT. DDC GRAPHICS SHALL INCLUDE FLOOR PLANS OF THE BUILDING INDICATING ZONE TEMPERATURES AND HVAC SYSTEMS. HEATING COILS SHALL LINK TO THE GRAPHICAL DATA DISPLAY FOR THE SPECIFIC COMPONENT. PROGRAM SOFTWARE TO PERMIT MONITORING AND EDITING OF ALL SYSTEM VARIABLES, SCHEDULING AND ALARMS IN REAL TIME VALUES. ALL EQUIPMENT ON/OFF FUNCTIONS AND SETPOINTS SHALL BE ADJUSTABLE VIA THE GRAPHICAL OPERATING SOFTWARE DISPLAY FOR THE SPECIFIC COMPONENT. LABEL ALL NEW CONTROL SYSTEM COMPONENTS.

SEQUENCES OF OPERATION

BOILERS B-1, B-2 & B-3 AND MAIN CIRCULATING PUMPS P1a & P1b

WHEN THE OUTDOOR AIR TEMPERATURE DROPS BELOW THE WARM WEATHER SHUTDOWN SETPOINT (18°C) OR ON A CALL FOR HEAT FROM ANY ZONE, THE DDC SYSTEM SHALL ENABLE THE HYDRONIC HEATING LOOP MAIN CIRCULATING PUMPS P1a/P1b AND THE HEATING BOILERS.

ON A CALL FOR HEAT AS SENSED IN THE SYSTEM SUPPLY LINE, THE LEAD HEATING BOILER AND SECONDARY CIRCULATING PUMP SHALL BE ENERGIZED.

THE LEAD PUMP SHALL BE STARTED AND MODULATED TO MAINTAIN THE DIFFERENTIAL PRESSURE SETPOINT 13.7 METERS (45 FT.). DDC SYSTEM SHALL OPERATE PUMPS P1a AND P1b IN A STANDBY CONFIGURATION PROVIDING AUTOMATIC CHANGEOVER BETWEEN LEAD AND LAG PUMP WHEN A FAILURE IS DETECTED. FAILURE OF A CIRCULATING PUMP SHALL GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER. DDC SYSTEM SHALL PROVIDE EQUAL RUN TIME ROTATION AND EXERCISING OF PUMPS DURING A PERIOD OF EXTENDED SHUTDOWN.

THE DDC SYSTEM SHALL OPERATE THE HEATING BOILERS B1 AND B2 IN A LEAD/LAG CONFIGURATION AND MODULATE THE BOILER OUTPUTS TO MAINTAIN THE GLYCOL HEATING LOOP SUPPLY TEMPERATURE AT SETPOINT. ON A REQUIREMENT FOR HEAT AS SENSED IN THE HOT WATER HEATING SYSTEM SUPPLY LINE, LEAD BOILER AND IT'S CIRCULATOR SHALL BE ENERGIZED. IF THE LEAD HEATING BOILER IS UNABLE TO MAINTAIN THE HEATING SYSTEM SUPPLY TEMPERATURE AT SETPOINT, THE LEAD BOILER OUTPUT SHALL BE REDUCED TO 50% AND BOILER B2 SHALL BE STARTED. BOILERS SHALL THEN BE MODULATED IN UNISON AS REQUIRED TO SATISFY THE SUPPLY WATER SETPOINT TEMPERATURE. WHEN THE HEATING PLANT OUTPUT REQUIRED TO SATISFY THE SUPPLY WATER TEMPERATURE SETPOINT DROPS TO 25%, THE LAG BOILER SHALL BE DE-ENERGIZED. LEAD BOILER CIRCULATING PUMP SHALL BE ENERGIZED BY THE INTERNAL BOILER CONTROL SYSTEM ON A CALL FOR HEAT. DDC SYSTEM SHALL RESET THE GLYCOL SUPPLY SETPOINT TEMPERATURE BASED ON AN OUTDOOR AIR RESET SCHEDULE (38.0°C AT 0.0°C TO 43.0°C AT -10.0°C). DDC SYSTEM SHALL MONITOR BOILER ALARM CONTACTS AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF A LOCKOUT CONDITION IS DETECTED.

WHEN THE OUTDOOR TEMPERATURE RISES ABOVE THE WARM WEATHER SHUTDOWN SETPOINT WITH NO CALL FOR HEAT, THE HEATING BOILERS AND CIRCULATING PUMPS ARE DE-ENERGIZED.

GLYCOL FEEDER GF-1

DDC SYSTEM SHALL MONITOR THE GLYCOL FEEDER LOW LEVEL ALARM AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF A LOW LEVEL CONDITION IS DETECTED.

DOMESTIC HOT WATER RECIRCULATION PUMP P2

THE DDC SYSTEM SHALL PROVIDE A WEEKLY SCHEDULE FOR THE OPERATION OF THE DOMESTIC HOT WATER CIRCULATING PUMP. THE CIRCULATOR SHALL RUN CONTINUALLY DURING BUILDING OCCUPIED HOURS.

CLIENT WATER FILLING METER M1

THE DDC SYSTEM SHALL MONITOR THE CLIENT WATER FILL METER PULSE OUTPUTS AND TOTALIZE DAILY AND MONTHLY WATER VOLUME USAGE. DDC SYSTEM SHALL RETAIN CONSUMPTION DATA HISTORY FOR A MINIMUM OF 24 MONTHS.

ROOFTOP AIR HANDLING UNIT RTU-1

THE DDC SYSTEM SHALL PROVIDE A WEEKLY SCHEDULE INCORPORATING OPTIMIZED START/STOP SCHEDULING FOR THE OPERATION OF THE ROOFTOP UNIT. ROOFTOP UNIT OPERATION SHALL BE INTERLOCKED WITH HEAT RECOVERY UNIT HRU-2.

OCCUPIED MODE  
THE DDC CONTROLLER SHALL ENERGIZE THE ROOFTOP UNIT. UPON PROOF OF ROOFTOP UNIT OPERATION THE TEMPERATURE, PRESSURE CONTROL, AND CO2 LOOPS ARE ENABLED. FAILURE OF THE ROOFTOP UNIT TO RESPOND TO COMMANDS FROM THE DDC SYSTEM SHALL SHUT THE ROOFTOP UNIT DOWN AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

A STATIC PRESSURE SENSOR LOCATED 2/3 OF THE DISTANCE DOWNSTREAM IN THE LONGEST SUPPLY DUCT SHALL MONITOR THE SYSTEM PRESSURE AND MODULATE THE SUPPLY FAN SPEED TO MAINTAIN THE SUPPLY AIR STATIC PRESSURE AT SETPOINT. THE DDC SYSTEM SHALL MONITOR THE POSITIONS OF THE TERMINAL UNITS AND RESET THE STATIC PRESSURE SETPOINT BETWEEN PROGRAMMED UNITS (0 TO 250 Pa) TO DRIVE THE MOST OPEN TERMINAL UNIT DAMPER TOWARD THE FULLY OPEN POSITION WHILE MAINTAINING THE TERMINAL UNIT FLOW SETPOINT.

DUCT MOUNTED AND ZONE THERMOSTAT MOUNTED CARBON DIOXIDE (CO2) DETECTORS SHALL MONITOR THE BUILDING CO2 LEVEL AND INITIATE A MIXED AIR SEQUENCE IF A SPACE CO2 LEVEL RISES ABOVE THE SETPOINT LEVEL (800 PPM). DDC SYSTEM SHALL MODULATE THE OUTSIDE AND RETURN AIR DAMPERS TO MAINTAIN THE CO2 LEVEL SETPOINT. MIXED AIR DAMPERS TO BE NORMALLY AT THE MINIMUM OUTDOOR AIR POSITION (CLOSED) AND ARE INITIATED ONLY BY A CALL FOR COOLING OR CO2 DETECTION.

MANUAL RESET HIGH AND AUTOMATIC RESET LOW LIMIT CUT-OUTS UPON SENSING A HIGH RETURN AIR TEMPERATURE OR LOW DISCHARGE TEMPERATURE RESPECTIVELY SHALL SHUT THE ROOFTOP UNIT DOWN AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

A SMOKE IONIZATION DETECTOR LOCATED IN THE SUPPLY AND RETURN DUCTS SHALL SHUT DOWN THE AIR HANDLER AND INDICATE AN ALARM SIGNAL AT THE SUPERVISORY CONTROLLER AND FIRE ALARM SYSTEM PANEL UPON SENSING THE PRESENCE OF SMOKE. DDC SYSTEM SHALL MONITOR FILTER CONTACTS AND INDICATE SERVICE IS REQUIRED IF A DIRTY FILTER CONDITION IS DETECTED.

VENTILATION MODE  
OUTDOOR AND RETURN AIR DAMPERS SHALL BE MODULATED TO MAINTAIN THE AIR HANDLING UNIT CALCULATED SUPPLY AIR DISCHARGE TEMPERATURE SETPOINT. DISCHARGE AIR TEMPERATURE SHALL BE RESET BETWEEN PROGRAMMED UNITS (13.7°C TO 21.1°C) BASED ON CRITICAL ZONE TEMPERATURE OFFSET. IF THE DISCHARGE AIR TEMPERATURE DROPS BELOW THE SETPOINT TEMPERATURE DUE TO CO2 SYSTEM OUTDOOR AIR REQUIREMENTS, THE DDC SYSTEM SHALL MODULATE THE GLYCOL HEATING COIL CONTROL VALVE TO MAINTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT.

COOLING MODE  
ON A CALL FOR COOLING, OUTDOOR AND RETURN AIR DAMPERS ARE TO BE MODULATED TO MAINTAIN THE CALCULATED DISCHARGE AIR TEMPERATURE SETPOINT. IF THE ECONOMIZER IS UNABLE TO MAINTAIN DISCHARGE AIR TEMPERATURE AT SETPOINT, THE DDC EQUIPMENT CONTROLLER SHALL ENERGIZE MECHANICAL COOLING AND MODULATE THE COOLING STAGES TO COOLANTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT. WHEN THE ENTHALPHY OF THE OUTDOOR AIR EXCEEDS THE ENTHALPHY OF THE RETURN AIR, THE MIXED AIR DAMPERS SHALL MOVE TO THE MINIMUM OUTDOOR AIR POSITION.

DDC SYSTEM SHALL MONITOR THE SUM OF ALL TERMINAL UNIT FLOWS. IF THE AIR FLOW DROPS BELOW THE DX COOLING COIL MINIMUM AIRFLOW (400 L/S) WHEN OPERATING MECHANICAL COOLING, THE DDC SYSTEM SHALL PROPORTIONATELY ADJUST TERMINAL UNIT MINIMUM POSITIONS AS REQUIRED TO MEET THE COOLING COIL MINIMUM AIRFLOW VALUE.

UNOCCUPIED MODE  
DURING UNOCCUPIED HOURS, THE ROOFTOP UNIT SHALL BE DE-ENERGIZED. THE OUTDOOR AIR AND RETURN AIR DAMPERS SHALL MOVE TO THE FULLY CLOSED POSITION. THE RETURN AIR DAMPER SHALL MOVE TO THE FULLY OPEN POSITION. TEMPERATURE, PRESSURE AND CO2 CONTROL LOOPS ARE TO BE DISABLED.

SEQUENCES OF OPERATION -CONTINUED

HEAT RECOVERY UNIT HRU-1, WATER WORKS & TRADES SHOPS CARBON MONOXIDE (CO) SYSTEMS, TERMINAL UNITS TU-1&2 AND AIR CONTROL VALVES ACV-1&2

OCCUPIED MODE:  
UPON SENSING OCCUPANCY THROUGH THE SPACE MOUNTED OCCUPANCY SENSOR, THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY UNIT. UPON START/STOP CONTACT, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL ENERGIZE THE DAMPER SECTION. UPON DETECTION OF DAMPER OPERATION THE PLC BLOWER INTERLOCK IS ENERGIZED AND THE FRESH AIR AND EXHAUST AIR FANS ARE ENERGIZED. UPON PROOF OF HEAT RECOVERY UNIT OPERATION, THE TEMPERATURE AND PRESSURE CONTROL LOOPS ARE ENABLED AND TERMINAL UNITS TU-1&2 AND AIR CONTROL VALVES ACV-1&2 SHALL MOVE TO THE MINIMUM AIR FLOW POSITION. IF THE MOTORIZED DAMPERS AND/OR FRESH AND EXHAUST AIR FANS FAIL TO START, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL SIGNAL THE DDC SYSTEM. DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

A STATIC PRESSURE SENSOR LOCATED IN THE SUPPLY AIR DUCT SHALL MONITOR THE SYSTEM PRESSURE AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF A HIGH OR LOW PRESSURE CONDITION IS DETECTED.

IF THE DISCHARGE AIR TEMPERATURE DROPS BELOW SETPOINT (20.5°C), THE DDC SYSTEM SHALL MODULATE THE HEAT RECOVERY UNIT HEATING COIL CONTROL VALVE TO MAINTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT. AS THE DISCHARGE AIR TEMPERATURE RISES TOWARD SETPOINT THE DDC SYSTEM SHALL MODULATE THE HEATING COIL CONTROL VALVE TOWARD THE CLOSED POSITION.

A SMOKE IONIZATION DETECTOR LOCATED IN THE FRESH AIR SECTION OF THE UNIT SHALL SHUT DOWN THE HEAT RECOVERY UNIT UPON SENSING AN ALARM CONDITION. THE DDC SYSTEM SHALL GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF AN ALARM CONDITION IS DETECTED.

THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL SIGNAL THE DDC SYSTEM UPON SENSING A HIGH RETURN AIR TEMPERATURE OR LOW DISCHARGE AIR TEMPERATURE RESPECTIVELY AND THE DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

DDC SYSTEM SHALL MONITOR THE UNIT DIRTY FILTER CONTACTS AND INDICATE SERVICE IS REQUIRED IF A DIRTY FILTER CONDITION IS DETECTED.

GAS DETECTION MODE:  
UPON DETECTION OF A HIGH CARBON MONOXIDE (CO) (25 PPM) GAS CONCENTRATION IN THE WATER WORKS SHOP Rm.110 AND/OR THE TRADES SHOP Rm.117 THE DDC SYSTEM SHALL MODULATE THE ASSOCIATED SPACE TEMPERATURE UNIT AND AIR CONTROL VALVE TO THE MAXIMUM AIR FLOW POSITION AND INCREASE THE HEAT RECOVERY VENTILATOR SUPPLY AND EXHAUST FAN SPEEDS AS REQUIRED. WHEN THE SPACE GAS CONCENTRATION DROPS BELOW SETPOINT, THE DDC SYSTEM SHALL MODULATE THE ASSOCIATED SPACE TERMINAL UNIT AND AIR CONTROL VALVE TO THE MINIMUM AIR FLOW POSITION AND REDUCE THE SPEED OF THE HEAT RECOVERY VENTILATOR SUPPLY AND EXHAUST FAN SPEEDS TO SUIT.

HEAT RECOVERY UNIT HRU-2 –OFFICE AREA

THE DDC SYSTEM SHALL PROVIDE AN ADJUSTABLE WEEKLY SCHEDULE FOR THE OPERATION OF THE HEAT RECOVERY UNIT. UPON START/STOP CONTACT, THE HEAT RECOVERY UNIT OPERATION SHALL BE INTERLOCKED WITH ROOFTOP UNIT RTU-1.

OCCUPIED MODE  
HEAT RECOVERY UNIT SHALL RUN CONTINUALLY DURING BUILDING OCCUPIED HOURS. THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY VENTILATOR VIA THE UNIT START/STOP CONTACT. UPON AN OCCUPIED SIGNAL FROM THE DDC SYSTEM, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL ENERGIZE THE DAMPER SECTION. UPON DETECTION OF DAMPER OPERATION THE PLC BLOWER INTERLOCK IS ENERGIZED AND THE FRESH AIR AND EXHAUST AIR FANS ARE ENERGIZED. IF THE MOTORIZED DAMPERS AND/OR FRESH AND EXHAUST AIR FANS FAIL TO START, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL A SIGNAL THE DDC SYSTEM. DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

IF THE DISCHARGE AIR TEMPERATURE DROPS BELOW SETPOINT (20.5°C), THE DDC SYSTEM SHALL MODULATE THE HEAT RECOVERY UNIT HEATING COIL CONTROL VALVE TO MAINTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT. AS THE DISCHARGE AIR TEMPERATURE RISES TOWARD SETPOINT THE DDC SYSTEM SHALL MODULATE THE HEATING COIL CONTROL VALVE TOWARD THE CLOSED POSITION.

A SMOKE IONIZATION DETECTOR LOCATED IN THE FRESH AIR SECTION OF THE UNIT SHALL SHUT DOWN THE HEAT RECOVERY UNIT UPON SENSING AN ALARM CONDITION. THE DDC SYSTEM SHALL GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF AN ALARM CONDITION IS DETECTED.

THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL SIGNAL THE DDC SYSTEM UPON SENSING A HIGH RETURN AIR TEMPERATURE OR LOW DISCHARGE AIR TEMPERATURE RESPECTIVELY. THE DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

DDC SYSTEM SHALL MONITOR THE UNIT DIRTY FILTER CONTACTS AND INDICATE SERVICE IS REQUIRED IF A DIRTY FILTER CONDITION IS DETECTED.

UNOCCUPIED MODE:  
DURING UNOCCUPIED HOURS, THE DDC SYSTEM SHALL DE-ENERGIZE THE HEAT RECOVERY UNIT. THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL MOVE THE INTERNAL DAMPERS TO THE CLOSED POSITION AND ISOLATE THE BUILDING FROM THE ATMOSPHERE. PRESSING ANY ZONE THERMOSTAT OCCUPIED OVERRIDE BUTTON SHALL ENERGIZE THE HEAT RECOVERY UNIT. HEAT RECOVERY UNIT SHALL RUN AS PER OCCUPIED MODE FOR 2 HOURS OR UNTIL THE OCCUPIED OVERRIDE BUTTON IS PRESSED AGAIN.

HEAT RECOVERY UNIT HRU-3 –MECHANICS SHOP

THE DDC SYSTEM SHALL PROVIDE AN ADJUSTABLE WEEKLY SCHEDULE FOR THE OPERATION OF THE HEAT RECOVERY UNIT.

OCCUPIED MODE  
HEAT RECOVERY UNIT SHALL RUN CONTINUALLY DURING BUILDING OCCUPIED HOURS. THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY VENTILATOR VIA THE UNIT START/STOP CONTACT. UPON AN OCCUPIED SIGNAL FROM THE DDC SYSTEM, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL ENERGIZE THE DAMPER SECTION. UPON DETECTION OF DAMPER OPERATION, THE PLC BLOWER INTERLOCK IS ENERGIZED AND THE FRESH AND EXHAUST AIR FANS ARE ENERGIZED. IF THE MOTORIZED DAMPERS AND/OR FRESH AIR AND EXHAUST AIR FANS FAIL TO START, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL A SIGNAL THE DDC SYSTEM. DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

IF THE DISCHARGE AIR TEMPERATURE DROPS BELOW SETPOINT (20.5°C), THE DDC SYSTEM SHALL MODULATE THE AIR HANDLER HEATING COIL CONTROL VALVE TO MAINTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT. AS THE DISCHARGE AIR TEMPERATURE RISES TOWARD SETPOINT THE DDC SYSTEM SHALL MODULATE THE HEATING COIL CONTROL VALVE TOWARD THE CLOSED POSITION.

A SMOKE IONIZATION DETECTOR LOCATED IN THE FRESH AIR SECTION OF THE UNIT SHALL SHUT DOWN THE HEAT RECOVERY UNIT UPON SENSING AN ALARM CONDITION. THE DDC SYSTEM SHALL GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER IF AN ALARM CONDITION IS DETECTED.

THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL SIGNAL THE DDC SYSTEM UPON SENSING A HIGH RETURN AIR TEMPERATURE OR LOW DISCHARGE AIR TEMPERATURE RESPECTIVELY AND THE DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

DDC SYSTEM SHALL MONITOR THE UNIT DIRTY FILTER CONTACTS AND INDICATE SERVICE IS REQUIRED IF A DIRTY FILTER CONDITION IS DETECTED.

VEHICLE EXHAUST EXTRACTION (VES) MODE:  
WHEN ONE (1) VES SYSTEM IS ACTIVATED AS SENSED BY THE DDC SYSTEM VIA THE VES FAN STARTER CURRENT SENSOR, THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY UNIT MOTORIZED BY-PASS DAMPER. THE DDC SYSTEM SHALL PROPORTIONATELY MODULATE THE MOTORIZED DAMPER TO POSITION No.1 (660 L/S) AND REDUCE THE SPEED OF THE HEAT RECOVERY UNIT EXHAUST FAN TO 4140 L/S. IF THE SECOND VES SYSTEM IS ACTIVATED AS SENSED BY THE DDC SYSTEM VIA THE VES FAN STARTER CURRENT SENSOR, THE DDC SYSTEM SHALL PROPORTIONATELY MODULATE THE HEAT RECOVERY UNIT MOTORIZED BY-PASS DAMPER TO POSITION No.2 (1320 L/S) AND FURTHER REDUCE THE SPEED OF THE HEAT RECOVERY UNIT EXHAUST FAN TO 3480 L/S. WHEN ONE (1) VES SYSTEM IS DEACTIVATED, THE DDC SYSTEM SHALL INCREASE THE SPEED OF THE HEAT RECOVERY UNIT TO 4140 L/S AND THE MOTORIZED BY-PASS DAMPER SHALL RETURN TO POSITION No.1 (660 L/S). WHEN THE SECOND VES SYSTEM IS DEACTIVATED, THE DDC SYSTEM SHALL INCREASE THE SPEED OF THE HEAT RECOVERY UNIT TO 4140 L/S AND DEENERGIZED THE MOTORIZED BY-PASS DAMPER. DAMPER SHALL RETURN TO THE NORMALLY CLOSED POSITION.

GAS DETECTION SYSTEM MODE:  
UPON DETECTION OF A HIGH CO (25 PPM) OR NO2 (3 PPM) GAS CONCENTRATION WITH THE UNIT NOT OPERATING, THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY UNIT TO FULL SPEED. HEAT RECOVERY UNIT SHALL OPERATE AS PER OCCUPIED MODE. WHEN THE GAS CONCENTRATION DROPS BELOW SETPOINT, THE HEAT RECOVERY UNIT SHALL BE DE-ENERGIZED.

UNOCCUPIED MODE:  
DURING UNOCCUPIED HOURS, THE DDC SYSTEM SHALL DE-ENERGIZE THE HEAT RECOVERY UNIT. THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL MOVE THE INTERNAL DAMPERS TO THE CLOSED POSITION AND ISOLATE THE BUILDING FROM THE ATMOSPHERE. PRESSING ANY ZONE THERMOSTAT OCCUPIED OVERRIDE BUTTON SHALL ENERGIZE THE HEAT RECOVERY UNIT. HEAT RECOVERY UNIT SHALL RUN AS PER OCCUPIED MODE FOR 2 HOURS OR UNTIL THE OCCUPIED OVERRIDE BUTTON IS PRESSED AGAIN.

SEQUENCES OF OPERATION -CONTINUED

HEAT RECOVERY UNIT HRU-4 –AUTOMATIC WASHBAY/TRANSPORTATION SERVICE BAY

THE DDC SYSTEM SHALL PROVIDE AN ADJUSTABLE WEEKLY SCHEDULE FOR THE OPERATION OF THE HEAT RECOVERY UNIT.

OCCUPIED MODE  
HEAT RECOVERY UNIT SHALL RUN ON CONTINUALLY ON LOW SPEED (350 L/S) DURING BUILDING OCCUPIED HOURS. THE DDC SYSTEM SHALL ENERGIZE THE HEAT RECOVERY VENTILATOR VIA THE UNIT START/STOP CONTACT. UPON AN OCCUPIED SIGNAL FROM THE DDC SYSTEM, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL ENERGIZE THE DAMPER SECTION. UPON DETECTION OF DAMPER OPERATION THE PLC BLOWER INTERLOCK IS ENERGIZED AND THE FRESH AIR AND EXHAUST AIR FANS ARE ENERGIZED. IF THE MOTORIZED DAMPERS AND/OR FRESH AIR AND EXHAUST AIR FANS FAIL TO START, THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL A SIGNAL THE DDC SYSTEM. DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

UPON A SIGNAL FROM THE TOUCHLESS ROLLOVER VEHICLE WASH SYSTEM PLC INDICATING THE START OF A WASH CYCLE THE DDC SYSTEM SHALL INCREASE THE HEAT RECOVERY UNIT TO HIGH SPEED (2000 L/S). HEAT RECOVERY UNIT SHALL RUN AT HIGH SPEED FOR DURATION OF WASH CYCLE. ONCE WASH CYCLE IS COMPLETE AS SIGNALED BY THE TOUCHLESS ROLLOVER VEHICLE WASH SYSTEM PLC, THE DDC SYSTEM SHALL REDUCE THE SPEED OF THE HEAT RECOVERY UNIT TO MEDIUM (1000 L/S). AFTER A THIRTY MINUTE TIME PERIOD, WITH NO SIGNAL FROM THE PLC INDICATING A NEW WASH CYCLE, THE DDC SYSTEM SHALL REDUCE THE HEAT RECOVERY UNIT SPEED TO LOW SPEED (350 L/S).

IF THE DISCHARGE AIR TEMPERATURE DROPS BELOW SETPOINT (20.5°C), THE DDC SYSTEM SHALL MODULATE THE HEAT RECOVERY UNIT HEATING COIL CONTROL VALVE TO MAINTAIN THE DISCHARGE AIR TEMPERATURE AT SETPOINT. AS THE DISCHARGE AIR TEMPERATURE RISES TOWARD SETPOINT THE DDC SYSTEM SHALL MODULATE THE HEATING COIL CONTROL VALVE TOWARD THE CLOSED POSITION.

THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL SIGNAL THE DDC SYSTEM UPON SENSING A HIGH RETURN AIR TEMPERATURE OR LOW DISCHARGE AIR TEMPERATURE RESPECTIVELY. THE DDC SYSTEM SHALL LOCKOUT THE HEAT RECOVERY UNIT OPERATION AND GENERATE AN ALARM AT THE SUPERVISORY CONTROLLER.

DDC SYSTEM SHALL MONITOR THE UNIT DIRTY FILTER CONTACTS AND INDICATE SERVICE IS REQUIRED IF A DIRTY FILTER CONDITION IS DETECTED.

UNOCCUPIED MODE:  
DURING UNOCCUPIED HOURS, THE DDC SYSTEM SHALL DE-ENERGIZE THE HEAT RECOVERY UNIT. THE HEAT RECOVERY UNIT INTERNAL CONTROLLER SHALL MOVE THE INTERNAL DAMPERS TO THE CLOSED POSITION AND ISOLATE THE BUILDING FROM THE ATMOSPHERE.

IN-SLAB HEATING

OCCUPIED MODE:  
ON A DROP IN SPACE TEMPERATURE BELOW THE THERMOSTAT HEATING SETPOINT, THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE OPEN. AS THE SPACE TEMPERATURE RISES TO SETPOINT, THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE CLOSED.

UNOCCUPIED MODE  
THE ZONE HEATING TEMPERATURE SHALL BE SET BACK TO UNOCCUPIED SETPOINT. IF THE SPACE TEMPERATURE DROPS BELOW THE UNOCCUPIED HEATING SETPOINT, THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE OPEN. AS THE SPACE TEMPERATURE RISES TOWARD THE UNOCCUPIED SETPOINT, THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE CLOSED.

SERVICES/UTILITY Rm.116 - SPLIT AIR CONDITIONING SYSTEM AC-1

THE DDC SYSTEM SHALL MONITOR THE SPACE TEMPERATURE AND PROVIDE AN ALARM AT THE SUPERVISORY CONTROLLER IF THE SPACE TEMPERATURE RISES ABOVE OR DROPS BELOW THE ALARM TEMPERATURE SETPOINT.

ON A RISE IN TEMPERATURE ABOVE THE THERMOSTAT COOLING SETPOINT (23°C), THE DDC SYSTEM SHALL ENERGIZE MECHANICAL COOLING. WHEN THE SPACE TEMPERATURE IS SATISFIED, MECHANICAL COOLING SHALL BE DE-ENERGIZED.

ON A DROP IN SPACE TEMPERATURE BELOW THE THERMOSTAT HEATING SETPOINT (20°C), MECHANICAL COOLING SHALL BE LOCKED OUT AND THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE OPEN. AS THE SPACE TEMPERATURE RISES TO SETPOINT, THE RADIANT HEATING ZONE TELESTAT(S) SHALL MODULATE CLOSED.

DESTRATIFICATION FANS DF-X

THE DDC SYSTEM SHALL PROVIDE CONTROL OF DESTRATIFICATION FAN OPERATION. FANS SHALL RUN CONTINUALLY DURING OCCUPIED HOURS.

THE DDC SYSTEM SHALL START, STOP AND ADJUST SPEED OF DESTRATIFICATION FANS VIA 0-10 VDC INTERFACE MODULE.

WINTER MODE:  
WHEN THE AMBIENT TEMPERATURE IS BELOW THE SPACE SETPOINT TEMPERATURE, THE DDC SYSTEM SHALL MONITOR THE DIFFERENCE IN THE TEMPERATURE BETWEEN THE ROOF MOUNTED TEMPERATURE SENSOR AND THE SPACE TEMPERATURE SENSOR. IF THE SPACE TEMPERATURE SENSED AT THE ROOF LEVEL INCREASES ABOVE THE SPACE TEMPERATURE SENSED AT THE FLOOR LEVEL, THE DDC SYSTEM SHALL PROPORTIONATELY INCREASE THE SPEED OF THE DESTRATIFICATION FANS TOWARD THE MAXIMUM SPEED SETTING. AS THE DIFFERENTIAL BETWEEN THE TEMPERATURE SENSORS DECREASES, THE DDC SYSTEM SHALL PROPORTIONATELY DECREASE THE SPEED OF THE DESTRATIFICATION FANS TOWARD THE MINIMUM SPEED SETTING.

SUMMER MODE:  
WHEN THE AMBIENT TEMPERATURE IS ABOVE THE SPACE SETPOINT TEMPERATURE, THE DDC SYSTEM SHALL MONITOR THE SPACE TEMPERATURE SENSOR ONLY. DESTRATIFICATION FANS SHALL RUN AT THE MINIMUM SPEED SETTING AT THE SPACE TEMPERATURE SETPOINT. AS THE SPACE TEMPERATURE RISES ABOVE SETPOINT, THE DDC SYSTEM SHALL PROPORTIONATELY INCREASE THE SPEED OF THE DESTRATIFICATION FANS TOWARD THE MAXIMUM SPEED SETTING AT THE MAXIMUM SPACE TEMPERATURE SETPOINT. AS THE SPACE TEMPERATURE DROPS TOWARD SETPOINT, THE DDC SYSTEM SHALL PROPORTIONATELY DECREASE THE SPEED OF THE DESTRATIFICATION FANS TOWARD THE MINIMUM SPEED SETTING.

MANUAL MODE:  
THE DDC SYSTEM SHALL PERMIT FANS TO BE ENERGIZED AND DEENERGIZED. MANUAL MODE FAN SPEED SHALL BE OPERATOR ADJUSTABLE BETWEEN THE MINIMUM AND MAXIMUM FAN SPEEDS.

UPON A SIGNAL FROM THE BUILDING FIRE ALARM PANEL, THE DDC SYSTEM SHALL SHUT DOWN DESTRATIFICATION FAN OPERATION.

BOILER Rm.201A TEMPERATURE CONTROL UH-1, EF-1, MD-1&2

THE DDC SYSTEM SHALL MONITOR THE BOILER ROOM TEMPERATURE AND CONTROL THE OPERATION OF UNIT HEATER UH-1 AND MECHANICAL ROOM EXHAUST FAN EF-1.

IF THE SPACE TEMPERATURE DROPS BELOW THE SPACE HEATING SETPOINT TEMPERATURE (20°C) AS DETECTED BY THE WALL MOUNTED TEMPERATURE SENSOR, THE DDC SYSTEM SHALL ENERGIZE UNIT HEATER UH-1. BOILER ROOM EXHAUST FAN EF-1 OPERATION SHALL BE LOCKED OUT. WHEN THE SPACE TEMPERATURE SETPOINT IS SATISFIED, THE DDC SYSTEM SHALL DEENERGIZE UNIT HEATER UH-1.

IF THE SPACE TEMPERATURE RISES ABOVE THE SPACE COOLING SETPOINT TEMPERATURE (26.0°C) THE DDC SYSTEM SHALL ENERGIZE MOTORIZED DAMPERS MD-1 AND MD-2. UPON DAMPERS REACHING THE FULLY OPEN POSITION AS SIGNALLED BY THE DAMPER END SWITCH, THE DDC SYSTEM SHALL ENERGIZE THE BOILER ROOM EXHAUST FAN EF-1. THE DDC SYSTEM SHALL PROPORTIONATELY MODULATE THE EXHAUST FAN TOWARD THE DESIGN AIR FLOW SETTING AS REQUIRED TO MAINTAIN THE SPACE TEMPERATURE AT SETPOINT. UNIT HEATER UH-1 OPERATION SHALL BE LOCKED OUT.

AS THE SPACE TEMPERATURE FALLS TOWARD THE SETPOINT, THE DDC SYSTEM SHALL PROPORTIONATELY MODULATE EXHAUST FAN EF-1 TOWARD MINIMUM SPEED.

WHEN THE SPACE TEMPERATURE SETPOINT IS SATISFIED, THE DDC SYSTEM SHALL DEENERGIZE THE EXHAUST FAN EF-1 AND MOTORIZED DAMPERS MD-1 AND MD-2. MOTORIZED DAMPERS SHALL RETURN TO THE NORMALLY CLOSED POSITION.

CABINET UNIT HEATER CUH-X

OCCUPIED MODE  
ON A DROP IN SPACE TEMPERATURE BELOW THE THERMOSTAT HEATING SETPOINT (20°C), THE DDC SYSTEM SHALL ENERGIZE THE FORCE FLOW HEATER CIRCULATING FAN AND MODULATE THE GLYCOL HEATING CONTROL VALVE TO THE FULLY OPEN POSITION. WHEN THE SPACE TEMPERATURE SETPOINT IS SATISFIED, THE FORCE FLOW HEATER CIRCULATING FAN SHALL BE DE-ENERGIZED AND THE GLYCOL HEATING CONTROL VALVE SHALL RETURN TO THE NORMALLY CLOSED POSITION. FORCE FLOW FAN SPEED SHALL BE ADJUSTABLE (OFF/LOW/MED./HIGH) VIA THE HEATER MOUNTED SPEED CONTROL SWITCH.

UNOCCUPIED MODE  
DURING UNOCCUPIED HOURS, THE SPACE HEATING TEMPERATURE IS TO BE SET BACK TO 18°C. IF THE SPACE TEMPERATURE DROPS BELOW THE SETPOINT, THE DDC SYSTEM SHALL ENERGIZE THE FORCE FLOW HEATER CIRCULATING FAN AND MODULATE THE GLYCOL HEATING CONTROL VALVE TO THE FULLY OPEN POSITION. WHEN THE SPACE TEMPERATURE SETPOINT IS SATISFIED, THE FORCE FLOW CIRCULATING FAN SHALL BE DE-ENERGIZED AND THE GLYCOL HEATING CONTROL VALVE SHALL RETURN TO THE NORMALLY CLOSED POSITION.

UNIT HEATER UH-X

IF THE SPACE TEMPERATURE DROPS BELOW THE HEATING SETPOINT TEMPERATURE (20°C) AS DETECTED BY THE WALL MOUNTED TEMPERATURE SENSOR, THE DDC SYSTEM SHALL ENERGIZE THE UNIT HEATER CIRCULATING FAN VIA THE LOW VOLTAGE RELAY.

WHEN THE SPACE TEMPERATURE SETPOINT IS SATISFIED, THE UNIT HEATER CIRCULATING FAN SHALL BE DEENERGIZED.

SEQUENCES OF OPERATION -CONTINUED

GENERAL

THE DDC CONTROL SYSTEM SHALL MONITOR AND DISPLAY ON THE GRAPHICAL USER INTERFACE (GUI) THE FOLLOWING POINTS AS A MINIMUM AND PROVIDE THE FOLLOWING ALARMS. ALL WRITABLE POINTS SHALL BE ADJUSTABLE VIA THE GUI.

- OUTDOOR DRY BULB TEMPERATURE
- OUTDOOR WET BULB TEMPERATURE
- ROOFTOP UNIT STATUS
- ROOFTOP UNIT SUPPLY AIR FAN FAILURE
- ROOFTOP UNIT RETURN/EXHAUST FAN FAILURE
- ROOFTOP UNIT MOTORIZED RECIRCULATION/FRESH/EXHAUST AIR DAMPER POSITIONS
- ROOFTOP UNIT MOTORIZED RECIRCULATION/FRESH/EXHAUST AIR DAMPER FAILURES
- ROOFTOP UNIT COMPRESSOR INVERTER STATUS
- ROOFTOP UNIT COMPRESSOR INVERTER SPEED
- ROOFTOP UNIT CONDENSING UNIT FAN INVERTER STATUS
- ROOFTOP UNIT CONDENSING UNIT FAN INVERTER SPEED
- ROOFTOP UNIT HIGH RETURN AIR TEMPERATURE
- ROOFTOP UNIT SUPPLY AIR TEMPERATURE
- ROOFTOP UNIT RETURN AIR TEMPERATURE
- ROOFTOP UNIT EXHAUST AIR TEMPERATURE
- ROOFTOP UNIT MIXED AIR TEMPERATURE
- ROOFTOP UNIT HEATING COIL CONTROL/BALANCE VALVE POSITION
- ROOFTOP UNIT SMOKE DETECTOR STATUS
- ROOFTOP UNIT RETURN AIR CO2 LEVEL
- ROOFTOP UNIT RETURN AIR HUMIDITY LEVEL
- ROOFTOP UNIT AIR HUMIDITY LEVEL
- SUPPLY AIR STATIC PRESSURE
- HIGH/LOW SUPPLY AIR STATIC PRESSURE
- SPACE TEMPERATURES/CO2 LEVEL
- TERMINAL UNIT POSITION
- TERMINAL UNIT FLOW RATE
- AIR CONTROL VALVE POSITION
- AIR CONTROL VALVE FLOW RATE
- LOW SPACE TEMPERATURE
- HEAT RECOVERY UNIT STATUS
- HEAT RECOVERY UNIT ALARM SIGNAL
- HEAT RECOVERY UNIT RETURN AIR DISCHARGE HUMIDITY LEVEL
- HEAT RECOVERY UNIT SMOKE DETECTOR STATUS
- HEAT RECOVERY UNIT FRESH AIR DISCHARGE HUMIDITY LEVEL
- HEAT RECOVERY UNIT EXHAUST AIR INLET HUMIDITY LEVEL
- HEAT RECOVERY UNIT DIRTY FILTER SWITCH
- HEAT RECOVERY UNIT HEATING COIL CONTROL/BALANCE VALVE POSITION
- HEAT RECOVERY UNIT HRU-3 MOTORIZED BY-PASS DAMPER POSITION
- HEAT RECOVERY UNIT HRU-3 MOTORIZED BY-PASS DAMPER FAILURE
- CONDENSING UNIT STATUS/CAPACITY
- CONDENSING UNIT FAILURE
- SPLIT AIR CONDITIONING SYSTEM SPACE TEMPERATURE
- SPLIT AIR CONDITIONING SYSTEM ALARM SIGNAL
- VEHICLE EXTRACTION SYSTEM STATUS
- BOILER STATUS/OPERATING OUTPUT
- BOILER FAILURE ALARM
- HEATING LOOP SUPPLY/RETURN TEMPERATURES
- PRIMARY HEATING CIRCULATING PUMP STATUS
- PRIMARY HEATING CIRCULATING PUMP FAILURE
- PRIMARY HEATING CIRCULATING PUMP SPEEDS
- BOILER PUMP STATUS
- BOILER PUMP FAILURE
- GLYCOL FEEDER LOW LEVEL ALARM
- DOMESTIC HOT WATER RECIRCULATION PUMP STATUS
- DOMESTIC HOT WATER RECIRCULATION PUMP FAILURE
- BOILER ROOM SPACE TEMPERATURE
- BOILER ROOM LOW/HIGH SPACE TEMPERATURE
- BOILER ROOM EXHAUST FAN STATUS
- BOILER ROOM EXHAUST FAN SPEED
- BOILER ROOM EXHAUST FAN AIR FLOW
- BOILER ROOM EXHAUST FAN FAILURE
- BOILER ROOM EXHAUST FAN MOTORIZED DAMPER POSITIONS
- BOILER ROOM VENTILATION SYSTEM MOTORIZED DAMPER FAILURE
- DOMESTIC HOT WATER RECIRCULATION PUMP STATUS
- DOMESTIC HOT WATER RECIRCULATION PUMP FAILURE
- CO/NO2 GAS DETECTION SYSTEM SENSOR LEVEL
- CO/NO2 GAS DETECTION STATUS/ALARMS
- DESTRATIFICATION FAN STATUS
- DESTRATIFICATION FAN FAILURE
- DESTRATIFICATION FAN SETTING
- DESTRATIFICATION FAN SPEED
- UNIT HEATER STATUS
- UNIT HEATER FAILURE
- CABINET UNIT HEATER STATUS
- CABINET UNIT HEATER CONTROL/BALANCE VALVE POSITION

THE ALARMS SHALL BE DISPLAYED AT THE SUPERVISORY CONTROLLER AND SHALL APPEAR AS "ACKNOWLEDGED" OR "UNACKNOWLEDGED".

PROGRAM FULL COLOUR GRAPHICS OPERATING SOFTWARE TO PERMIT MONITORING AND EDITING OF SYSTEM VARIABLES, SCHEDULING AND ALARMS VIA WEB ENABLED SUPERVISORY CONTROLLER. GRAPHICALS SHALL LINK THE OPERATOR TO THE GRAPHICAL DATA DISPLAY FOR THE SPECIFIC COMPONENT. PROVIDE COMPLETE COMMISSIONING SERVICES BY THE DDC SYSTEM AUTHORIZED REPRESENTATIVE TO VERIFY THE PROPER OPERATION OF THE DDC SYSTEM. COMMISSIONING WORK TO BE PERFORMED IN CONJUNCTION WITH THE DESIGN CONSULTANT TO VERIFY THE PROPER FUNCTIONING OF THE MECHANICAL SYSTEMS IN ACCORDANCE WITH THE SEQUENCE OF OPERATION.

AN ELECTRONIC COPY OF THE SEQUENCE OF OPERATION FOR EACH PIECE OF EQUIPMENT SHALL BE INCORPORATED IN THE DDC PROGRAMMING AND BE EASILY AVAILABLE FOR VIEWING BY THE OPERATOR BY USING A BUTTON ON EACH EQUIPMENT GRAPHIC. LOCAL BUTTTONS SHALL BE PROVIDED FOR EACH LOCATION ON EACH GRAPHIC.

THE SCOPE OF COMMISSIONING SHALL INCLUDE THE FOLLOWING AS A MINIMUM:  
-VERIFY ALL CONTROL SYSTEM SETPOINTS AND ALARMS  
-CHECK THE OPERATION OF ALL THERMOSTATS  
-CHECK THE OPERATION OF ALL TEMPERATURE SENSORS  
-REVIEW THE OPERATION OF THE HVAC SYSTEMS INCLUDING THE FOLLOWING:

- <

AUTOMATIC CIRCUIT BALANCING VALVE SCHEDULE (ABV-X)

VALVE No.	EQUIPMENT SERVED	SIZE	FLOW RATE (L/S)
ABV-1	IN-SLAB HEATING MANIFOLD M1	13ø	0.126
ABV-2	IN-SLAB HEATING MANIFOLD M2	19ø	0.158
ABV-3	IN-SLAB HEATING MANIFOLD M3	13ø	0.095
ABV-4	IN-SLAB HEATING MANIFOLD M4	13ø	0.063
ABV-5	IN-SLAB HEATING MANIFOLD M5	19ø	0.158
ABV-6	IN-SLAB HEATING MANIFOLD M6	13ø	0.063
ABV-7	IN-SLAB HEATING MANIFOLD M7	19ø	0.442
ABV-8	IN-SLAB HEATING MANIFOLD M8	19ø	0.442
ABV-9	IN-SLAB HEATING MANIFOLD M9	19ø	0.252
ABV-10	IN-SLAB HEATING MANIFOLD M10	19ø	0.315
ABV-11	UNIT HEATER UH-1	13ø	0.095
ABV-12	UNIT HEATER UH-2	13ø	0.095
ABV-13	UNIT HEATER UH-3	13ø	0.032

## CONTROL / BALANCING VALVE SCHEDULE (CBV-X)

VALVE No.	EQUIPMENT SERVED	SIZE	FLOW RATE (L/S)
CBV-1	ROOFTOP UNIT RTU-1 HEATING COIL	19#	0.233
CBV-2	HEAT RECOVERY UNIT HRU-1 HEATING COIL	19#	0.170
CBV-3	HEAT RECOVERY UNIT HRU-2 HEATING COIL	19#	0.170
CBV-4	HEAT RECOVERY UNIT HRU-3 HEATING COIL	38#	2.27
CBV-5	HEAT RECOVERY UNIT HRU-4 HEATING COIL	25#	0.953
CBV-6	CABINET UNIT HEATER CUH-1 HEATING COIL	19#	0.170
CBV-7	CABINET UNIT HEATER CUH-2 HEATING COIL	13#	0.038

## DIFFUSER / GRILLE SCHEDULE

ROOM		EQUIP. No.	SUPPLY AIR				RETURN / EXHAUST AIR			
			TYPE	QTY.	1/s	NECK SIZE	TYPE	QTY.	1/s	NECK SIZE
RTU-1	102 LUNCH/MEETING ROOM	TU-3	A	6	40	150ø	B	2	—	610x305
	103 TRAINING	TU-5	J	1	60	150ø	B	1	—	610x150
	104 ADMINISTRATION	TU-6	A	2	55	150ø	B	1	—	610x150
	109 OFFICE	TU-4	J	1	30	125	Q	1	—	405x355
HRU-1	111 OFFICE	TU-7	A	1	30	150ø	—	—	—	—
	112 OFFICE	TU-8	A	1	100	150ø	—	—	—	—
	110 WATER WORKS SHOP	TU-1 ACV-1	F	2	155	405x150	G	1	335	455x305
	117 TRADES SHOP	TU-2 ACV-2	F1 F2	3 15	160 255x100	405x150 255x100	G	1	520	760x305
HRU-2	101 CORRIDOR	—	A	5	60	150ø	—	—	—	—
	102 LUNCH/MEETING ROOM	—	H	1	160	255ø	E	1	25	150x100
	104 ADMINISTRATION	—	—	—	—	—	E	1	25	150x100
	105 MALE CHANGE ROOM	—	D	1	50	150ø	C	1	75	255x150
	106 FEMALE CHANGE ROOM	—	D	1	25	150ø	C	1	50	205x125
	107 WASHROOM	—	—	—	—	—	E	1	25	150x100
	108 WASHROOM	—	—	—	—	—	E	1	25	150x100
	110 WATER WORKS SHOP	—	—	—	—	—	G	1	30	150x150
	112 G.N. CHG. Rm. & SHOWER	—	—	—	—	—	C	1	30	150x100
	113 UNIVERSAL WASHROOM	—	—	—	—	—	E	1	25	150x100
	115 CUSTODIAL/P.P.E. STOR.	—	—	—	—	—	E	1	35	150x150
	116 SERVICE/UTILITY	—	—	—	—	—	G	1	10	150x150
HRU-3	117 TRADES SHOP	—	—	—	—	—	G	1	30	150x150
	118 SMALL EQUIPMENT	—	—	—	—	—	G	1	25	150x150
	119 WASHROOM	—	—	—	—	—	E	1	25	150x150
	124 BATT. CHARGING/STOR.	—	Q	1	—	405x355	E	1	25	150x100
	118 SMALL EQUIPMENT	—	F	1	150	305x205	F	1	150	305x205
	120 MECHANICS SHOP	—	N1 N2	3 6	270 265	510x255 510x255	M	8	465	760x305
	122 TOOL CRIB	—	S	1	25	255x100	—	—	—	—
	123 METAL FAB. SHOP	—	S	2	30	255x100	—	—	—	—
	125 WORK STATION	—	S	3	135	305x205	—	—	—	—
	126 TIRE SHOP	—	S	2	135	305x205	—	—	—	—
	127 STORAGE	—	—	—	—	—	E	1	40	150x150
	128 LUBE & SERVICE BAY	—	N	2	440	610x305	M	2	425	760x305
HRU-4	128A WASHBAY EQUIP. Rm.	—	—	—	—	—	E	1	30	150x100
	201 TRADE SHOP MEZZANINE	—	N	2	155	305x205	G	1	—	560x255
	201A BOILER ROOM	—	—	—	—	—	E	1	10	150x150
	202 MECHANICS SHOP MEZZ.	—	N	2	150	305x205	—	—	—	—
	129 AUTOMATIC WASHBAY TRANSPORT SERVICE BAY	—	K	2	1000	1220x305	L	2	1000	1220x305

REMARKS: TAB CONTRACTOR SHALL FIELD ADJUST ALL SUPPLY AIR GRILLE AIRFLOW BLADES AND DRUM LOUVER SPREAD CONTROL MEMBERS AS REQUIRED TO PROVIDE SUITABLE AIR FLOW PATTERNS FOR THEIR RESPECTED ZONES

## TERMINAL UNIT / AIR CONTROL VALVE SCHEDULE

(BASED ON EH. PRICE 'SDV' SINGLE DUCT TERMINAL UNITS AND 'RDV' AIR VOLUME CONTROL VALVES)

TERMINAL UNIT No.	SIZE	CONTROL ASSEMBLY	AREA SERVED	MIN./MAX. L/S
TU-1	205	RIGHT HAND	110 WATER WORKS SHOP	100/310
TU-2	255	RIGHT HAND	117 TRADES SHOP	165/495
TU-3	230	RIGHT HAND	102 LUNCH/MEETING	75/360
TU-4	100	RIGHT HAND	109 OFFICE	10/30
TU-5	100	RIGHT HAND	103 TRAINING	10/40
TU-6	125	RIGHT HAND	104 ADMINISTRATION	25/110
TU-7	100	LEFT HAND	111 OFFICE	10/30
TU-8	125	RIGHT HAND	121 OFFICE	20/100
ACV-1	205	RIGHT HAND	110 WATER WORKS SHOP	125/335
ACV-2	255	RIGHT HAND	117 TRADES SHOP	190/520

## DIFFUSER / GRILLE TYPES

(BASED ON PRICE INDUSTRIES PRODUCTS)

TYPE	DESCRIPTION
A	(SIZE AS NOTED)/610x610/SPD/31/B12
B	(SIZE AS NOTED)/80/NF/B12
C	(SIZED AS NOTED)/620/F/L/A/B12
D	(SIZE AS NOTED)/610x610/SPD/31/SPF/B12
E	(SIZE AS NOTED)/520/F/L/A/B12
F	SDGE / *(/SIZE AS NOTED)/DD/L/VCS3/A/B15
G	(SIZE AS NOTED)/530/F/L/A/B12
H	OPEN END DUCT
J	(SIZE AS NOTED)/305x305/SPD/31/B12
K	(SIZE AS NOTED)/AHC2/F/A/B15
L	(SIZE AS NOTED)/620D/L/F/L/A/B15
M	SDGER / *(/SIZE AS NOTED)/A/CA
N	(SIZE AS NOTED)/152/F/L/A/VCS5/B15
P	NOT USED
Q	(SIZE AS NOTED)/ATG2/BF/B15
R	NOT USED
S	SDGE / *(/SIZE AS NOTED)/DD/L/VCS3/A/CA

REMARKS:  
\* REFER TO DESIGN DRAWINGS FOR DUCT SIZE

[illegible]

Do not scale from this drawing. The Constructor shall verify all actual on-site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE



Project: **TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

Drawing Title:  
SCHEDULES

Drawn By: ER	Checked By: DS
-----------------	-------------------

Scale: N/A	Project No: 22-098
---------------	-----------------------

Date Plotted

Date Revised:

Drawing No:

# M703



SCOPE OF WORK -ABANDONED GASOLINE FUELING SYSTEM

- PURGE AND CLEAN ABANDONED UNDERGROUND GASOLINE STORAGE TANK AND ALL PIPING. CONTRACTOR IS RESPONSIBLE FOR DISPOSAL OF ANY REMAINING GASOLINE AND/OR SLUDGE WATER IN STORAGE TANK AND FUELING SYSTEM PRIOR TO REMOVAL.
- DISCONNECT UNDERGROUND PIPING FROM UNDERGROUND STORAGE TANK AND REMOVE COMPLETE WITH ALL SUPPORTS, APPURTENANCES, GASOLINE PUMP AND CONCRETE FUELING ISLAND.
- DECOMMISSION, EXCAVATE, CUT UP AND REMOVE ABANDONED UNDERGROUND GASOLINE STORAGE TANK COMPLETE WITH BACKFILL, DECOMMISSIONING TANKS TO BE REMOVED FROM SITE AND DISPOSED OF AT A LICENSED FACILITY AS PER TSSA REGULATIONS.
- CONSULTANT TO TAKE VERIFICATION SOIL SAMPLES AS PER TSSA REQUIREMENTS. SAMPLING AND TESTING BY TBT ENGINEERING LIMITED.
- UPON COMPLETION OF REMOVAL, BACKFILL, COMPACT AND GRADE EXCAVATED AREAS, REFER TO CIVIL DRAWINGS FOR REQUIREMENTS.
- CONTRACTOR IS RESPONSIBLE FOR ALL SITE LOCATES PRIOR TO STARTING UNDERGROUND WORK.

SCOPE OF WORK -FUEL OIL STATION AND INVENTORY MANAGEMENT SYSTEM

- DEMOLITION AND INSTALLATION OF NEW FUELING STATION AND FUEL INVENTORY MANAGEMENT SYSTEM SHALL BE SCHEDULED/COORDINATED WITH BUILDING OWNER TO MINIMIZE THE DISRUPTION OF THE FUELING SERVICE TO THE CLIENT.
- CONTRACTOR SHALL TRANSFER THE CLEAR AND COLOURED FUEL OILS FROM THE EXISTING STORAGE TANKS TO THE NEW FUELING STATION. CONTRACTOR SHALL PROVIDE TEMPORARY STORAGE FOR FUEL OILS AS REQUIRED.
- PURGE AND CLEAN FUEL OIL STORAGE TANKS, SUMPS AND ALL PIPING. CONTRACTOR IS RESPONSIBLE FOR DISPOSAL OF ANY SLUDGE WATER IN STORAGE TANKS, SUMPS AND FUELING SYSTEM PRIOR TO REMOVAL.
- DECOMMISSION SKID MOUNTED FUELING STATION AND COMPUTROL INVENTORY FUEL MANAGEMENT SYSTEM. CUT UP AND REMOVE ABOVE GROUND FUEL OIL STORAGE TANKS COMPLETE WITH SKID, SUMPS, FUEL OIL PIPING, PUMP AND APPURTENANCES. DECOMMISSIONED TANKS TO BE REMOVED FROM SITE AND DISPOSED OF AT A LICENSED FACILITY AS PER TSSA REGULATIONS. REFER TO ELECTRICAL DRAWINGS FOR FUEL OIL PUMP AND FUEL MANAGEMENT SYSTEM POWER/CONTROLS DEMOLITION REQUIREMENTS. CONTRACTOR TO PROVIDE PROOF OF DISPOSAL LETTER TO CONSULTANT.
- CONTRACTOR IS RESPONSIBLE FOR ALL SITE LOCATES PRIOR TO STARTING UNDERGROUND WORK.
- CONSULTANT TO TAKE VERIFICATION SOIL SAMPLES AS PER TSSA REQUIREMENTS. SAMPLING AND TESTING BY TBT ENGINEERING LIMITED.
- UPON COMPLETION OF REMOVAL, GRADE DEMOLITION AREA, REFER TO CIVIL DRAWINGS FOR REQUIREMENTS.
- PROVIDE NEW FUELING STATION AREA COMPLETE WITH CONCRETE FUEL STORAGE TANK CONCRETE SUPPORTS (REFER TO STRUCTURAL DRAWINGS) AND COLLISION PROTECTION (REFER TO ARCHITECTURAL DRAWINGS).
- SUPPLY AND INSTALL ONE (1) NEW 20,000L TRIPLE COMPARTMENT FUEL VAULT COMPLETE WITH ACCESS PLATFORM, FILL LIMITER VALVES, LEVEL GAUGES, LEAK DETECTORS, HI/HI/LEVEL/ALARM SENSORS, INVENTORY CONTROL PROBES, TURBINE PUMPS, STARTER, FILL BOXES, FUEL DISPENSERS AND APPURTENANCES AS INDICATED ON THE CONTRACT DRAWINGS.
- CONTRACTOR SHALL ASSEMBLE AND INSTALL ALL FUELING STATION "SHIPPED LOOSE" ITEMS, INCLUDING BUT NOT LIMITED TO, ACCESS LADDER, ACCESS PLATFORM, CATWALK, TANK VENTING, ETC. COMPONENTS SHALL BE ASSEMBLED AND INSTALLED AS PER MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS.
- PROVIDE NEW AUTOMATIC TANK GAUGE PANEL "ATG-1", INVENTORY MANAGEMENT AND CONTROL SYSTEM "IMC-1" AND FIRE EXTINGUISHER "FE-3 C/W ALL NECESSARY BRACKETS AND MOUNTING ACCESSORIES AS REQUIRED AND FASTEN TO END OF FUELING STATION SKID.
- PROVIDE ALL AUTOMATIC TANK GAUGE PANEL CONTROLS, PROBES, SWITCHES, ETC. AS INDICATED ON DESIGN DRAWINGS, CONNECT/WIRE COMPONENTS TO ASSOCIATED EQUIPMENT AS PER MANUFACTURER'S INSTRUCTION AND RECOMMENDATIONS AND AS REQUIRED TO PROVIDE A COMPLETE AND WORKING SYSTEM.
- SUPPLY AND INSTALL NEW BULK STORAGE TANK PLATFORM ASSEMBLY AS INDICATED ON DRAWINGS.
- PROVIDE A SPILL KIT IN THE FUEL OFFLOAD AREA AS SHOWN.
- PROVIDE LAMINATED TANK LEVEL GAUGE CHARTS AND SEQUENCE OF OPERATIONS FOR ALL FUEL STORAGE TANKS IN THE FUEL OFFLOAD AREA.

FUEL SYSTEM SPECIFICATIONS

GENERAL

- PROVIDE ALL LABOUR, MATERIAL, EQUIPMENT, FEES, PERMITS AND INSPECTIONS BY OUTSIDE AGENCIES AND CHARGES TO PERFORM ALL OPERATIONS FOR THE COMPLETE INSTALLATION OF THE FUEL STORAGE & DISPENSING SYSTEM AS INDICATED.
- ALL MATERIALS AND INSTALLATION IS TO COMPLY WITH THE ONTARIO BUILDING CODE, NFPA REGULATIONS, ONTARIO FIRE CODE, NATIONAL FIRE CODE, AND ONTARIO HYDRO ELECTRICAL CODE, AND LIQUID FUELS HANDLING CODE 2017.
- MAINTAIN INSURANCE TO FULLY PROTECT OWNER, CONSULTANT AND SELF FROM ANY AND ALL CLAIMS DUE TO ACCIDENTS, MISFORTUNES, ETC., TO LIMITS SET DOWN BY THE OWNER.
- REMOVE ALL WASTE MATERIALS AND CLEAN UP TO OWNER'S SATISFACTION. AT THE END OF THE JOB, CLEAN THE EQUIPMENT AND TOUCH UP FINISH TO RESTORE TO "AS NEW" CONDITION.
- ONLY FIRST CLASS WORKMANSHIP AND GOOD INSTALLATION PRACTICES WILL BE ACCEPTED. USE QUALIFIED TRADESMEN FOR ALL TYPES OF WORK.
- PROVIDE ALL NECESSARY HANGERS AND SUPPORT STEEL FOR YOUR WORK.
- BE RESPONSIBLE FOR ALL CUTTING AND PATCHING REQUIRED BY YOUR WORK.
- PROVIDE SHOP DRAWINGS TO CONSULTANT PRIOR TO ORDERING EQUIPMENT.
- VERIFY THAT ALL EXISTING AND NEW SIGNAGE IS IN ACCORDANCE WITH THE LIQUID FUELS HANDLING CODE 2017.

FIRE PROTECTION

- PROVIDE TYPE 80-B-C FIRE EXTINGUISHER COMPLETE WITH OUTDOOR FIRE EXTINGUISHER CABINET AS INDICATED ON DRAWINGS. STANDARD OF ACCEPTANCE: NATIONAL FIRE EQUIPMENT LTD.
- MOUNT EXTINGUISHER CABINETS AT LOCATIONS INDICATED ON THE DRAWINGS AND AT 1.2m (4'-0") TO TOP OF EXTINGUISHERS.
- UNDER DISPENSER FIRE SUPPRESSION UNITS MUST BE INSPECTED AS PART OF THE YEARLY FIRE EXTINGUISHER INSPECTION REQUIREMENTS AS PER THE ONTARIO FIRE CODE.

GENERAL NOTES

- FUEL STORAGE TANKS AND PIPING SYSTEM TO BE INSTALLED IN ACCORDANCE WITH LIQUID FUELS HANDLING CODE 2017.
- MISCELLANEOUS STEEL TO BE PREPPED IN ACCORDANCE WITH STANDARD SSPC-SP2.
- STRUCTURAL AND MISCELLANEOUS STEEL TO BE SHOP PRIMED WITH 1 COAT OF ZINC RICH PRIMER, 2 COATS ALKYD ENAMEL. COLOURS TO BE SPECIFIED BY THE OWNER.
- TOUCH UP PAINT ON NEW TANKS AND EQUIPMENT, ONCE INSTALLATION IS COMPLETED.
- CONTROL SYSTEM WHICH MEETS THE OPERATIONAL REQUIREMENTS AND PERFORMANCE SPECIFICATIONS INCLUDING ALL LEAK DETECTORS AND ALARMS MATCHING THE AUTOMATIC TANK GAUGE "ATG-1" AND INVENTORY MANAGEMENT SYSTEM "IMS-1".
- CONTRACTOR TO PROVIDE ALL NECESSARY ELECTRICAL/CONTROL COMPONENTS AND WIRING TO PROVIDE A COMPLETE AND OPERATIONAL SYSTEM.
- DURING CONSTRUCTION THE CONTRACTOR SHALL KEEP AN ACCURATE RECORD OF ALL DEVIATIONS BETWEEN THE WORK SHOWN ON THE DESIGN DRAWINGS AND THAT OF WHICH IS INSTALLED AND PROVIDE AS-BUILT DRAWINGS.
- THE CONTRACTOR SHALL REMOVE ALL WASTE MATERIALS AND CLEAN-UP TO THE ENGINEER'S SATISFACTION AT THE END OF THE JOB. CLEAN ALL NEW EQUIPMENT, TOUCH-UP FINISHES, AND RESTORE TO 'AS NEW CONDITION'.
- PROVIDE 2 SETS OF O&M MANUALS AND AS-BUILT DRAWINGS. MANUALS TO BE REVIEWED BY THE CONSULTANT.
- PROVIDE TRAINING TO THE MAINTENANCE PERSONNEL AT THE MARATHON PUBLIC WORKS FACILITY IN THE OPERATION AND MAINTENANCE OF THE NEW FUEL STORAGE/FILLING AND CONTROL SYSTEMS.
- THE CONTRACTOR SHALL PROVIDE LICENSED AND CERTIFIED TRADESMAN TO PERFORM ALL WORK IN ACCORDANCE WITH ONTARIO REGULATION 216/01 AND 215/01, ESA, AND OTHERS APPLICABLE.
- CONTAMINATED SOIL SAMPLING, TESTING BY TBT ENGINEERING. CONTRACTOR TO CARRY ALLOWANCES FOR REMEDIATION, REMOVAL, ETC. AS PER CONTRACT DOCUMENTS.
- IF CONTAMINATED MATERIALS/SOILS ARE ENCOUNTERED DURING THE CONTRACT, AN IMMEDIATE HALT OF WORK SHALL BE ORDERED. THE CONTRACTOR IS TO NOTIFY THE CONSULTANT OF THE CONTAMINATION AND IDENTIFY THE LOCATION AND EXTENT OF CONTAMINATION. REMEDIATION ACTIONS WILL BE PERFORMED BY GUIDELINES. CONTRACT WORK WILL PROCEED WHEN INSTRUCTED BY THE CONSULTANT.
- TEST AND COMMISSION NEW AND UPGRADED FUEL STORAGE AND CONTROL SYSTEMS.
- COMMISSION THE NEW FUEL STORAGE SYSTEM IN ITS ENTIRETY AND PROVIDE ALL CERTIFICATION DOCUMENTATION, APPROVAL DOCUMENTATION, TEST REPORTS, AND WARRANTY INFORMATION.
- SUBMIT SHOP DRAWINGS TO CONSULTANT PRIOR TO ORDERING EQUIPMENT.

PERFORMANCE SPECIFICATIONS

GENERAL

- CONTROL PANEL TO A HAVE A NEMA 4X ENCLOSURE RATING.
- AUTOMATIC TANK GAUGE PANEL (ATG-1) IS TO BE EQUIPPED WITH A LOCKABLE ENCLOSURE, SEALED WEATHERIGHT COMPLETE WITH STRIP HEATER AND WINDOW FOR VISIBLE GAUGING OF TANK LEVEL VIA DIGITAL LEVEL DISPLAY.
- AUTOMATIC TANK GAUGE PANEL (ATG-1) OPERATING TEMPERATURE RANGE OF 40°C TO -40°C OR BETTER.
- PROVIDE ALL NECESSARY ELECTRICAL POWER AND CONTROL APPURTENANCES INCLUDING WIRING AND CABLE TRAY TO ENSURE A FULLY OPERATIONAL SYSTEM.
- PROVIDE THE INSTRUMENTATION AND CONTROL EQUIPMENT AS SPECIFIED HEREIN AND AS INDICATED ON THE CONTRACT DRAWINGS.
- INSTRUMENTATION AND CONTROLS SUPPLIER IS TO PROVIDE THE FOLLOWING:
  - SUBMITTALS OF ALL EQUIPMENT SPECIFICATIONS, DRAWINGS, SCHEMATICS, AND COMPLETE INTERCONNECTING WIRING DIAGRAMS PRIOR TO PURCHASE AND INSTALLATION FOR REVIEW BY THE CONSULTANT.
  - CONTROL SYSTEM O&M MANUALS (2 COPIES).
  - TRAINING FOR MAINTENANCE AND OPERATIONS STAFF ON CONTROL SYSTEM OPERATION.
  - CONTROL SYSTEM AS-BUILT DRAWINGS (6 COPIES).
- PROVIDE ALL NECESSARY ADJUSTING, FIELD CALIBRATION, TESTING, AND COMMISSIONING OF CONTROL SYSTEM. SUBMIT WRITTEN TEST AND COMMISSIONING REPORT TO CONSULTANT FOR FINAL APPROVAL.
- CONTROLS PERFORMANCE SPECIFICATIONS TO BE READ IN CONJUNCTION WITH SEQUENCE OF OPERATIONS FOR BULK TANK FILLING & DISPENSING.

BULK TANK LEVEL TRANSMITTER -DIESEL/ DYED DIESEL/ GASOLINE

- OPERATING SIGNAL RANGE OF 4-20mA
- LEVEL IS DISPLAYED ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI DISPLAY IN PERCENTAGE AND VOLUME IN LITRES.
- LEVEL SIGNAL IS USED TO CALCULATE FUEL INVENTORY. TOTAL INVENTORY ON SITE IS DISPLAYED ON HMI.
- IF ANALOG PROBE IS DISCONNECTED OR SIGNAL IS LOST:
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ERROR ALARM ON HMI DISPLAY.
  - GENERATES HMI ALARM LOG ENTRY.
- IF LOW LEVEL SET POINT IS REACHED:
  - 6600 L TANK COMPARTMENT (15% OF TANK VOLUME)
  - AUTOMATIC TANK GAUGE PANEL (ATG-1) GENERATES A LOW LEVEL ALARM ON THE HMI DISPLAY.
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ALARM LOG ENTRY.
- IF HIGH LEVEL SET POINT IS REACHED:
  - 6600 L TANK COMPARTMENT (88% OF TANK VOLUME)
  - AUTOMATIC TANK GAUGE PANEL (ATG-1) GENERATES A HIGH LEVEL ALARM ON THE HMI DISPLAY.
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ALARM LOG ENTRY.
- IF HIGH/HIGH LEVEL SETPOINT IS REACHED:
  - 6600 L TANK COMPARTMENT (90%) OF TANK VOLUME)
  - AUTOMATIC TANK GAUGE PANEL (ATG-1) GENERATES A HIGH/HIGH LEVEL ALARM ON THE HMI DISPLAY.
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ALARM LOG ENTRY.

NOTE: MANUAL OVERFILL LIMITER VALVE TO BE SET TO 95% OF TANK VOLUME.

BULK TANK HI/ HI/ HI LEVEL SWITCH

- IF HIGH/HIGH/HIGH LEVEL SETPOINT IS REACHED:
  - 6600 L TANK COMPARTMENT (95% OF TANK VOLUME)
  - AUTOMATIC TANK GAUGE PANEL (ATG-1) GENERATES A HIGH/HIGH LEVEL ALARM ON THE HMI DISPLAY.
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ALARM LOG ENTRY.

NOTE: MANUAL OVERFILL LIMITER VALVE TO BE SET TO 95% OF TANK VOLUME.

BULK TANK AND SUMP LEAK DETECTOR

- IF A LEAK IS DETECTED IN THE BULK TANK INTERSTITIAL SPACE, DISPENSER SUMPS, FILL/SPILL BOXES:
  - POWER IS CUT OFF TO TURBINE PUMPS IN BULK TANKS.
  - AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES, GENERATES A LEAK DETECTION ALARM INDICATING WHICH LEAK DETECTOR IS IN ALARM ON THE HMI DISPLAY.
  - "INDICATOR LED" ON AUTOMATIC TANK GAUGE PANEL (ATG-1) HMI SCREEN FLASHES.
  - GENERATES HMI ALARM LOG ENTRY.

LABELING OF EQUIPMENT

CONTRACTOR IS TO PROVIDE 3MIL VINYL LABELS AS FOLLOWS:

- PRODUCT LABELS:
  - INSTALLED ON ALL SIDES OF EACH TANK
  - INSTALLED ON ALL PIPING
  - TANK LABELS TO HAVE A CHARACTER HEIGHT OF 100mm
  - PIPING LABELS TO HAVE A CHARACTER HEIGHT AND LABEL SPACING AS PER ANSI/ASME A13.1-2007
  - ALL CHARACTERS ARE TO BE BLACK IN COLOUR
- ENVIRONMENT CANADA IDENTIFICATION NUMBERS 'EC XXXXXXXXX':
  - INSTALLED ON ALL SIDES OF EACH TANK (STORAGE, SUPPLY, DAY AND WASTE OIL TANKS)
  - INSTALLED ON FUEL TRANSFER PUMP KIOSK & FUEL OFFLOAD KIOSK DOORS
  - TANK AND KIOSK LABELS TO HAVE A CHARACTER HEIGHT OF 75mm
- TANK BUNG LABELS:
  - INSTALLED ADJACENT TO EACH TANK BUNG
  - ALL BUNGS ARE TO BE LABELED. UNOCCUPIED BUNGS ARE TO BE LABELED 'SPARE'
  - LABEL TO IDENTIFY MECHANICAL EQUIPMENT OR PIPING OCCUPYING THE TANK BUNG (IE: LEVEL GAUGE, DIP PORT, FUEL OIL SUPPLY, ETC.)
  - BUNG LABELS TO HAVE A CHARACTER HEIGHT OF 25mm
- EQUIPMENT LABELS:
  - LABELS TO HAVE A CHARACTER HEIGHT OF 75mm
  - FUEL TRANSFER PUMPS
  - FILL/SPILL BOXES

CONTRACTOR IS TO LABEL ALL VALVES, GAUGES AND STRAINERS IN THE SYSTEM WITH PLASTIC TAGS COMPLETE WITH STAINLESS STEEL BEADED CHAIN. TAGS SHALL HAVE A SHAPE, SIZE, AND COLOUR IN ACCORDANCE WITH CANADIAN FUELS ASSOCIATION COLOUR-SYMBOL SYSTEM TO MARK EQUIPMENT AND VEHICLES FOR PRODUCT IDENTIFICATION.

CONTRACTOR IS TO PROVIDE LAMECOD LABELS FOR EACH SYSTEM CONTROL PANEL.

EQUIPMENT LIST

FS-1 FUELING STATION

WESTEEL PACKAGED SKID MOUNTED TRIPLE COMPARTMENT FUELING STATION CONSISTING OF THE FOLLOWING COMPONENTS:

PRODUCT No.HFV20000L TRIPLE COMPARTMENT DD/D/G HORIZONTAL FUEL VAULT KIT SUPPLIED COMPLETE WITH 118" (3048MM) HIGH, 11" (279MM) DIA. (4400 IMP. GAL.) TANK, THREE (3) 610mm SPILLBOX/TANK ACCESS OPENING (ONE PER COMPARTMENT) WITH 50# NPT GAUGE STICK PORT WITH CAMLOCK AND DUSTCAP AND ONE (1) 19mm NPT FITTING AND PLUG, ONE (1) 75mm NPT NORMAL VENT FITTING, INTEGRAL PRIMARY AND SECONDARY EMERGENCY VENTS, TWO (2) 100mm NPT FITTINGS, ONE (1) 50mm SECONDARY INSPECTION FITTING, TWO (2) 610mm WIDE SADDLES, TWO (2) GROUND LUGS, WHITE FINISH, UL/C SBOI-14 RATING, GAUGE STICK (SHIPPED LOOSE) AND TANK GAUGE (SHIPPED LOOSE).

THREE (3) PRODUCT No.900062 PIPE 3.00x48.00 (1219) ALUM TUE

TWO (2) PRODUCT No.900062 VENT 75mm ATMOSPHERIC 354-0300-AV

ONE (1) PRODUCT No. 276871 VENT 75mm PRESSURE/VACUUM 7495-1100-AV (80z. PRESSURE SETTING/0.50z. VACUUM SETTING)

TWO (2) PRODUCT No. TL1113 QMT HFV SPLIT - 2375mm# (93 1/2") SPLIT COMPARTMENT OPTION SUPPLIED COMPLETE WITH DOUBLE BULKHEAD WITH 50mm INSPECTION PORT WITH CAMLOCK AND DUSTCAP.

ONE (1) PRODUCT No. TL138 QMT HFV SKID - 20,000L STD SUPPLIED COMPLETE WITH W8x18 A36/44W BEAMS, 100mm NPS SCHEDULE 40 TOW PIPE BOTH ENDS, WHITE FINISH

ONE (1) PRODUCT No. TL175 QMT HFV SIDE LADDER/PLATFORM - 2375mm (93 1/2") SPLIT SIDE MOUNT LADDER PACKAGE SUPPLIED COMPLETE WITH 610mm WIDE PLATFORM ACCESS LADDER, 610mmW x 1830mmL PLATFORM WITH GALVANIZED GRATING WALKING SURFACE AND GALVANIZED STEEL HANDRAIL ON BOTH SIDES, WHITE FINISH FOR LADDER, CATWALK FRAME AND TOEPLATES.

ONE (1) PRODUCT No. TL230 QMT ACC EXTRA CATWALK SECTION SUPPLIED COMPLETE WITH 610mmW x 1830mmL PLATFORM WITH GALVANIZED GRATING WALKING SURFACE AND GALVANIZED STEEL HANDRAIL ON BOTH SIDES, WHITE FINISH FOR CATWALK FRAME AND TOEPLATES.

THREE (3) PRODUCT No. TL164 QMT PUMP PKG B 94 FEP 75 STP SINGLE HOSE INSTALLED PUMP PACKAGE SUPPLIED COMPLETE WITH 3/4hp 220 VAC SUBMERSIBLE TURBINE PUMP WITH ANTI-SIPHON KIT, PRE-WIRED INSPECTION READY PUMP CONTROLLER.

THREE (3) REMOTE TOP FILL FOR EACH COMPARTMENT.

THREE (3) PRODUCT No. TL351 QMT OVERFILL VALVE MRSN 9095x2" INSTALLED MORRISON FIGURE 9095X 50mm OVERFILL PREVENTION VALVE WITH ALUMINUM DROP TUBE.

THREE (3) PRODUCT No. TL394ULC QMT HFV VERT. ULC RTF - 93 1/2" TANK BOTTOM FILL SUPPLIED COMPLETE WITH 75mm NPS 150# FLANGED PIPE, 715-1F5-3MB0-0 75mm 38 LITER (2.0 GAL) REMOTE FILL BOX, 75mm ALUMINUM DROP PIPE, 75mm NPS ALUMINUM INLET CONNECTION WITH DUSTCAP AND INTEGRAL DRIP TRAY WITH COVER, WHITE FINISH.

THREE (3) PRODUCT No.101307 PULSER MODEL 800-F

THREE (3) PRODUCT No.909055 E VENT 6 EXTENSION SUPPLIED COMPLETE WITH INSTALLATION HARDWARE. SHIPPED LOOSE FOR FIELD INSTALLATION.

TWO (2) FACTORY INSTALLED DISPENSER SUMPS COMPLETE WITH ALL PIPING, FITTINGS AND SHEAR VALVES. SUMPS SHALL BE COMPATIBLE WITH FUEL DISPENSERS FD-1 AND FD-2.

GASBOY ATLAS 9800 SERIES ELECTRONIC DISPENSER, MODEL 9853KXTW2 HI-FLOW TWIN 2 DISPENSER, ELECTRONIC REGISTER, 83 L/MIN (22 GPM) FLOW RATING SUPPLIED COMPLETE WITH 25mm HIGH LCD DISPLAY WITH LED BACKLIGHT, LED LIGHTING TO IDENTIFY FUEL GRADE AND ILLUMINATED FRONT PANEL, FOUR PISTON CFT METER WITH FLOW THROUGH CENTER CHAMBER, 25mm INTERNAL PIPING, OPTIONAL PULSE OUTPUT FOR 3rd PARTY CONTROLLERS, ATLAS STANDARD DISPENSER INLET CENTERING KIT M07676K001, 115/1/60 POWER AND FOLLOWING COMPONENTS:

DISPENSER NOZZLE -TWO (2) REQUIRED  
OPW 11B PRESSURE SENSITIVE AUTOMATIC NOZZLE, MODEL: 11B-0900-B20, COMPLETE WITH YELLOW 2 PIECE HANDWARMER AND FILL GUARD, HOLD OPEN RACK, 19mm# (3/4") NPT INLET, 23mm# (15/16") OD SPOUT, SUITABLE FOR B20 BIODESEL.

DISPENSER HOSE -TWO (2) REQUIRED  
CONTITECH/GOODYEAR BC COLD FLEX HOSE ASSEMBLY, 19mm# (3/4") HOSE, MAXIMUM W.P. 345 KPA (50 PSI), 7.62m (25'-0") LENGTH, COMPLETE WITH 19mm# (3/4") SOLID X 19mm# (3/4") SWIVEL CRIMPED NPT END FITTINGS. COMPONENTS TO BE APPROVED, ASSEMBLED, MARKED, AND TESTED PER ULC REQUIREMENTS.

HOSE BUSHING -QUANTITY AS REQUIRED  
OPW HOSE BUSHING TO SUIT HOSE INSTALLATION.

HOSE RETRIEVER -TWO (2) REQUIRED  
UNIVERSAL HOSE RETRIEVER, MODEL: 871 MOUNTED ONTO 6.1M (10'-6") HIGH 50mm# (2") GALVANIZED PIPE COMPLETE WITH BASE AND COUNTERWEIGHTS.

HOSE BUN -TWO (2) REQUIRED  
UNIVERSAL HOSE BUN, MODEL: 100HB-100 SUITABLE FOR 19mm# (3/4") ID HOSE.

BREAKAWAY -TWO (2) REQUIRED  
OPW 66REC RECONNECTABLE BREAKAWAY, MODEL: 66REC-1000, 19mm# (3/4") NPT

SWIVEL -TWO (2) REQUIRED  
OPW 45 HOSE SWIVEL, MODEL: 45-5060, 19mm (3/4") MNPT X 19mm (3/4") FNPT

WHIP HOSE -TWO (2) REQUIRED  
CONTITECH/GOODYEAR BC COLD FLEX HOSE ASSEMBLY, 19mm# (3/4") HOSE, MAXIMUM W.P. 345 KPA (50 PSI), 250mm (9") LENGTH, COMPLETE WITH 19mm# (3/4") SOLID X 19mm# (3/4") SWIVEL CRIMPED NPT END FITTINGS. COMPONENTS TO BE APPROVED, ASSEMBLED, MARKED, AND TESTED PER ULC REQUIREMENTS.

AUTOMATIC FIRE SUPPRESSION -ONE (1) REQUIRED  
OPW FLEXWORKS AUTOMATIC FIRE SUPPRESSION SYSTEM, MODEL: FSS-50. FUSIBLE LINK TO ACTIVATE AT 79°C (173°F)

PARTICULATE FILTER -TWO (2) REQUIRED  
DONALDSON PARTICULATE FILTER, MODEL: DBB8777 COMPLETE WITH DONALDSON SINGLE FILTER HEAD, MODEL: P570330, 32mm# (1 1/4") NPT PORTS COMPLETE WITH DIFFERENTIAL GAUGE

WATER ABSORBING FILTER -TWO (2) REQUIRED  
DONALDSON WATER ABSORBING FILTER, MODEL: DBB0248 COMPLETE WITH DONALDSON SINGLE FILTER HEAD, MODEL: P570330, 32mm# (1 1/4") NPT PORTS COMPLETE WITH DIFFERENTIAL GAUGE

GASBOY ATLAS 9800 SERIES ELECTRONIC DISPENSER, MODEL 9853KX HI-FLOW SINGLE DISPENSER, ELECTRONIC REGISTER, 83 L/MIN (22 GPM) FLOW RATING SUPPLIED COMPLETE WITH 25mm HIGH LCD DISPLAY WITH LED BACKLIGHT, LED LIGHTING TO IDENTIFY FUEL GRADE AND ILLUMINATED FRONT PANEL, FOUR PISTON CFT METER WITH FLOW THROUGH CENTER CHAMBER, 25mm INTERNAL PIPING, OPTIONAL PULSE OUTPUT FOR 3rd PARTY CONTROLLERS, ATLAS STANDARD DISPENSER INLET CENTERING KIT M07676K001, 115/1/60 POWER AND FOLLOWING COMPONENTS:

DISPENSER NOZZLE -ONE (1) REQUIRED  
OPW 11B PRESSURE SENSITIVE AUTOMATIC NOZZLE, MODEL: 11B-0900-B20, COMPLETE WITH YELLOW 2 PIECE HANDWARMER AND FILL GUARD, HOLD OPEN RACK, 19mm# (3/4") NPT INLET, 23mm# (15/16") OD SPOUT, SUITABLE FOR B20 BIODESEL.

DISPENSER HOSE -ONE (1) REQUIRED  
CONTITECH/GOODYEAR BC COLD FLEX HOSE ASSEMBLY, 19mm# (3/4") HOSE, MAXIMUM W.P. 345 KPA (50 PSI), 7.62m (25'-0") LENGTH, COMPLETE WITH 19mm# (3/4") SOLID X 19mm# (3/4") SWIVEL CRIMPED NPT END FITTINGS. COMPONENTS TO BE APPROVED, ASSEMBLED, MARKED, AND TESTED PER ULC REQUIREMENTS.

HOSE BUSHING -QUANTITY AS REQUIRED  
OPW HOSE BUSHING TO SUIT HOSE INSTALLATION.

HOSE RETRIEVER -ONE (1) REQUIRED  
UNIVERSAL HOSE RETRIEVER, MODEL: 871 MOUNTED ONTO 6.1M (10'-6") HIGH 50mm# (2") GALVANIZED PIPE COMPLETE WITH BASE AND COUNTERWEIGHTS.

HOSE BUN -ONE (1) REQUIRED  
UNIVERSAL HOSE BUN, MODEL: 100HB-100 SUITABLE FOR 19mm# (3/4") ID HOSE.

BREAKAWAY -ONE (1) REQUIRED  
OPW 66REC RECONNECTABLE BREAKAWAY, MODEL: 66REC-1000, 19mm# (3/4") NPT

SWIVEL -ONE (1) REQUIRED  
OPW 45 HOSE SWIVEL, MODEL: 45-5060, 19mm (3/4") MNPT X 19mm (3/4") FNPT

FLOW REGULATOR -ONE (1) REQUIRED  
OPW 44 FLOW LIMITER, MODEL: 44-0044, 19mm (3/4") FNPT X 19mm (3/4") FNPT

WHIP HOSE -ONE (1) REQUIRED  
CONTITECH/GOODYEAR BC COLD FLEX HOSE ASSEMBLY, 19mm# (3/4") HOSE, MAXIMUM W.P. 345 KPA (50 PSI), 250mm (9") LENGTH, COMPLETE WITH 19mm# (3/4") SOLID X 19mm# (3/4") SWIVEL CRIMPED NPT END FITTINGS. COMPONENTS TO BE APPROVED, ASSEMBLED, MARKED, AND TESTED PER ULC REQUIREMENTS.

AUTOMATIC FIRE SUPPRESSION -ONE (1) REQUIRED  
OPW FLEXWORKS AUTOMATIC FIRE SUPPRESSION SYSTEM, MODEL: FSS-50. FUSIBLE LINK TO ACTIVATE AT 79°C (173°F)

FILTER -ONE (1) REQUIRED  
DMTEK 70012 DISPENSER FILTER, MODEL: 300-30, PARTICULATE FILTER COMPLETE WITH 50002 CAST IRON MOUNTING ADAPTER, 25mm# (1") NPT INLET AND OUTLET

EQUIPMENT LIST -CONTINUED

ATG-1 AUTOMATIC TANK GAUGE PANEL ONE (1) REQ'D  
VEEDER ROOT MODEL TLS-450PLUS AUTOMATIC TANK GAUGE SYSTEM SUPPLIED COMPLETE WITH PART No.860091-401 TLS-450PLUS CONSOLE WITH 205mm (8") WYGA COLOUR TOUCH SCREEN DISPLAY, NO PRINTER, THREE (3) ETHERNET AND DUAL USB/EXPANSION, DUAL RS-232, UL/C/UL, PART No.333545-001 APPLICATION SOFTWARE WITH WEB-ENABLED STORAGE, TLS EXPANSION, STATIC LEAK DETECTION, 30PH DP/LD, STANDARD HARDWARE INCLUDING 3 PORT ETHERNET MODULE (COMM SLOT 4), 2 PORT USB MODULE (COMM SLOT 5), 3 MODULE COMPARTMENTS, PART No.332812-001 FACTORY INSTALLED MODULE WITH UNIVERSAL SENSOR MODULE (USM) INTERFACE FOR ALL PROBES, SENSORS AND DP/LD, PART No.332813-001 FACTORY INSTALLED MODULE WITH UNIVERSAL INPUT/OUTPUT INTERFACE MODULE (UIOM) FOR RELAY CONTROL AND INPUT SIGNAL MONITORING, SUITABLE INPUTS FOR THREE (3) HIGH LEVEL SWITCHES, INDEPENDENT OF MAG LEVEL, GAUGES FOR TANK LEVEL MONITORING, MODULES AS REQUIRED TO SUIT INSTALLATION OF EIGHT (8) LEAK DETECTORS (3 LEAK DETECTORS SUITABLE FOR GASOLINE, 5 DETECTORS SUITABLE FOR #2 DIESEL FUEL), 120V POWER

IMC-1 INVENTORY MANAGEMENT CONTROL ONE (1) REQ'D  
COMPUTROL SIMCOM FUEL MANAGEMENT SYSTEM SUPPLIED COMPLETE WITH NEMA R3 RATING, THERMOSTATICALLY CONTROLLED HEATER, INSULATED WEATHER COVER, TANK LEVEL MONITORING SYSTEM INTERFACE, CARD/CODE CAPACITY, TRANSACTION MEMORY, 1-32 HOSE CAPACITY, STAINLESS STEEL KEY PAD, ALPHA-NUMERIC KEYPAD ENTRY, FULL COLOUR SCREEN, PROXIMITY CARD/FOB, MAG STRIPE AND COIL CARD READER/CARD TYPES, TRANSACTION/DAILY/POLLING LIMITS, FUEL LIMIT PER CARD CODE CAPABILITIES, PRODUCT REGISTRATION, PRODUCT GRADES, 2-CARD DRIVER/VEHICLE SYSTEM, WEB-BASED MANAGEMENT SOFTWARE AND SQL DATABASE HOSTED IN THE "CLOUD", REAL-TIME/POLLING INTERVAL DATA SYNC WITH SOFTWARE, ODOMETER/HOURMETER VERIFICATION, CUSTOM MESSAGES, AUDIT PRINTER SUPPORT, AUTOMATIC SWITCHING BETWEEN REAL-TIME AND STANDALONE OPERATION MODES IN THE EVENT OF NETWORK COMMUNICATIONS FAILURE, MULTI-LAYER SECURITY AND ENCRYPTION METHODS AND 110-120/1/60 POWER.

ICP-1 INVENTORY CONTROL PROBE TWO (2) REQ'D  
VEEDER ROOT PART No.846397-3XX STAINLESS STEEL MAG PLUS IN-TANK PROBE SUPPLIED COMPLETE WITH HIGH GRADE POLYMER CANISTER WITH WATER DETECTION AND NO LEAK DETECTION/INVENTORY ONLY, PART No.332812-001 PROBE INTERFACE MODULE WITH UNIVERSAL SENSOR MODULE (USM) INTERFACE FOR PROBES, SENSORS AND DP/LD, 4 MODULES PER CONSOLE, 16 PROBE INPUTS PER MODULE, PART No.846400-1X1 MAG PLUS DIESEL FLOAT KIT AND PART No.312020-984 AST INSTALLATION KIT.

ICP-2 INVENTORY CONTROL PROBE ONE (1) REQ'D  
VEEDER ROOT PART No.846397-3XX STAINLESS STEEL MAG PLUS IN-TANK PROBE SUPPLIED COMPLETE WITH HIGH GRADE POLYMER CANISTER WITH WATER DETECTION AND NO LEAK DETECTION/INVENTORY ONLY, PART No.332812-001 PROBE INTERFACE MODULE WITH UNIVERSAL SENSOR MODULE (USM) INTERFACE FOR PROBES, SENSORS AND DP/LD, 4 MODULES PER CONSOLE, 16 PROBE INPUTS PER MODULE, PART No.No.846400-1X0 MAG PLUS GASOLINE FLOAT KIT AND PART No.312020-984 AST INSTALLATION KIT.

HLS-1 HI/HI/HI LEVEL/ALARM SENSOR THREE (3) REQ'D  
KTECH INDUSTRIES PRODUCTS INC. PART No.FS801E-1 OVERFILL PROTECTION DEVICE SUPPLIED COMPLETE WITH 8mm (5/16") O.D. STAINLESS STEEL STEM, 25mm# (1") 316 STAINLESS STEEL FLOAT, 25mm (1") NPT BUSHING, EXPLOSION PROOF J-BOX, FACTORY SET NORMALLY OPEN (NO) CONTACT ARRANGEMENT, 120V DC/AC MAXIMUM SWITCHING VOLTAGE, 0.4 AMPS DC/AC MAXIMUM SWITCHING CURRENT, 50 VOLT/AMPS DC/AC MAXIMUM SWITCHING POWER.

NOTE: CONTRACTOR SHALL CONFIRM LENGTH REQUIREMENTS BASED ON 95% HI/HI TANK LEVEL

LD-1 LEAK DETECTOR THREE (3) REQ'D  
VEETER ROOT PART No.794390-420 INTERSTITIAL SENSOR SUPPLIED COMPLETE WITH 4880mm (16'-0") LONG CABLE, SUITABLE FOR ANNULAR SPACES, GAS/DIESEL FUEL COMPATIBILITY, 64x38# (2 1/2" x 1 1/2") SENSOR AND PART No.312020-928 50mm (2") INTERSTITIAL SENSOR RISER CAP AND ADAPTOR KIT.


LD-2 LEAK DETECTOR FIVE (5) REQ'D  
VEETER ROOT PART No.794390-420 INTERSTITIAL SENSOR SUPPLIED COMPLETE WITH 4880mm (16'-0") LONG CABLE, SUITABLE FOR ANNULAR SPACES, GAS/DIESEL FUEL COMPATIBILITY AND 64x38# (2 1/2" x 1 1/2") SENSOR.

FE-3 FIRE EXTINGUISHER TWO (2) REQ'D  
NATIONAL FIRE EQUIPMENT LIMITED MODEL B10P (PART NUMBER 23778) BADGER PURPLE "K" DRY CHEMICAL FIRE EXTINGUISHER SUPPLIED COMPLETE WITH 10lbs CAPACITY, 80-B-C UL FIRE RATING, PURPLE "K" AGENT TYPE, 0.45 lb/SEC AGENT FLOW RATE, STEEL CYLINDER, PLATED BRASS VALVE, STAINLESS STEEL HANDLER/LEVER, NITROGEN EXPELLANT, -40°C TO 48.9°C (NO) CONTACT ARRANGEMENT, 120V DC/AC MAXIMUM SWITCHING VOLTAGE, 0.4 AMPS DC/AC MAXIMUM SWITCHING CURRENT, 50 VOLT/AMPS DC/AC MAXIMUM SWITCHING POWER.


SPILL KIT  
LARGE SPILL KIT SUPPLIED COMPLETE WITH SOCKS, PADS AND ACCESSORIES FOR ABSORPTION OF UP TO 250L (65 GAL) OF FUEL

										Revision 0 JULY 28 / 22 ISSUED FOR PERMIT AND TENDER Date	
Do not scale from this drawing. The Contractor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.											
CRITCHLEY HILL ARCHITECTURE						TBT ENGINEERING CONSULTING GROUP					
Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY Marathon, Ontario Drawing Title: SCOPE OF WORK, SPECIFICATIONS AND EQUIPMENT LIST Checked By: DS Scale: N/A Project No: 22-098 Date Plotted: Date: JULY 2022 Drawing No: M801											







DEMOLITION SITE PLAN - ELECTRICAL SITE SERVICES  
SCALE: 1:500




RENOVATION SITE PLAN - ELECTRICAL SITE SERVICES  
SCALE: 1:500



1 TRENCH DETAIL - PRIMARY FEED TO TRANSFORMER  
E002 SCALE: N.T.S.



2 TRENCH DETAIL - SECONDARY FEED - TRANSFORMER TO BUILDING  
E002 SCALE: N.T.S.



ENLARGED PARTIAL SITE PLAN - ELECTRICAL SITE SERVICES - PAD MOUNTED TRANSFORMER & POWER FEEDS  
SCALE: 1:300

ALL TRENCHING, AND CONCRETE BASES, INDICATED HEREIN, SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR

ELECTRICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

CONTRACTOR TO PROVIDE AND INSTALL NEW TRANSFORMER BASE COMPLETE WITH GROUND GRID REQUIREMENTS. COORDINATE LOCATION WITH HYDRO ONE REFER TO TRANSFORMER BASE DETAILS ON THIS DRAWING. TRANSFORMER PROVIDED AND INSTALLED BY HYDRO ONE.


UNDERGROUND CONDUIT FROM PROPERTY LINE TO EXISTING BELL TELEPHONE PEDESTAL TO BE COMPLETED BY CASH ALLOWANCE.

TRANSFORMER 'T1'. REFER TO ENLARGED PLAN THIS DRAWING.

REFER TO PRIMARY TRENCH DETAIL.

PROVIDE NEW POLE MOUNTED AREA LIGHT AS INDICATED. REFER TO DETAIL FOR SITE LUMINAIRE.

UNDERGROUND ELECTRICAL & MECHANICAL SERVICES EXIST ON THE PROPERTY. CONTRACTOR TO PERFORM A LOCATE TO MAKE THEMSELVES AWARE OF THEIR LOCATION AND TAKE CARE WHEN EXCAVATING IN THEIR VICINITY.



Revision	Date	Issued For Permit and Tender
0	JULY 28 / 22	

Do not scale from this drawing. The Contractor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project:  
TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario

Drawn By:  
NL


Scale:  
AS NOTED

Date Plotted:

Date Revised:  
JULY 2022

Drawing No:


E002




#### NOTES:

- ALL CONNECTIONS TO THE TRANSFORMER GROUND RODS THAT ARE TO BE PERMANENTLY BURIED SHALL BE MADE WITH APPROVED THERMITE WELD, COMPRESSION CONNECTORS OR AN APPROVED MECHANICAL CONNECTOR.
- WHERE REQUIRED TO BE BONDED, THE LOW VOLTAGE NEUTRAL 'XO' OF THE TRANSFORMER SHALL BE BONDED TO GROUND WITH A MINIMUM #3/0AWG COPPER CONDUCTOR.


TRANSFORMER GROUND GRID DETAILS  
FOR PRECAST PAD MOUNT TRANSFORMER




TRANSFORMER PAD ENCLOSURE DETAILS  
SCALE: N.T.S.




3 TRENCH DETAIL - BELL TRENCH  
E003 SCALE: N.T.S.




4 TRENCH DETAIL - GATE OPERATOR (TYP.2)  
E003 SCALE: N.T.S.




5 TRENCH DETAIL - COLD STORAGE  
E003 SCALE: N.T.S.



A SECTION - GATE ENTRY ACCESS SECTION  
E003 SCALE: 1:20




6 DETAIL - GATE ENTRY ACCESS PLAN  
E003 SCALE: 1:20



#### NOTES:

- 200MM NOMINAL DIAMETER BOLLARDS ARE FOR EXTERIOR BUILDING APPLICATIONS.
- PAINT NOTE:  
PRIME COAT: 1-SHOP  
FINISH COAT: 2-FIELD

7 DETAIL - BOLLARD  
E003 SCALE: 1:20



8 DETAIL - PARKING LOT LIGHT STANDARD  
E003 SCALE: N.T.S.

ELECTRICAL DRAWINGS SHALL BE READ IN  
CONJUNCTION WITH ALL DESIGN DRAWINGS.

Revision	Date	Issued For Permit and Tender
0	JULY 28 / 22	ISSUED FOR PERMIT AND TENDER

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE  
TBT ENGINEERING  
CONSULTING GROUP

Project: TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY  
Marathon, Ontario  
Drawing Title: ELECTRICAL SITE SERVICES  
ELECTRICAL DETAILS  
TRENCH DETAILS, POWER AND COMMUNICATIONS

Drawn By: NL  
Checked By: JK  
Scale: AS NOTED  
Project No: 22-098  
Date Plotted:

Date Revised:  
JULY 2022

Drawing No:  
**E003**

# E004




120/208 VOLT 225 AMP MAINS 3 PHASE, 4 WIRE			TYPE : PRL1A MOUNTING : SURFACE FED FROM : P1			PANEL 'B'										REMARKS: 22KA BREAKER RATINGS			LOCATION : BOILER RM 201A		
NOTES	DESCRIPTION OF LOAD	WATTAGE			CCT No.	BKR AMP	SN			BKR AMP	CCT No.	WATTAGE			DESCRIPTION OF LOAD	NOTES					
		#A	#B	#C			A	B	C			#A	#B	#C							
	BOILER B1				1	15	◆			15	2				PUMPS P1a & P1b						
	BOILER B2				3	15		◆			4										
	BOP-1				5	15			◆	15	6				DHW RECIRC. PUMP P2						
	BOP-2				7	15	◆			15	8				GYCOL FEEDER GF-1						
	UH-1,2,3 / CUH-2				9	15		◆		15	10				WATER HEATER WH-1						
	TRAP SEAL PRIMER TSP-1				11	15			◆	15	12				WATER HEATER WH-2						
	RECEPT. - BOILER RM 201A				13	20	◆			15	14				LIGHTING - BOILER RM, TRADE MEZZ.						
					15			◆		15	16										
	HRU-2				17	20			◆	15	18				ELEC. ROOM AC SYSTEM						
					19		◆			50	20										
	RECEPT. - MEZZ 201 - NORTH				21	15		◆		22					CU-1						
	RECEPT. - MEZZ 201/STAIRS				23	15		◆		20	24				CU-1 MAINTENANCE RECEPT.						
					25		◆				26										
					27			◆			28										
					29				◆		30										
					31		◆				32										
					33			◆			34										
					35				◆		36										
					37		◆				38										
					39			◆			40										
					41				◆		42										
					43		◆				44										
					45			◆			46										
					47				◆		48										
					49		◆				50										
					51			◆			52										
					53				◆		54										
					55		◆				56										
					57			◆			58										
					59				◆		60										
					61		◆				62										
					63			◆			64										
					65				◆		66										
					67		◆				68										
					69			◆			70										
					71				◆		72										
					73		◆				74										
					75			◆			76										
					77				◆		78										
	SPARE				79	15	◆			15	80				SPARE						
	SPARE				81	15		◆		15	82				SPARE						
	SPARE				83	15			◆	15	84				SPARE						

120/208 VOLT 225 AMP MAINS 3 PHASE, 4 WIRE			TYPE : PRL1A MOUNTING : SURFACE FED FROM : P1			PANEL 'C'			REMARKS: 22KA BREAKER RATINGS			LOCATION : TRADE SHOP RM 117				
NOTES	DESCRIPTION OF LOAD	WATTAGE			CCT No.	BKR AMP	SN			BKR AMP	CCT No.	WATTAGE			DESCRIPTION OF LOAD	NOTES
		#A	#B	#C			A	B	C			#A	#B	#C		
	HRU-1 MAINTENANCE RECEPT.				1	20	+			15	2				TSPM-1	
	O/H DOOR - WATER WORKS				3	15				4					O/H DOOR - TRADE SHOP	
	RECEPT. - WATER OFFICE RM 109				5					6						
	EXT. RECEPT. - WATER WORKS				7	15	+			15	8				RECEPT. - TRADES OFFICE	
	EXT. RECEPT. - WATER WORKS				9	20				20	10				EXT. RECEPT. - TRADES SHOP	
	EXT. RECEPT. - TRADES SHOP				11	20				20	12				EXT. RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				13	20	+			20	14				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				15	20				20	16				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				17	20				20	18				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				19	20	+			20	20				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				21	20				20	22				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				23	20				20	24				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				25	20	+			20	26				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				27	20				20	28				RECEPT. - TRADES SHOP	
	RECEPT. - WATER WORKS				29	20				20	30				RECEPT. - TRADES SHOP	
	RECEPT. - TRADES SHOP				31	20	+			20	32				RECEPT. - TRADES SHOP	
	RECEPT. - TRADES SHOP				33	20				20	34				RECEPT. - TRADES SHOP	
	EXT. RECEPT. - WATER WORKS				35	20				30	36				TABLE SAW - TRADES SHOP	
	EXT. RECEPT. - TRADES SHOP				37	20	+				38					
	EXT. RECEPT. - TRADES SHOP				39	20					40					
	EXT. RECEPT. - TRADES SHOP				41	20					42					
					43		+				44					
					45						46					
					47						48					
					49		+				50					
					51						52					
					53						54					
					55		+				56					
					57						58					
					59						60					
					61		+				62					
					63						64					
					65						66					
					67		+				68					
					69						70					
					71						72					
					73		+				74					
					75						76					
					77						78					
	SPARE				79	15	+			15	80				SPARE	
	SPARE				81	15				15	82				SPARE	
	SPARE				83	15				15	84				SPARE	

120/208 VOLT 225 AMP MAINS 3 PHASE, 4 WIRE			TYPE : PRL1A MOUNTING : SURFACE FED FROM : P1			PANEL 'D'												REMARKS: 22KA BREAKER RATINGS											
						LOCATION : MECH. SHOP RM 120																							
NOTES	DESCRIPTION OF LOAD	WATTAGE			CCT No.	BKR AMP	SN			BKR AMP	CCT No.	WATTAGE			DESCRIPTION OF LOAD	NOTES													
		#A	#B	#C			A	B	C			#A	#B	#C															
	LIGHTING – MECH. SHOP RM 120–EAST				1	20	◆				2																		
	LIGHTING – MECH. SHOP RM 120–WEST				3	20	◆				4																		
	WELDER – FAB SHOP				5	50	◆				6																		
					7		◆				8																		
	WELDER – FAB SHOP				9	50	◆				10																		
					11		◆				12																		
	RECEPT. – BATTERY CHARGE RM 124				13	20	◆				14																		
	RECEPT. – BATTERY CHARGE RM 124				15	20	◆				15																		
	HEAT TRACE – RM 124				17	15*	◆				18																		
	RECEPT. – FAB SHOP RM 123				19	20	◆				20																		
	RECEPT. – FAB SHOP RM 123				21	20	◆				15																		
	RECEPT. – FAB SHOP RM 123				23	20	◆				24																		
	RECEPT. – FAB SHOP RM 123				25	20	◆				15																		
	RECEPT. – TOOL CRIB RM 122				27	20	◆				15																		
					29		◆				30																		
	O/H DOOR – SHOP SOUTH WEST				31	15	◆				15																		
							◆				32																		
					33		◆				34																		
	O/H DOOR – SHOP SOUTH MIDDLE				35	15	◆				15																		
							◆				36																		
	CORD REEL – NORTH WEST				37	20	◆				20																		
	EXT. RECEPT. – SHOP NORTH				39	20	◆				20																		
	EXT. RECEPT. – SHOP NORTH				41	20	◆				40																		
	RECEPT. – SHOP WEST				43	20	◆				20																		
	RECEPT. – SHOP WEST				45	20	◆				20																		
	RECEPT. – SHOP WEST				47	20	◆				48																		
	RECEPT. – SHOP WEST				49	20	◆				50																		
	RECEPT. – SHOP WEST				51	20	◆				52																		
					53		◆				54																		
					55		◆				56																		
					57		◆				58																		
					59		◆				60																		
					61		◆				62																		
					63		◆				64																		
					65		◆				66																		
					67		◆				68																		
					69		◆				70																		
					71		◆				72																		
					73		◆				74																		
					75		◆				76																		
					77		◆				78																		
	SPARE				79	15	◆				15				SPARE														
	SPARE				81	15	◆				15				SPARE														
	SPARE				83	15	◆				15				SPARE														








Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



CRITCHLEY HILL  
ARCHITECTURE



**TOWN OF MARATHON  
NEW PUBLIC WORKS FACILITY**  
Marathon, Ontario

Drawing Title:  
ROOF PLAN  
ELECTRICAL REQUIREMENTS

Drawn By: NI	Checked By: .JK
-----------------	--------------------


Scale: AS NOTED	Project No: 22-098
--------------------	-----------------------

Date Plotted:

Date Revised:  
JULY 2022

Drawing No: **5004**

## E201




MAIN FLOOR PLAN - LIFE SAFETY REQUIREMENTS  
SCALE: 1:100

**NOTE:**  
EMERGENCY LIGHTING BATTERY PACKS SHALL MONITOR THE FOLLOWING LIGHTING CIRCUITS USING ZONE RELAYS:

- EM1: A-7,9,11,13,15,17
- EM2: D-1,3
- EM3: E-1,2,3,4

PROVIDE ZONE CONTROL BOX WITH APPROPRIATE QUANTITY OF ZONES



MEZZANINE FLOOR PLAN - LIFE SAFETY REQUIREMENTS  
SCALE: 1:100

ELECTRICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

<p>Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY Marathon, Ontario</p> <p>Drawn By: NL</p> <p>Scale: AS NOTED</p> <p>Date Plotted:</p> <p>Date Revised: JULY 2022</p> <p>Drawing No:</p>	<p>Checked By: JK</p> <p>Project No: 22-098</p> <p>Revision</p> <p>Date</p> <p>ISSUED FOR PERMIT AND TENDER JULY 28 / 22</p>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------


CRITCHLEY HILL  
ARCHITECTURE

**TBT ENGINEERING**  
CONSULTING GROUP


LICENSED PROFESSIONAL ENGINEER  
J. R. KIERSTEAD  
100181072  
Jul 28 / 22  
PROVINCE OF ONTARIO

Project Title:  
MAIN FLOOR PLAN  
MEZZANINE PLAN  
LIFE SAFETY REQUIREMENTS  
FIRE ALARM ZONING


**E300**



MAIN FLOOR PLAN - FIRE ALARM ZONING  
SCALE: 1:200



MEZZANINE FLOOR PLAN - FIRE ALARM ZONING  
SCALE: 1:200



FIRE ALARM RISER DIAGRAM - PUBLIC WORKS  
SCALE: N.T.S.

- NOTES:**
1. QUANTITIES SHOWN ARE NOT INDICATIVE OF ACTUAL REQUIREMENTS.
  2. REFER TO PLANS FOR QUANTITIES AND LOCATIONS OF DETECTION AND SIGNALING DEVICES.
  3. FIRE ALARM DEVICES SHALL BE ADDRESSABLE.
  4. CO-ORDINATE WITH MECHANICAL CONTRACTORS FOR DUCT SMOKE LOCATIONS IN SUPPLY DUCTS.
  5. EACH DUCT TYPE SMOKE DETECTOR TO BE ADDRESSED AS SEPARATE ZONES.
  6. PROVIDE ISOLATION MODULES PER CAN/ULC-S524
  12. PROVIDE NEW ZONING MAP ADJACENT TO FIRE ALARM ANNUNCIATOR.

ELECTRICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL DESIGN DRAWINGS.

CRITCHLEY HILL ARCHITECTURE		TBT ENGINEERING CONSULTING GROUP	
Project: TOWN OF MARATHON NEW PUBLIC WORKS FACILITY Marathon, Ontario		Drawing Title: MAIN FLOOR PLAN MEZZANINE PLAN FIRE ALARM ZONING FIRE ALARM RISER DIAGRAM	
Drawn By: NL	Checked By: JK	Scale: AS NOTED	Project No: 22-098
Date Plotted:			
Date Revised: JULY 2022			
Drawing No: <b>E301</b>			

ISSUED FOR PERMIT AND TENDER

0

Revision

Date

JULY 28 / 22

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.

LICENSED PROFESSIONAL ENGINEER  
J. R. KIERSTED  
100181072  
Jul 28 / 22  
PROVINCE OF ONTARIO



## LIGHTING

- LIGHTING CONTACTOR - 'LC1'

- ## EMERGENCY LIGHTING

### EMERGENCY LIGHTING ZONE CONTROL BOX

- ## EXIT SIGNS

PHOTOCELL

1. ALL SENSOR LOCATIONS ARE

VOICE/DATA

- CAT 6 CABLE

VOICE/DATA - CONT'D

- ## MOUNTING HEIGHTS OF NEW FIRE ALARM EQUIPMENT

## 1. REMOTE ANNUNCIATOR

- ## FIRE ALARM

2. A


FIRE ALARM - CONT'D

- ## FIRE ALARM SYSTEM - WIRING

- FIRE ALARM MAP

- VANDAL RESISTANT SLIM PROFILE THAT MOUNTS DIRECTLY TO THE WALL.

Do not scale from this drawing. The Constructor shall verify all actual on site dimensions and report any discrepancies to the Consultant prior to proceeding with the work.



Drawn By: NL	Checked By: JK
-----------------	-------------------

Scale: AS NOTED	Project No: 22-098
--------------------	-----------------------

Date Plotted: \_\_\_\_\_  
Date Reviewed: \_\_\_\_\_

JULY 2022

Drawing No:

## E401

ELECTRICAL DRAWINGS SHALL BE READ IN  
CONJUNCTION WITH ALL DESIGN DRAWINGS.

## POWER AND CONTROL

- ## POWER AND CONTROL - GENERAL

1. POWER WIRING FOR ALL EQUIPMENT LISTED ABOVE TO BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS. INSTALLATION AND WIRING OF ALL 24 VOLT CONTROL EQUIPMENT ASSOCIATED WITH ABOVE LISTED EQUIPMENT (I.E. THERMOSTATS, ETC.) TO BE PERFORMED BY THE MECHANICAL DIVISION.

## ACCESS CONTROL SYSTEM

## VIDEO SURVEILLANCE SYSTEM

ELECTRICAL DRAWINGS SHALL BE READ IN  
CONJUNCTION WITH ALL DESIGN DRAWINGS.