



May 15, 2026

Project No. 25-055

TO: All Bidders

PROJECT: Marathon WWTP Upgrades

This addendum forms part of the Contract Documents. Include the related costs in the Tender Prices. Insert the Addendum behind the front page of the Contract Documents.

General

Qn. Is there a lighting fixture schedule? The drawing provides a product number but no other information regarding the specified lights is available.

Explosion proof area light, Class 1 division 1 rated for hazardous locations, 120-277VAC, 80W, 4000k colour temperature, 12000 lumens, 120-degree beam angle, rated for -40 Celsius to 60 Celsius, rated for wet locations
LDPI Cat. No.: LEXFG2-L1-V1-4-V120-1-C-PB

Qn. Drawing E6 shows the removed humidistats being re-installed on the electrical board located outside the clarifiers, does there need to be any humidity monitoring in the clarifier?

The humidistats in the two clarifiers are no longer in use and there is no need for for humidity monitoring in the clarifier. The contractor is still responsible for the complete removal of the humidistats including wiring back to source.

END OF ADDENDUM #3